## Building America Industrialized Housing Partnership (BAIHP)

Annual Report – Fifth Budget Period April 1, 2003 - March 31, 2004

### Produced by the BAIHP Team

Stephen Barkaszi, FSEC
David Beal, FSEC
Subrato Chandra, FSEC
David Chasar, FSEC
Carlos Colon, FSEC
Ken Fonorow, FLHERO
Andrew Gordon, WSU
David Hoak, FSEC
Stephanie Hutchinson, ALACF
Mike Lubliner, WSU

Eric Martin, FSEC
Ross McCluney, FSEC
Mark McGinley, NCA&TSU
Janet McIlvaine, FSEC
Mike McSorley, WSU
Neil Moyer, FSEC
Mike Mullens, UCFIE
Danny Parker, FSEC
John Sherwin, FSEC
Rob Vieira, FSEC

Compiled by Janet McIlvaine, FSEC

University of Central Florida/ Florida Solar Energy Center 12443 Research Parkway, Suite 207 Orlando, Florida 32826

December 31, 2004

PREPARED FOR THE UNITED STATES
DEPARTMENT OF ENERGY
Under Cooperative Agreement
No. DE-FC26GO10478

#### **NOTICE**

This report was prepared as an account of work sponsored by an agency of the United States government. Neither the United States government, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States government or any agencies thereof.

#### TABLE OF CONTENTS

	ACKNOWLEDGEMENTi				
EXE	CCUTIVE SUMMARY	ii			
I.	BAIHP INTRODUCTION	1			
II.	BAIPH TECHNICAL ASSISTANCE	5			
	All America Homes of Gainesville				
	AMJ Construction				
	Applegren Construction, Eastern Dakota Housing Alliance (EDHA	10			
	Atlantic Design and Construction				
	Avis American Homes				
	Bellview Air				
	Cambridge Homes				
	Cardinal Homes				
	Champion Homes				
	City of Gainesville, Cedar Grove II				
	City of Orlando, The Orlando House				
	City of Lubbock Community Development				
	Clayton Homes				
	Dukane Precast				
	Dye Company and Del Air, Southern Living Home				
	Energy Gauge, USA				
	Fleetwood Homes				
	G.W. Robinson Builder/Developer				
	Green Housing				
	Habitat for Humanity–BAIHP Partnership				
	Heat Pipe Technology	36			
	HKW Enterprises (Lewis Place Association, Ltd.; Meadowbrook	2.5			
	Development Inc.; Millpond Development Corp., and Joyner Construction.)				
	Homes of Merit				
	Kit HomeBuilders West				
	Marlette Homes, NOGI Gardens				
	Miami-Dade HOPE VI Project				
	Nez Perce Fish Facility				
	Oakwood Homes				
	Palm Harbor Homes				
	Penn Lyon Homes				
	Podia Construx/Rainbow Springs Construction				
	Sandspur Housing				
	Southern Energy Homes				
	Spain Construction				
	Timeless Construction				
	Tommy Williams Homes				
	Top of the World Retirement Community				
	Top of the world Remember Community	,⊤0			

#### **TABLE OF CONTENTS continued**

II.		PH TECHNICAL ASSISTANCE continued	4.0
		ity Construction Corporation	
		ent Village	
	WCI	Communities, Inc.	50
III.		HP RESEARCH	
	BAI	HP Research Overview	
	<b>A.</b>	Manufactured Housing Research	
		Building Science and Moisture Problems in Manufactured Housing	
		BAIHP Field Visits to Moisture Problem Homes	
		Manufacturers Participating in Building Science Research	62
		Side By Side Study Of Energy Use And Moisture Control Comparing	
		Standard Split System Air Conditioning And A Coleman® Prototype	<i>c</i> 4
		Heat Pump, Bousier City, LA	
		WSU Energy House	
		Zero Energy Manufactured Home (ZEMH)	
		Manufactured Housing Indoor Air Quality Study	
		Manufactured Housing Laboratory – Ventilation Studies	
		Manufactured Housing Energy Use Study, North Carolina A&T	
		Portable Classrooms.	
	D	Duct Testing Data from Manufactured Housing Factory Visits	
	В.	Site Built Housing Research	
		Building America Prototype, Cambridge Homes Unvented Attic Study, Rey Homes	
		Sharpless Construction, Hoak Residence Energy and Moisture Studies	
		Eastern Dakota Housing Alliance (EDHA), Applegren Construction	
		Zero Energy Affordable Housing, ORNL and Loudon County	
		Habitat for Humanity	101
	C.	Field and Laboratory Building Science Research	
	•	Air Handler Air Tightness Study	
		Air Conditioning Condenser Fan Efficiency	
		Fenestration Research	
		Reflective Roofing Research	
		Return Air Pathway Study	
		Heat Pump Water Heater Evaluation	
		NightCool - Building Integrated Cooling System	
IV	BAI	HP WEB PAGE, TRAINING, and PUBLICATIONS	131
		HP Web Page	
		HP Training	
		HP Publications	
$\mathbf{V}$	BAI	HP COLLABORATIONS	152
VI	RAT	HP PROJECT MANAGEMENT	156
, =			

#### **TABLE OF CONTENTS continued**

APPENDIX A	A1
APPENDIX B	B1
APPENDIX C	C1
APPENDIX D	D1
(Note: In electronic copy of report, Appendices A-D are in separate files.)	

#### ACKNOWLEDGMENT

This work is sponsored, in large part, by the US Department of Energy (DOE), Office of Energy Efficiency and Renewable Energy, Building Technologies Program under cooperative agreement number DE-FC26--99GO10478. This support does not constitute an endorsement by DOE of the views expressed in this report. Additional funding was provided by the Florida Department of Community Affairs and the Northwest Energy Efficiency Alliance. Their support is appreciated.

The authors appreciate the encouragement and support from George James, Ed Pollock, and Chris Early, program personnel at DOE, Keith Bennett, project officer in Golden, Colorado and Bill Haslebacher, project officer at the National Energy Technology Laboratory. We also are grateful to our colleagues Philip Fairey, Robin Vieira, and Safvat Kalaghchy for advice and assistance. Thanks to project staff (Bob Abernethy, Mable Flumm, Wanda Dutton, Rafik Alidina, Joy Mayne, and Sue Wichers) and students (Matt Lombardi, Mike McCloud, and Matt McCloud) for their contributions.

This work could not have been completed without the active cooperation of our industry partners and all collaborators. We greatly appreciate their support.



BAIHP researchers and staff in front of the Manufactured Housing Lab at FSEC (Back row from left to right.) Neil Moyer, Subrato Chandra, Mike Mullens, Wanda Dutton, David Beal, Dave Chasar, Rafik Alidina, Ross McCluney. (Front row from left to right.) John Sherwin, Bob Abernethy, Danny Parker, Janet McIlvaine.

#### **EXECUTIVE SUMMARY**

#### **Background and Scope**

This report covers the 5th budget period (April 1, 2003 - March 31, 2004) and includes significant material from the first four budget period final reports September 1, 1999 - March 31, 2003) for a comprehensive account of the Building America Industrialized Housing Partnership (BAIHP) work to date.

The BAIHP team is one of five Building America teams competitively funded by the US Department of Energy, Office of Energy Efficiency and Renewable Energy-Building Technologies program. BAIHP began work on September 1, 1999 with a focus on improving energy efficiency, durability, and indoor air quality of new industrialized housing.

Industrialized housing includes manufactured housing (built to the HUD code), modular housing (factory built housing modules assembled on site), production housing (site built housing produced in a systematic manner). *Figure E-1* shows 2003 U.S. home production by sector.

BAIHP's work during the 5th budget period included:


- Technical Assistance (Section II)
- Field and Laboratory Research (Section III)
- Training and Education (Section IV)
- Collaborations (Section V)
- Program Management (Section VI)

#### **BAIHP Technical Assistance (Section II)**

The BAIHP team provided technical assistance to HUD Code Home manufactures, modular home manufacturers, and site builders including Habitat for Humanity International and its affiliates throughout the nation. Site builders receiving technical assistance are located primarily North and Central Florida.

BAIHP also collaborates with suppliers and non-profit organizations See *Table E-1* for a list of BAIHP Industry Partners.

Systems engineering forms the core of the Building America approach. BAIHP industry partners evaluate the integration of their construction standards and consider improvements that enhance energy






Figure E-1 2003 census data shows 1.8 million housing starts (site built) and placements (manufactured). Sources of Housing Starts Statistics:

Multi Family: <a href="http://www.census.gov/const/startsan.pdf">http://www.census.gov/const/startsan.pdf</a></a>
Site Built, Modular:

http://www.census.gov/const/C25Ann/sftotalconstmethod.pdf
Manufactured Housing Placements:
http://www.census.gov/const/mhs/histplac.pdf

In providing technical assistance BAIHP generally recommends improving equipment efficiency and reducing conditioning loads while taking durability and health issues into consideration. Some examples include:

#### Improving Equipment Efficiency

- High efficiency, correctly sized heating and cooling equipment
- Water heating efficiency
- Duct system design and construction
- Appliances
- Lighting efficiency

#### Reducing Conditioning Loads

- Orientation, shading, and window characteristics
- Surface heat gain (roof finish)
- Thermal, moisture, and air barrier envelope

#### Durability and Health Issues Considered

- Fresh air ventilation
- Moisture control and dehumidification
- Pressure balance and return air flow
- Materials selection
- Maintenance

It is the combination of these improvements that enables the BAIHP industry partners to achieve high performance homes like those documented in *Table E-2*, *Homes Built in Partnership with BAIHP*.

#### BAIHP tracks Industry Partners production in 4 categories:

- <u>Category A</u>: Homes meeting the Building America program goal of saving at least 40% of heating, cooling and water energy use, incorporating fresh air ventilation, and including superior durability and health features. HERS Score results are greater than 88.6.
- <u>Category B</u>: Homes meeting the EPA Energy Star criteria for saving 30% of heating, cooling, and water heating energy use.
- <u>Category C</u>: Homes with energy efficiency improvements falling slightly short of the EPA Energy Star criteria for saving 30% of heating, cooling, and water heating energy use. HERS score of approximately 85. Also homes designed and built to this level or higher but not specifically rated and tested by BAIHP.
- Category D: Manufactured homes built with substantially leak free ducts ( $Qn_{OUT} \le 0.03$ ). This category may include some Category B and C homes.

#### Since inception, BAIHP has assisted home builders and manufacturers to construct:

- 11,767 homes built to Energy Star level or better (*Category A and B, Table E-2*)
- 11,746 homes built 30% to 50% better than the HUD code approx 5% below Energy Star (*Category C, Table E-2*)
- ~46,400 manufactured homes with airtight duct systems (*Category D, Table E-2*)

These homes are estimated to save over \$10 million annually in reduced energy bills for their owners.

Table E-1 BAIHP Industry Partners (Present and Past)					
HUD Code Home Manufacturers					
Cavalier Homes Karsten Company					
CAVCO Industries LLC	Kit Manufacturing				
Champion Homes (Redman)	Liberty Homes				
Champion Homes (Silvercrest)	Marlette Homes				
Clayton Homes	Nashua Homes				
Fleetwood Homes	Oakwood Homes				
Fuqua Homes	Palm Harbor Homes				
Golden West Homes	Skyline Corporation				
Guerdon Enterprises	Southern Energy Homes				
Hi-Tech Homes	Valley Manufactured Housing				
Homebuilders North West	Western Homes				
Homes of Merit					
Modular	Builders				
Avis America Homes	Genesis Homes				
Cardinal Homes	Nationwide Homes				
Epoch Corporation	Penn Lyon Homes				
Excel Homes The Homestore					
General Homes					
Production	Builders				
All America Homes	Dye Company				
American Energy Efficient Homes &	G.W. Robinson Builder				
Investments Inc.	New Generation Homes by Kingon Inc.				
AMJ Construction	On Top of the World				
Arvida Homes	Podia Construx				
Atlantic Design and Construction	Regents Park (Condominiums)				
Beck Builders	Rey Homes				
Cambridge Homes	WCI Communities				
Centex Homes	Winton/Flair Homes				
Affordable Hou					
East Dakota Housing Alliance	Habitat for Humanity International				
City of Gainesville, FL	HKW Enterprises				
City of Lubbock, TX Sandspur Housing (Apartment builder					
City of Orlando, FL	Williamsburg (townhouses)				
Custom I					
All America Homes of Gainesville, Inc.	Pruett Builders, Inc.				
Fallman Design and Construction	Spain Construction				
Marquis Construction & Development, Inc.	Timeless Construction				

Table E-2 Homes Built i	n Partnershi	p with	n BAIH	IP (throu	gh 2/28/04)	
Category / Industry F	Partner		Hon	nes	Dates	
Category A Building		el Hor	mes, H	ERS scor	·es ≥ 88.6	
Homes assisted by Florida H.E.R.	*					
Atlantic Design, GW Robinson, H	IKW Enterpri	ses,	<i>-</i>	- I	O-4 02 E-1- 04	
Spain)			5		Oct 02 - Feb 04	
Fallman Design and Construction			2		09/01 - 08/03	
Sharpless Construction			1		06/02	
WCI			1		08/03	
Applegren Construction (East Dal		)	2		08/03	
Habitat for Humanity, Lakeland, l	FL		1		06/01	
Category A Total			64	1		
Category B (Includes Category			d Beyo	nd, HER	S scores $\geq$ of $\sim$ 86	
Super Good Cents/Natural Choice Cascades)	e (West of the	•	7,8	08	09/99 - 01/04	
Homes by Florida H.E.R.O.			10		~01/00 - 02/04	
Palm Harbor Homes			13		~01/00 - 05/02	
Habitat for Humanity					98 - 07/03	
Homes by D.R. Wastchak in Phoe	niv		265		~01/00 - 10/02	
Marquis Construction	IIIA		2,0		06/03	
Applegren Construction			5		08/03	
Redman Homes			1		12/01	
Cambridge Homes			1		05/03	
Category B Total	LTT NI	-	11,7		07 4 4 1	
Category C Energy Improved			gy Stai	r, HERS	≈85 or not rated	
Super Good Cents Homes (East o and Natural Choice Homes (only			9,8	41	09/99 - 01/04	
Energy Efficient Div. of PHH, in	North Carolin	ıa	1,6	45	09/99 - 02/01	
Habitat Homes (approx.)			26	0	95- 01	
Category C Total			11,7	<b>746</b>		
Category D - Homes with Airtig	ht Ducts thro	ough e	end of 2	2002		
May include B and C homes)	Total	20	000	2001	2002	
Palm Harbor Homes	32,000	11,	,361	11,000	9,639	
Cavalier	1,132	1,	132	0	0	
Southern Energy	12,803	3,0	000	5,600	4,203	
Fleetwood - Auburndale	500				500	
Category D Total	46,435					
	Approximate	Savir	ngs			
Energy Use				nBtu anı	nual	
Energy Cost at \$14/mBtu				739 annu		

#### **BAIHP Research**

BAIHP's ongoing research strives to identify the strategies and technologies that will enable Industry Partners to reach the Department of Energy's 2010 goals for energy savings. By systematically evaluating the savings potential technologies and construction techniques, research provides the home building industry with vital information needed to meet this challenge. BAIHP Research presented here is grouped into three categories: *Manufactured Housing Research*, *Site Built Housing Research*, and *Field and Laboratory Building Science Research*.

#### Manufactured Housing Research

BAIHP has found that using the systems engineering approach to help Industry Partners solve building science related problems develops a strong working relationship and increases the likelihood of the Partner incorporating concepts central to achieving Building America goals such as sealed and tested ducts, right sizing air conditioning, and moisture management. BAIHP's work with the manufactured housing industry illustrates this principal.

BAIHP conducted research for manufactured homes in both field and laboratory which is reported in the following summaries:

- Building Science and Moisture Problems in Manufactured Housing
- BAIHP Field Visits to Moisture Problem Homes
- Manufacturers Participating in Building Science Research
- Side By Side Study Of Energy Use And Moisture Control Comparing Standard Split System Air Conditioning And A Coleman® Prototype Heat Pump, Bossier City, LA
- WSU Energy House
- Zero Energy Manufactured Home (ZEMH)
- Manufactured Housing Indoor Air Quality Study
- Manufactured Housing Laboratory Ventilation Studies
- Manufactured Housing Energy Use Study, North Carolina A&T
- Portable Classrooms
- Duct Testing Data from Manufactured Housing Factory Visits

#### Site Built Housing Research

Industry Partners rise above "business as usual" production to strive toward the Building America program goals of saving 40% of total energy use while improving durability, indoor air quality, and comfort. BAIHP assists the builders, much as described in Section II, Technical Assistance, but goes on to instrument and collect relevant data to validate the approach.

BAIHP conducted research for site built housing which is reported in the following summaries:

- Building America Prototype, Cambridge Homes
- Unvented Attic Study, Rey Homes
- Sharpless Construction, Hoak Residence Energy and Moisture Studies
- Eastern Dakota Housing Alliance (EDHA), Applegren Construction
- Zero Energy Affordable Housing, ORNL and Loudon County Habitat for Humanity
- Apartment Ventilation and Humidity Study, Sandspur Housing

Field and Laboratory Building Science Research

BAIHP builds on a 20 year foundation of basic building science research at the Florida Solar Energy Center. This research generally focuses on issues important in hot-humid climates similar to Florida's but is relevant to our understanding of building science concepts manifest in all climatic regions. BAIHP has conducted field and laboratory building science research in these areas:

- Air Handler Air Tightness Study
- Air Conditioning Condenser Fan Efficiency
- Reflective Roofing Research
- Return Air Pathway Study
- Heat Pump Water Heater Evaluation
- NightCool Building Integrated Cooling System
- Ventilation and Humidity Research, Sandspur Housing

#### **BAIHP Training and Education Summary**

BAIHP research is communicated to public and industry audiences through the BAIHP web page, conference papers and presentations, and various media coverage. Training events are listed in reverse chronological order, divided by budget period.

BAIHP has presented research findings and Building America systems engineering concept to a variety of audiences including architects, builders, HUD Code home manufacturers, and housing decision makers; construction trades and realtors; attendees at building science conferences; portable classroom producers and decision makers; energy raters and green home certifiers, and college students in academic venues.

The BAIHP web page offers access to any interested parties with presentation of case studies, research, and publications.

#### **BAIHP Collaboration**

BAIHP researchers collaborate with a variety of entities in the homebuilding industry and the energy efficiency and research realm including DOE National Labs, Code and Standards Bodies, and Industry/Professional Organizations, Universities, and Product Suppliers.

#### **BAIHP Project Management**

BAIHP project management includes participating in Building America program reviews/meetings and preparing monthly and yearly reports for project activities as well as managing all project tasks (see Sections 1-6) and subcontracts. In the 5<sup>th</sup> Budget Period, BAIHP also held a Project Review Meeting at FSEC in January 2004 to give interested parties an opportunity to give feedback to the project management team.

#### **Project Contact**

Subrato Chandra, BAIHP Project Director Florida Solar Energy Center 1679 Clearlake Road Cocoa, FL 32922 321-638-1412 www.baihp.org www.fsec.ucf.edu subrato@fsec.ucf.edu

### I BAIHP INTRODUCTION

#### **BAIHP INTRODUCTION**

The Building America Industrialized Housing Partnership (BAIHP) team is one of five Building America teams competitively funded by the US Department of Energy, Office of Energy Efficiency and Renewable Energy-Building Technologies program.

#### **BAIHP History**

BAIHP began work on September 1, 1999 with a focus on improving energy efficiency, durability, and indoor air quality of new industrialized housing. DOE funding for the project has been supplemented by cost share funding from the Florida Energy Office (now defunct) of the Florida Department of Environmental Protection, the Northwest Energy Efficiency Alliance (NEEA), Florida Solar Energy Center (FSEC), and many Industry Partners. FSEC, a research institute of the University of Central Florida (UCF), serves as the project prime contractor.

#### Scope of this Report

This report covers the 5th budget period (April 1, 2003 - March 31, 2004) and includes significant material from the first four budget period final reports for a *comprehensive* account of the BAIHP work to date.

#### BAIHP's Goals

- 1. Cost effectively reduce the energy cost of industrialized housing and portable classrooms by up to 50% while enhancing indoor air quality, durability and productivity.
- 2. Assist in the construction of thousands of energy efficient industrialized houses annually.
- 3. Make our partners pleased and proud to be working with us.

#### **BAIHP Research Team**

The Florida Solar Energy Center (FSEC) and the Department of Industrial Engineering of the University of Central Florida (UCF) serve as the prime contractor. Subcontractors during the 5th budget period included the Washington State University Energy Program (WSU), the American Lung Associations of Central Florida (ALACF), and the Florida Home Energy and Resources Organization (Florida H.E.R.O.)

Previously funded subcontractors have included the American Lung Association of Washington, Blue Sky Foundation of North Carolina, D.R. Wastchak, GreenSmart Inc., North Carolina A&T State University, the Oregon Office of Energy, the Idaho Department of Water Resources, and Alten Design.

#### What is Building Science?

Industrialized housing encompasses much of modern American construction including:

- Manufactured Housing factory-built to the nation wide HUD Code
- Modular Housing factory-built, site assembled modules meeting local code
- Production Housing site-built systematically, factory built components

The project scope has also included portable classrooms during 2000-2002.

Of the 1.8 million homes built in the US in 2003 (*Figure 1*), over 7% were factory built to US Housing and Urban Development (HUD) code (U.S. Department of Commerce, 2003(a)(b)

referred to as HUD Code Homes or Manufactured Homes. Manufactured Homes are one of the most affordable types of single-family detached housing available anywhere in the world, generally costing less than \$35/ft2 plus land costs for centrally air conditioned and heated homes with built-in kitchens. Available in all parts of the country, manufactured homes are more popular in rural areas and in the southern and western US where land is still plentiful.

# 2003 Housing Starts and Placements Modular, 2.2% Multi Family, 18.6% Other, 1.8% HUD Code, 7.4%

Figure 1 2003 census data shows 1.8 million housing starts (site built) and placements (manufactured).

Sources of Housing Starts Statistics:

Multi Family:

http://www.census.gov/const/startsan.pdf

Site Built, Modular:

<u>http://www.census.gov/const/C25Ann/sftotalconstmethod.pdf</u>
Manufactured Housing Placements:

http://www.census.gov/const/mhs/histplac.pdf

#### Scope of BAIHP Activities

Within the larger context of the Building America program, BAIHP works to foster achievement of the Department of Energy's goals. BAIHP researchers work in these areas:

- Technical Assistance (Section I)
- Field and Laboratory Research (Section II)
- Training and Education (Section III)
- Collaborations with the Homebuilding and Energy Industries (Section IV)
- Program Management (Section V)

#### **Industry Partnerships**

Many manufacturers, builders, suppliers, and research organizations have joined the Building America Industrialized Housing Partnership. Those receiving Technical Assistance for their projects are described Section II of this report. Those participating in BAIHP Research efforts are described in Section III. Table 1 lists current and past BAIHP Project Industry Partners by housing sector.

#### **Project Contact**

Subrato Chandra, BAIHP Project Director Florida Solar Energy Center 1679 Clearlake Road Cocoa, FL 32922 321-638-1412 www.baihp.org www.fsec.ucf.edu subrato@fsec.ucf.edu

Table 1 BAIHP Industry Partners (Present and Past)					
HUD Code Home	Manufacturers				
Cavalier Homes	Karsten Company				
CAVCO Industries LLC	Kit Manufacturing				
Champion Homes (Redman)	Liberty Homes				
Champion Homes (Silvercrest)	Marlette Homes				
Clayton Homes	Nashua Homes				
Fleetwood Homes	Oakwood Homes				
Fuqua Homes	Palm Harbor Homes				
Golden West Homes	Skyline Corporation				
Guerdon Enterprises	Southern Energy Homes				
Hi-Tech Homes	Valley Manufactured Housing				
Homebuilders North West	Western Homes				
Homes of Merit					
Modular	Builders				
Avis America Homes	Genesis Homes				
Cardinal Homes	Nationwide Homes				
Epoch Corporation	Penn Lyon Homes				
Excel Homes	The Homestore				
General Homes					
Production	ı Builders				
All America Homes	Dye Company				
American Energy Efficient Homes &	G.W. Robinson Builder				
Investments Inc.	New Generation Homes by Kingon Inc.				
AMJ Construction	On Top of the World				
Arvida Homes	Podia Construx				
Atlantic Design and Construction	Regents Park (Condominiums)				
Beck Builders	Rey Homes				
Cambridge Homes	WCI Communities				
Centex Homes	Winton/Flair Homes				
Affordable Ho	using Builders				
East Dakota Housing Alliance	Habitat for Humanity International				
City of Gainesville, FL	HKW Enterprises				
City of Lubbock, TX Sandspur Housing (Apartment builder					
City of Orlando, FL	Williamsburg (townhouses)				
Custom Builders					
All America Homes of Gainesville, Inc.	Pruett Builders, Inc.				
Fallman Design and Construction	Spain Construction				
Marquis Construction & Development, Inc.	Timeless Construction				

# II BAIHP TECHNICAL ASSISTANCE

#### BAIHP TECHNICAL ASSISTANCE

The BAIHP team provided technical assistance to HUD Code Home manufactures, modular home manufacturers, and site builders including Habitat for Humanity International and its affiliates throughout the nation. Site builders receiving technical assistance are located primarily in the hot-humid region of North and Central Florida.

Systems engineering forms the core of the Building America approach. BAIHP Industry Partners evaluate the integration of their construction standards and consider improvements that enhance energy efficiency, durability, indoor air quality, and health of their homes. The Industry Partner decides which improvements to implement.

In providing technical assistance BAIHP generally recommends improving equipment efficiency and reducing conditioning loads while taking durability and health issues into consideration. Some examples include:

#### *Improving Equipment Efficiency*

- High efficiency, correctly sized heating and cooling equipment
- Interior duct systems and unvented attics
- High efficiency water heating, appliances, and lighting.

#### Reducing Conditioning Loads

- Well orientated and shaded windows
- Climate appropriate windows characteristics
- Reflective or absorptive surfaces (roof, wall)
- Continuous thermal, moisture, and air barriers

#### Durability and Indoor Air Quality

- Fresh air ventilation
- Moisture control
- Balanced/controlled air flow
- Reduced long term maintenance needs

It is the combination of these improvements that enables the BAIHP Industry Partners to achieve high performance homes (*Figure 2*) to move the homebuilding industry toward DOE's 2010 goals. *Table 2, Homes Built in Partnership with BAIHP*, shows BAIHP Industry Partner production in 4 categories:

- Category A: Homes meeting the Building America program goal of saving 40% of heating, cooling and water energy use, incorporating fresh air ventilation, and including superior durability and health features. HERS scores are greater than 88.6.
- Category B: Homes meeting the EPA Energy Star criteria for saving 30% of heating, cooling, and water heating energy use.
- Category C: Homes with energy efficiency improvements that fall slightly short of the EPA Energy Star criteria for saving 30% of heating, cooling, and water heating energy use. HERS score of approximately 85. Also homes designed and built to this level or higher that have not been specifically rated and tested by BAIHP.

• Category D: Manufactured homes built with substantially leak free ducts ( $Qn_{OUT} \le 0.03$ ). This category may include some Category B and C homes.

Since inception, BAIHP has assisted home builders and manufacturers to construct:

- 11,767 homes built to Energy Star level or better (*Category A and B, Table 2*)
- 11,746 homes built 30% to 50% better than the HUD code approx 5% below Energy Star (*Category C, Table 2*)
- ~46,400 manufactured homes with airtight duct systems (*Category D, Table 2*)
- Estimated energy savings to homeowners: Over \$10 million annually

Section II describes each BAIHP Industry Partnership, arranged alphabetically. Readers may contact the BAIHP researchers noted in the heading of each summary for further information. Many of these Industry Partners are also featured on the BAIHP website at <a href="https://www.baihp.org">www.baihp.org</a>.



**Figure 2** Building America homes like this one built by BAIHP Industry Partner G.W. Robinson Homes in the Cobblefield community (Gainesville, Florida) reduce energy bills for individual homeowners while pushing the standard of building closer to DOE's 2010 goals.

Table 2 Homes Built in Partnership with BAIHP (through 2/28/04)

Table 2 Homes Built in Partnership with BAIHP (through 2/28/04)  Category / Industry Partner Homes Dates							
Category / Industry Partner				······	vates		
Category A Building America Level Homes, HERS scores ≥ 88.6							
Homes assisted by Florida H.E.R.	`		_	_			
Design, GW Robinson, HKW Ent	erprises, Spai	<u>n)</u>	5		Oct 02 - Feb 04		
Fallman Design and Construction			2	2	09/01 - 08/03		
Sharpless Construction			]		06/02		
WCI			]		08/03		
Applegren Construction (East Dak	ota Housing)			2	08/03		
Habitat for Humanity, Lakeland, F	FL		1		06/01		
Category A Total			6	4			
Category B (Includes Category	A) Energy St	ar an	d Beyo	ond, HEF	RS scores $\geq$ of $\approx$ 86		
Super Good Cents/Natural Choice	(West of the	•					
Cascades)			7,8		09/99 - 01/04		
Homes by FL HERO			10	15	~01/00 - 02/04		
Palm Harbor Homes			1	3	~01/00 - 05/02		
Habitat for Humanity			26	55	98 - 07/03		
Homes by D.R.Wastchak in Phoen	nix		2,6	58	~01/00 - 10/02		
Marquis Construction			1		06/03		
Applegren Construction			5		08/03		
Redman Homes			1		12/01		
Cambridge Homes			]		05/03		
Category B Total			11,	767			
Category C Energy Improved	Homes, Not	Ener	gy Sta	r, HERS	$\approx$ 85 or not rated		
Super Good Cents Homes (East of	f the Cascades	s)					
and Natural Choice Homes (only t	hrough 11/30	<u>/01)</u>	9,8	341	09/99 - 01/04		
Energy Efficient Div. of PHH, in 1	North Carolin	ıa	1,645		09/99 - 02/01		
Habitat Homes (approx.)			26	50	95- 01		
Category C Total			11,746				
Category D - Homes with Airtig	ht Ducts thro	ough (	i		ay include some		
Category B and C homes		Ü					
	Total	<b></b>	000	2001	2002		
Palm Harbor Homes	32,000	11,	361	11,000	9,639		
Cavalier	1,132	1,	132	0	0		
Southern Energy	12,803	3,0	000	5,600	4,203		
Fleetwood - Auburndale	le 500				- 500		
Category D Total	46,435						
	Approximate	Savii	1gs				
Energy Use		7	18,124	mBtu an	nual		
Energy Cost at \$14/mBtu		\$1	10,053.	739 annı	ıally		

#### All America Homes of Gainesville

Gainesville, Florida Category A, 2 Homes

Awards: 2003 Energy Value Housing Award, Silver

Medal, Custom Home/Hot Climate

2002 South East Builder's Conference, Grand Aurora Award for Solar Energy

All America Homes has been in business for 17 years and builds 10 homes each year in the Gainesville (FL) area. After providing design assistance for the award wining 2002 home (*Figure 3*) during the 4<sup>th</sup> budget period, BAIHP provided additional assistance to All America for a second home with solar and energy efficiency concepts during the 5<sup>th</sup> budget period. The home was built with a photovoltaics



Figure 3 All America Homes of Gainesville, 2003 Energy Value Housing Award, Silver Medal, Custom Home/Hot Climate.

(PV) system, and achieved a HERS rating of 90.6. This home serves as a model for the hothumid climate using a combination of on-site power generation and energy efficiency to reach near-zero utility demand, similar to the home built in 2002 (*Table 3*).

It incorporates energy efficient air conditioning, hydronic solar water heating, excellent air distribution design and construction (pressure tested for validation) and right sizing of the heating and cooling capacity. It also incorporates envelope improvements in the roof, ceiling, walls, windows and infiltration control. A passive fresh sir ventilation system provides filtered outside air to the return side of the mechanical system during operation. See *Appendix C*, *Florida H.E.R.O. Standard Technical Specifications*.

Table 3 All America Homes of Gainesville (FL) Specifications

Component	2002 Home	2003 Home
Conditioned Area	3644 sq ft	2884 sq ft
Hers Score	90.6	90.6
Utility Cost	\$150 for summer (including water,	Average summer energy use
	sewer, and trash pickup) (Source:	= 58kw/day (Source:
	Homeowner records.)	Gainesville Regional Util.)
Solar: PV Array	2.5 kW	1.8 kW
Solar: Water Heating	Integrated storage solar collector	Integrated storage solar
	(4' x 8' ) EF≈2.4	collector (4' x 8' ) EF ≈4.7
Solar: Water Heating	Solar pool heater	N/A - no pool
Solar: Attic Ventilation	PV powered attic fan	N/A – Unvented attic
Solar: Outdoor Lighting	PV (low-voltage) patio lighting.	N/A – No pool.
Heating	Hydronic coil with solar heated	Hydronic coil with solar
	water and gas backup	heated water and
		instantaneous gas backup
Cooling	SEER 14 AC	Dual compressor SEER 17
	Variable speed AHU fan	Variable speed AHU fan
	Maintains indoor RH =< 60%	Maintains indoor RH =< 60%
Ducts	Interior Duct System	Interior Duct System in
	Fur down construction	Unvented Attic
Duct Leakage	CFM25 <sub>OUT</sub> < 5% of AHU flow	CFM25 <sub>OUT</sub> <5% of AHU flow

Table 3 All America Homes of Gainesville (FL) Specifications

Roof/Ceiling Assembly	Radiant barrier roof decking R-30 dense pack cellulose (ceiling)	R-20 Icynene at roof decking unvented attic
Wall Assembly	R-13 Dense pack cellulose	R-15 Blown in batt fiberglass
Windows	Reduced window area	
Glazing & Frame	Double pane, vinyl frame	Same
Window Radiant Gain	Large overhangs (high windows	Low-E glazing for unshaded
	located beneath the roof overhangs	east and west windows
	to provide daylighting without	
	contributing to solar heat gain)	
Lighting	85% fluorescent.	95% fluorescent
Infiltration	Natural ACH < 0.1	Est. natural ach =0.059
Ventilation	Filtered passive fresh air inlet on	Same
	the return side of AHU	

#### **AMJ Construction**

Gainesville, Florida

Category A, 54 Town homes (pending)

Florida Home Energy Rating Organization (Florida H.E.R.O.) provided an engineered duct system for 26 models in the Regents Park Townhouse development. This downtown urban infill project will result in 54 units with Building America features including ductwork in the conditioned space, outside air ventilation, and combo hydronic heat and 13 SEER cooling.

#### Applegren Construction, Eastern Dakota Housing Alliance (EDHA)

Grand Forks, North Dakota

Category A, 2 Homes

Category B, 5 Homes

Awards: North Dakota Housing Finance Agency's Champion of Affordable Housing

**Production Award** 

Papers: Cold Climate Case Study: High Efficiency North Dakota Twin Homes

EDHA set a goal of achieving up to 50% energy savings over the 1993 Model Energy Code with superior indoor air quality (AIQ). Phase I (March 2003) and Phase II (Feb 2004) each included two twin homes (duplexes) for a total of eight homes.

The two story dwellings (Figure 4) include an insulated basement with air circulation to the main house, suitable for conversion to living space. Features of the Phase I and Phase II homes are summarized in Table 5 which also shows a theoretical base case house using local conventional construction and code minimums modeled in DOE2 to determine energy savings and cost effectiveness. Estimated combined gas and electric utility savings ranged from 25% on Phase I homes to 35% on Phase II homes over



Figure 4 Selkirk Twin Homes, Grand Forks, ND.

the base case. The homes also met the BA goal of 40% savings compared to the Benchmark house.

#### Annual Energy Use

A performance comparison of the base case and improved structures is shown in *Table 5*. The DOE2 model predicts the need for very little cooling, however many new homes in this area, including these, are being built with central air conditioning.

#### Moisture Issues

Phase II of construction added a layer of R-10 rigid extruded polystyrene (XPS) to the exterior side of the wall assembly. The low water vapor permeance of rigid XPS foam sheathing (1.1 perms) presents a dilemma in this climate where an interior vapor barrier (usually 6-mil polyethylene) is considered mandatory to minimize moisture diffusion from the conditioned space into the wall cavity. The installation of two vapor barriers leaves the wall vulnerable to moisture accumulation should water unintentionally enters the cavity. One BAIHP recommendation calls for removing the interior vapor barrier and relying on two coats of latex paint on the interior to limit diffusion from the conditioned space into the wall. This option allows the wall to dry to some extent in both directions, but was not chosen by the builder.

#### Ventilation

A heat recovery ventilator (HRV) mounted in the basement provides controlled mechanical ventilation with an energy penalty estimated at \$45/year. The unit contains an 80-watt fan that introduces 75 CFM of outside air while exhausting a similar amount at a heat transfer efficiency of 70%. The HRV can operate either continuously or on an intermittent 20 minutes on, 40 minutes off cycle. Intermittent operation was simulated to meet the old guideline. Attempting to meet the new ASHRAE 62.2 standard (ASHRAE 1999) would require 42 CFM of continuous ventilation. For these simulations however, the old ASHRAE guideline of 0.35ACH was used, calling for a continuous rate of 25 CFM.

**Table 5 Applegren Twin Home Specifications** 

Component	Base Case	Phase I (March 2003)	Phase II (Feb 2004)
Conditioned Area Of Each Dwelling	1840 sq. ft. (w/basement)	Same	Same
Hers Score	85.2	89.7	92.2
Estimated Annual Energy Cost	\$1179	\$815	\$701
% Cost Savings Compared to Base		25%	35%
Heating Cost	\$458	\$366	\$294
Cooling Cost	\$15	\$11	\$10
Hot Water Cost	\$245	\$157	\$116
H/C/WH Total Cost	\$718	\$534	\$420
Envelope			
Above-Grade Wall Structure	2x6 wood frame	Same	2x4 wood frame
Above-Grade Wall Insulation	R-19 fiberglass batt	Same	R-15 blown fiberglass
Above-Grade Wall Sheathing	Plywood	Same	R10 XPS foam corners: R7.5+plywood
Basement Walls	R-11	Same	Same

**Table 5 Applegren Twin Home Specifications** 

Vented Attic	R-49	Same	Same	
Windows	Double pane, Low-E, Argon-filled, vinyl slider frame U=0.34, SHGC=0.33	Casement (instead of slider)	Same as Phase I	
Infiltration (ACH50) (Including Basement)	5 (assumed)	2.8 (average of 4 units)	2.4 (average of 4 units)	
Equipment				
Gas Furnace	60kBtu, AFUE=78	60kbtu, AFUE=92 w/sealed combustion	60kBtu, AFUE=92	
Gas Furnace Capacity	29.8kBtu/h	33.4kBtu/h	30.7kBtu/h	
Air Conditioner	1.5 ton, 10 SEER	Same	Same	
Air Conditioner Capacity	9.9kBtu/h	10.6kBtu/h	10.3kBtu/h	
Thermostat	Standard	Programmable	Same as Phase I	
Ventilation	None	70% efficient HRV	Same as Phase I	
Water Heater	40gallon, EF=0.88 Electric	40 gallon, EF=0.62 Natural gas with power vent	Tankless, EF=0.83 Natural gas	
Lighting	10% fluorescent	85% fluorescent (linear and CFL) Note: only bathroom and dimmable fixtures were incandescent	Same as phase I	
Appliances	Standard	Energy Star dishwasher Horizontal-axis washer Energy Star refrigerator	Same as Phase I	

#### Cost Analysis

Tables 6 (Phase I) and 7 (Phase 2) show the cumulative effect of *All Measures* in comparison to the base case home. The heat recovery ventilator (HRV) is also shown separate from the other measures because the HRV is an essential IAQ feature, yet it increases energy use by \$45/year. With the exception of the HRV all measures show a positive cash flow on a 6%, 30 year fixed rate mortgage beginning in the first year.

TABLE 6 Economic Assessment of Phase I Measures\*\*\*\*

Energy Measure	Annual	Installed	Simple	First Year
	Savings	Cost	Payback	Cash Flow
Reduce infiltration to 2.8 ACH50	\$90	\$325	3.6	\$68
Upgrade to 92% direct vent furnace	\$52	\$600	11.5	\$11
Switch to Programmable Thermostat	\$23	\$130	5.7	\$11
Upgrade to Energy Star appliances*	\$61	\$730	12	\$12
Change to EF=0.62 power vented water heater	\$52	\$520	10	\$16
Increase from 10% to 85% fluorescent lighting	\$31	\$200	6.5	\$17
All Measures	\$309	\$2,505	8.1	\$135
Heat recovery ventilation @75cfm, 33% RTF	(\$45)	\$1,400	N/A	(\$134)
All Measures with HRV	\$264	\$3,905	14.8	\$1

<sup>\*</sup> Energy Star appliances include refrigerator, dishwasher and h-axis clothes washer.

<sup>\*\*</sup> First year cash flow based on 30 year fixed rate mortgage with interest rate of 6%, down payment of 5%, and discount rate of 5%. A general inflation rate of 3% per year was applied to the upgrade cost of measures replaced at end of lifetime. Final value of equipment is determined by linear depreciation over lifetime. Interest paid on mortgage is considered tax deductible using a tax rate of 28%. Energy costs escalate at 3% per year. A property tax rate of 0.8% was applied to the energy upgrade cost and is inflated at 3% per year.

The higher savings of Phase II over Phase I arise from two energy saving measures unusual for this region: XPS foam sheathing with 2x4 framing and tankless gas water heating. Simple paybacks for these measures were 8.3 and 13.3 years respectively. Electric water heaters are the current norm in the Grand Forks area, but with electricity 26% below the national average and natural gas prices on the rise, simple payback on the tankless model was relatively long. In addition, fluctuating natural gas prices complicate the economic analysis. Initial concerns of how the tankless water heater would perform in this extreme climate were met with positive feedback through the first winter, which was colder than normal including an all-time record low of -44°F set at the Grand Forks International Airport on January 30, 2004.

TABLE 7 - Economic Assessment of Phase II Measures Error! Bookmark not defined. Error! Bookmark not defined.

Energy Measure	Annual Savings	Installed Cost	Simple Payback	First Year Cash Flow
Upgrade walls to (R10 sheath + R15 FG batt)	\$72	\$600	8.3	\$31
Reduce infiltration to 2.4 ACH50	\$106	\$325	3.1	\$82
Upgrade to 92% direct vent furnace	\$40	\$600	15.0	-\$1
Switch to Programmable Thermostat	\$18	\$130	7.2	\$6
Upgrade to Energy Star appliances*	\$60	\$730	12.2	\$12
Change to EF=0.83 tankless gas water heater	\$94	\$1,250	13.3	\$10
Increase from 10% to 85% fluorescent lighting	\$31	\$200	6.5	\$18
All Measures	\$421	\$3,835	9.1	\$158
Heat recovery ventilation @75cfm, 33% RTF	(\$43)	\$1,400	N/A	(\$134)
All Measures with HRV	\$378	\$5,235	13.8	\$24

Four more dwellings (two duplexes) are slated for completion in the summer of 2004. See also *Cold Climate Case Study: High Efficiency North Dakota Twin Homes* on <a href="https://www.baihp.org.">www.baihp.org.</a>

#### **Atlantic Design and Construction**

Gainesville, Florida

Category A

Awards: 2001 EPA Energy Star Builder of the Year

Atlantic Design & Construction (AD&C) is a production builder located in Gainesville, Florida, who builds about 50 homes a year. Though initially producing homes better than the Florida Energy Code minimum, Florida HERO worked with AD&C to increase their efficiency to Energy Star and then to Building America standards. (Table 8). The new upgrades resulted in homes achieving an average HERS score of 89.



Figure 5 Atlantic Design and Construction home in the Mentone neighborhood.

Savings from the increased the cooling system efficiency more than offset the additional \$250 to \$375 needed for improved duct sealing and insulation and air sealing protocol adjustments. This savings, while sufficient to offset those costs, were not enough to pay for all implemented measures. Instead, increasing the price of the home by \$1,250 was sufficient to cover the additional costs and derive an excellent profit margin. Despite adding \$1,250 to \$2,500 to home buyer costs up-front, AD&C's award-winning development, Mentone, has been the best-selling subdivision in Alachua County for four years running (*Figure 5*).

Kenny Brekenridge, AD&C Project Manager, says that the company believes with energy costs continuing to rise that it makes sense to build energy efficient, and that they emphasize the Building America improvements in their sales literature and discussions.

**Table 8 Atlantic Design and Construction Specifications** 

Component	Original	Mentone
Conditioned Area	1800-2400 sq. ft	1800-2400 sq. ft
Hers Score	~82	~89
Selling Price	~\$90,000	\$190,000 - \$325,000
Cooling	SEER 10 with standard thermostat	System sized using Manual J, SEER 13 with passive, filtered ventilation air and programmable thermostat
Ducts	Local conventional construction	System engineered using manual d, mastic sealed, and performance tested to have cfm25out < 5% of AHU flow
Ceiling Insulation	R-30 fiberglass	R-30 cellulose
Wall Assembly	R-11 fiberglass	R-13 cellulose
Windows	Double pane clear metal frame	Double pane Low-E
Lighting	Standard	Air lock can lights

#### **Avis American Homes**

Avis, Pennsylvania

In the summer of 2003, Avis
American Homes tested an alpha
prototype Status and Control
System (STACS) developed by the
UCF Constructability Lab
researchers (BAIHP Partner). The
system is a real-time shop floor
labor data collection and reporting
system. Production workers use
wireless laser scanners to report
their current work assignment.
STACS reporting is web based and
provides both real time
manufacturing status and summaries




Figure 6 STACS system components and relationships.

of historical production performance (*Figure 6*). While labor represents a relatively modest fraction of production cost, typically 10-15%, it has a profound impact on operations, including product quality, cycle time, material waste, and labor productivity.

Avis American employees tested STACS in drywall finishing operations. Test results demonstrated that production workers could operate the system effectively and that the system accurately captured scanned activity.

See also *Penn Lyon Homes* (Technical Assistance section) and *Status and Control System* (*STACS*) (Research Section III).

#### **Bellview Air**

Gainesville, Florida

Florida H.E.R.O. discussed a range of issues with Bellview Air, including the impact of input data on Manual J equipment sizing and the air handler location in an effort to improve indoor air quality, comfort, and energy performance. The potential benefits of unvented cathedralized roof systems were also addressed. Construction anticipated in 2005.

#### **Cambridge Homes**

Orlando, Florida Category B, 1 Home

This BAIHP partnership resulted in monitored field research in the Augusta Building America model (*Figure 7*) and a control home. See BAIHP Research (Section III), Site Built Housing Research, Cambridge Homes.



Figure 7 The Augusta, Cambridge Homes BA Prototype.

#### Cardinal Homes, Inc.

During the 4<sup>th</sup> budget period in cooperation with the University of Central Florida Industrial Engineering Department (UCFIE), FSEC researchers tested four Cardinal modular homes with the Cardinal sales manager and plant quality engineer. Initial results found that peak loads for heating were almost double that for cooling. All four of the homes had leaky ducts. These leaks accounted for the largest peak load in the homes, averaging 28% of the winter peak and 21% of the summer peak.

#### **Champion Homes**

*Washington (state)* 

Champion Homes built the first stress skin insulated panel (SIP) manufactured home now sited in western Washington. The house air tightness was measured at ACH50=3.55, well below the average numbers for all homes previously tested in the WSU random home study (see Northwest Energy Efficient Manufactured Homes). Energy savings are estimated at 50% greater than a home constructed to the HUD Code. These results were presented at the 2003 ASHRAE Summer Meeting, authored by Pacific Northwest National Laboratory (PNNL), with contributions from BAIHP staff.

#### City of Gainesville, Cedar Grove II

Gainesville, Florida Category B, 139 Homes

Award: HUD award for Innovation in

Housing in 2004

Florida H.E.R.O. began working with the City of Gainesville before the ground-breaking in the Cedar Grove II subdivision of HUD housing. Project manager Judy Raymond envisioned a new urban style development (HUD's first) with single family homes



Figure 8 City of Gainesville house in Cedar Grove II.

featuring high quality construction and individualized character with front porches and front façade details (*Figure 8*). She worked with Florida H.E.R.O. to develop engineered plans for mechanical and air distribution systems and a whole house package that was recognized with a HUD award in 2004. *Table 9* summarizes the specifications.

Table 9 City of Gainesville, Cedar Grove II Subdivision, HUD Home

Component	Specification	
Conditioned Area	~1200-1400 (139 units)	
HERS Rating	86-88 (goal = 86)	
Cooling And Heating	SEER 12 with hydronic heating; some 80% AFUE furnaces	
	with programmable thermostat.	
Duct System	Ducts in conditioned space. Ducts moved to attic in later	
	phase. Return duct and air handler still conditioned space.	
	Duct system engineered using Manual D, sealed with mastic,	
	all homes performance tested for duct air tightness.	
	CFM25 <sub>out</sub> ≈25	
System Capacity	Cooling and heating systems sized using Manual J calculation	
	procedure	
Walls	R-13 cellulose	
Ceiling	R-30 cellulose insulation with radiant barrier	
Windows	Double pane metal frame	

#### City of Orlando, The Orlando House

Orlando, Florida Category A, 1 House

The City of Orlando, through the office of Housing and Community Development in the Planning and Development Department, constructed an environmentally friendly demonstration home called *The Orlando House: Florida's Future*, on an infill site within the city (*Figure 9*). The City requested FSEC assistance to assure the home met Building America goals and the Florida Green Home Designation Standards. Ground broke on the



Figure 9 The Orlando House.

demonstration home in December 2001 and the home was open to the public for community education purposes for approximately one year. Specifications are listed in *Table 10*.

The City acquired more than \$100,000 in donated materials and services for the project, and completed much of the construction using their own staff. Along with public education, a primary purpose for this project was to give the city staff first hand experience in the use of green building materials and techniques - especially those relating to energy efficiency, indoor air quality, durability, disaster mitigation, and termite resistance. That experience would allow the products and techniques to be effectively used in future low-income housing constructed by the city.

One particular focus of this project was disaster resistance. For protection from wind storms, a durable steel structure was used along with a safe room located in the detached garage. For termite resistance, all structural and exterior finish materials were selected on the basis of providing the least amount of available food source. Materials such as borate treated lumber and sheathing, steel structural components, and plastic/composite finishes were used extensively in conjunction with a Termi-mesh barrier system.

FSEC certified the house for the Florida Green Home Designation Standard in February 2003. FSEC staff also presented information regarding Florida Green Home Designation as part of a builder training event held at the Orlando House. Two CEUs were available to attendees, and approx. 30 people attended from the central Florida area. Training also included talks on Zero Energy Homes, Florida Sun Built Program, and a "builder panel" that included 3 BAIHP partner builders.

The demonstration home was sold in May 2003, and money acquired from the sale will go directly towards the construction of low income housing that utilizes several green building techniques.

**Table 10 City of Orlando – Orlando House** 

Component	Specifications		
Conditioned Area	2148 sq. ft.		
HERS Score	88.3		
Envelope			
Above-grade Wall Structure	Steel Frame 1 <sup>st</sup> and 2 <sup>nd</sup> floors		
Above-grade Wall Insulation	R-19 Icynene		
Exterior Wall and Roof Sheathing	OSB - Borate treated		
Attic	Unvented R-19 Icynene		
Roof	Metal		
Windows	Double pane Low-E		
Equipment			
Heating & Cooling	13 SEER heat pump		
Thermostat	Programmable		
Ventilation	Passive outside air vent		
Water Heater	50 gal, EF=0.88 (Electric)		

Table 10 City of Orlando – Orlando House

Component	Specifications	
Lighting	100% fluorescent	
Appliances	Energy Star	
Additional Green Features:		
<ul><li>Termi-mesh</li></ul>	<ul> <li>Durable exterior finishes</li> </ul>	
■ Safe Room	<ul><li>Ultra-low-flow water fixtures</li></ul>	
<ul> <li>VOC source control</li> </ul>	<ul> <li>Low water using landscape</li> </ul>	
<ul> <li>Resource efficient interior finishes</li> </ul>	<ul> <li>Pervious driveway/walkway</li> </ul>	

#### **City of Lubbock Community Development**

Lubbock, Texas

Through the Portland Cement Association (PCA), contact was established with the City of Lubbock who is building low income houses with insulated concrete form (ICF) systems (Figure 10). FSEC researchers visited Lubbock twice to conduct diagnostic tests and provide training and technical assistance. FSEC also conducted initial HERS ratings on four Lubbock Habitat for Humanity (see Habitat for Humanity, Texas) homes plans and introduced the Habitat



Figure 10 Low income housing built by the City of Lubbock using insulated concrete forms.

affiliate to the City of Lubbock's other low-income housing activities.

#### **Clayton Homes**

Waycross, Georgia

FSEC personnel conducted a plant visit of the Clayton Homes factory in Waycross, Georgia in June 2002. A singlewide home was tested and observations recorded of home and duct construction techniques. Findings and remedies for leaky ducts found during the visit were reported to factory representatives in a follow-up trip report (see *Appendix A*).

#### **Dukane Precast**

Naperville, Illinois

FSEC made a February 2002 site visit to Dukane Precast in Naperville, Illinois and provided technical design assistance in a follow-up telephone conference call in March '02.



Figure 11 Completed Dukane Precast home tested by BAIHP

In 2003, Dukane Precast requested

BAIHP assistance in the design phase and monitoring of the first prototype of a new line of homes called "The Fortified House (*Figure 11*). Objectives of Dukane's Fortified House include energy efficiency, comfort, durability, and good indoor environment conditions.

In December 2003, FSEC visited 3 prototype buildings in various stages of construction in. One was complete. Researchers made recommendations regarding window flashing, below grade drainage and waterproofing, interior ducts, air sealing, attic access detail, floor finishes with radiant heating, radiant heat zoning, ventilation system design and operation.

In February, FSEC returned to Dukane for testing and infrared evaluation of 3 completed prototype Fortified Homes built by Dukane's sister company, Mustang Construction at Keller Court, Boilingbrook, IL, just west of Chicago.

Infrared images were recorded from the inside and outside during a calm morning with ambient air temperature of about 25° F and interior temperatures of about 70° F, and whole house air tightness was assessed with a blower door test. Whole house infiltration was ACH50=1.28 (very low) 11 Keller Court data (*Specifications*, *Table 11*) was obtained with a multipoint blower door test. IR scans found no major infiltration pathways.

The ceiling and gable end of the vaulted living room were built with wood frame construction instead of precast concrete. Both showed higher heat loss than was generally found in the precast panels. Flaws in the continuity of ceiling insulation over the vaulted ceiling were visible from the vented attic. especially around can lights. The flat ceilings in this home were insulated with R-38 rigid polyisocyanurate loosely laid on the concrete ceiling panels. Dukane has now switched to an R-23 precast panel for ceilings.

Table 11 Dukane Precast's Fortified Home Specifications

Component	Dukane Home	
Conditioned area	5100 (with basement)	
HERS score	NA	
Envelope		
Floors and Ceiling	Precast concrete panels	
Walls	R-23 (~3") Polyisocyanurate between precast concrete	
Attic	Vented with R-38 Polyisocyanurate and Batt	
Windows	Insulated glass, vinyl frame, u-value=0.36,	
Willdows	SHGC=0.45	
Infiltration	Ach50=1.28	
Equipment		
Heating	Radiant floor	
Boiler	140kBtu, 50 gallon AFUE=92 Gas Boiler	
Cooling	3 ton, 10 SEER, Unico-type	
Ducts	High velocity, small ducts, unconditioned space	
Thermostat	Programmable	
Ventilation	Honeywell 150cfm HRV	
Water Heating	From Boiler	

#### **Opportunities for Improvement**

Infrared scans were performed on the ranch home and two other homes nearing completion on Keller Court. All three had the space heating system in operation holding the interior near 70 F. Initial scans of the exterior clearly showed increased heat conduction at the truss locations in the precast panels (*Figure 12*). The metal truss members are cast into the assembly to connect the interior and exterior panels and allow for approximately 3 inches of polyisocyanurate foam (R-23). Exterior infrared scans showed a 2 - 4° F temperature rise at truss locations; exterior temperatures were between 12° and 24°F.




Figure 12 IR-scan showing metal trusses in precast walls. Temperature at the crosshairs is 20.2 °F. Overlaid temperature graph shows temperature variation of the surfaces at the white line running horizontally through the crosshairs.

Increased heat loss was also visible at the top the crosshairs. and bottom of precast sections where field connections are made during construction and filled with grout. Each panel has at least two lifting fasteners imbedded in the top edge for the crane to connect to during home construction. Foam insulation around these fasteners is sometimes removed to connect the lifting hook and the void is re-insulated in the field. Insulation levels are reduced where precast walls are connected to floors and ceilings. These areas have one inch of rigid XPS foam (R-5) next to the outer panel but are otherwise left open until structural and electrical conduit connections are made in the field after which they are filled with grout.

#### **Interior Ducts and Moisture Issues**

FSEC Researchers met with Dukane Precast staff, their architect and mechanical contractor to identify a way to incorporate interior ducts into a new model of the *Fortified House*. Ducts are used primarily for cooling and ventilation as all Dukane Precast homes are designed with in-floor radiant heat driven by a high efficiency (92 AFUE) boiler. The boiler also provides domestic hot water in conjunction with a 50-gallon storage tank.

The main obstacle to building interior ducts was finding a place to run ducts from the basement mechanical room to the first and second floors. Agreement was made to run supply risers near the center of the home and returns in a chase on an outside. The two-story foyer offers the best placement for a central return for both the first and second floor supplies.

Dukane is currently using a high velocity, small duct air conditioning system by Unico with 2-inch diameter supply branches that are easier to fit into walls and chases than low velocity ducts. One unoccupied home had problems with condensation accumulating on the attic-mounted ducts. The cause was traced to humid indoor air contacting cold metal trunk lines in the vented attic.

No occupant-related moisture was present but the precast panels, which are still in the process of drying, are one possible source. Periodic mixing of the indoor air may be all that is required until moisture output from the panel is reduced. Otherwise, introducing dry air was recommended to prevent condensation. Findings and recommendations were sent of the Dukane Precast in a Trip Report.

#### Dye Company and DelAir - Southern Living Home

Category A, 1 Home Category B, 1 Home

Florida H.E.R.O. met with Dye Company president and his staff to discuss the new Southern Living Home planned for showcase at the 2003 Southeast Building Conference (SEBC) in Orlando, Florida. This firm has a strong desire to differentiate their homes by emphasizing healthy and energy efficient homes. Florida HERO introduced the Building America systems engineering approach to the builder and subsequent discussions resulted in Dye's commitment to partner with Building America in this project. As a result, researcher met with DelAir mechanical contracting to discuss the development of mechanical specifications for the Southern Living project.

This home did have a Honeywell ERV added and had a HERS score of 88.5. While this home did not meet the BA standard of performance for the 2003 SEBC show, retrofits are being completed with the anticipation that it will be a BA home.

The 2004 home achieved a HERS of 89.6. Both homes have unvented attics with ducts in conditioned space, and used heat pumps with SEERs ranging from 13.5 - 14.1. Windows in the 2004 home have a SHGC of .29 and gas (LP) instant hot water heaters were used.

#### EnergyGauge® USA

FSEC - Cocoa, Florida

This software uses the hourly DOE 2.1E engine with FSEC enhancements and a FSEC-designed user friendly front end to calculate home energy ratings and energy performance. (*Figure 13*) Researchers continue to improve the software's features and accuracy. Version 2.0 incorporates many enhancements, which may include multiple zones, multi-fuel use, and a detailed solar thermal and solar electric system analysis. For more information, please visit www.energygauge.com.

#### **Fleetwood Homes**

Category D, 500 Homes Auburndale, Florida factory




Figure 13 Window input screen from EnergyGauge USA home energy rating and simulation software.

In 2002, researchers visited four Fleetwood factories in southern Georgia to investigate the cause of moisture-related building failures when units were installed in a hot-humid climate. The factories are located in Douglas, Alma, Pearson, and Willacootche. As a result of FSEC recommendations, the factories have changed their duct construction practices and are now constructing airtight ducts with mastic.

Six Fleetwood homes, all in Florida, were tested for moisture and mold damage from April 2002

through March 2003. All of the homes had damaged flooring due in part to a lack of ground cover and poor crawlspace ventilation. Damage to the floor in one home was exacerbated by a plumbing leak. Only one home had moisture damage to the wallboard material, and this home showed a history of thermostat settings below 72° F. A report for each home was submitted to Fleetwood for corrective measures. One additional high bill complaint in Cobb, Georgia was investigated during that period. Between April 2003 and March 2004 eight Fleetwood moisture damaged homes were investigated by BAIHP, seven in Florida and one in Texas.

In May 2003, FSEC researchers were asked by Fleetwood and Coleman to travel to Fleetwood's five southeastern plants and test three homes built by each factory to get their plants certified for building ENERGYSTAR Homes. A sample of the data collected is shown in Table 12.

At the Auburndale, FL plant, BAIHP researchers conducted the tests in houses set up in the factory's parking lot. The houses did not have air handlers, but total duct leakage was within range to achieve Fleetwood's goal for this plant which was to build houses according to the EPA EnergyStar Building Option Packages (BOPs) for manufactured housing, Climate Zone 4, and to attain a less than 5% duct leakage rate (Qn,total < 5%). The houses showed some need for additional envelope sealing which was implemented after the first house was tested. The other two houses showed marked improvement in whole house air tightness. Recommendations and test results were provided to Fleetwood via email (no formal trip report). Similar testing was conducted at the Georgia Fleetwood factories in Willacoochee, Pearson, Douglas, and Alma.

Table 12 Test Results, Factory Certification at Fleetwood's Auburndale facility

House #	Size	ACH50	Estimated natural ach (ACH50/18)	Qn <sub>total</sub> (CFM25 <sub>total/cond. area</sub> )
1	24 X 48	8.7	0.48	0.031
2	28 X 52	5.5	0.31	0.034
3	28 X 52	5.5	0.31	0.029

#### G.W. Robinson Builder/Developer Gainesville, Florida Category A, 143 Homes

This builder, a leading member of the BAIHP program, takes care to incorporate features and measures that enhance not only the energy and resource efficiency, but also the indoor air quality, safety, durability, and comfort, consistent with the spirit of Building America.



Figure 14 G.W. Robinson home in Cobblefield neighborhood.

#### **Cobblefield Development**

G.W. Robinson committed to building the first "green homes" community, as designated by the Florida Green Building Coalition (FGBC), and to achieving Building America standards in each home built (*Table 13*). Individual home performance testing by Florida H.E.R.O. ensures that the homes meet both program specifications. G.W. Robinson proudly refers to these programs in weekly newspaper ads. (*Figure 14*)

Table 13 G. W. Robinson Specifications

Component	Original	Cobblefield
Conditioned Area	1,812 - 3,128	1,812 - 4,107
Hers Score	~82	~89
Cooling and Heating	SEER 10 air conditioner and AFUE=80% gas furnace with standard thermostat	System sized using Manual J SEER 12, 13, and 14 (depending on construction date, higher seers more recent) and AFUE=90% gas furnace with programmable thermostat and variable speed air handler
System Capacity		Reduced capacity up to 2 tons; eliminated bonus room system by zoning main system.
Outside Air Ventilation	None	Passive, filtered ventilation air. Ceiling fans in all bedrooms.
Ducts	Local conventional construction	System engineered using manual d, mastic sealed, and performance tested to have cfm25out < 5% of AHU flow, coated duct board
Water Heating	Conventional builder model EF=0.56 gas water heater	EF=0.60 gas water heater, solar water heaters - Now instant
Roof/Clg Assembly	R-30 fiberglass	R-30 cellulose and radiant barrier
Wall Assembly	R-11 fiberglass	R-13 cellulose
Windows	Double pane clear metal frame	Double pane Low-E metal frame SHGC = 0.36 - Now vinyl with .28 SHGC
Lighting	Standard	Air lock can lights
Construction Process Innovations		Statement of Work for each trade. Load calculations and duct engineering done with in-house design team.
Durability And Green Features		Low VOC interior paint, 15 year exterior paint, 30 year architectural shingles, Enviroscaping: saved trees, community wide reclaimed water for irrigation, native plants grouped according to water needs, wildlife habitats, no turf near house.

Initial discussions between Florida H.E.R.O. and the builder, sales manager, project manager, and mechanical, insulation, and solar system subcontractors resulted in the original decision to include batch solar water heating and hydronic heating systems.

Florida H.E.R.O. undertook a redesign of the air distribution system for the Cobblefield homes to insure that ducts are properly sealed with mastic and that the air handler closet (or mechanical room) is sealed from the attic. Field tests showed that leaks on the return side of the air handler depressurized the mechanical rooms. When the ceiling was not properly sealed, air from the attic was introduced to the home, which diminished indoor air quality, increased summer latent loads, decreased comfort, and increased the home's operating costs.

In response to an ongoing challenge to achieve a reasonably air tight mechanical equipment closet, a new protocol shifted installation of ductboard adjacent to the ceiling to rough-in instead of finish mechanical, which allowed maximum accessibility for the field technicians. Once the main supply and return trunk line were stubbed out, the ductboard was custom cut and installed over the ducts, then affixed to framing members with nails or screws and plastic grommets. The duct line seam between the ceiling and duct was sealed with pressure sensitive tape and mastic and perimeter seams were caulked after sheetrock installation. A flow hood CFM test on a Cobblefield model found less than a 5% deviation from the anticipated design flows.

Initially Florida H.E.R.O. recommended using hydronic heating systems for the Cobblefield Development. Since the original decision to include these systems, additional County requirements for anti-scald mixing valves and automatic air vents have added to the difficulty and precision of system installations. Larger models also required bigger water heating units which proved difficult to locate and costly. Installation irregularities and inconsistencies, despite repeated training attempts, exacerbated the situation and compromised the envelope tightness. While the hydronic system offers many benefits, Florida H.E.R.O. decided that the benefits did not justify the costs and problems associated with installing these systems in this development. Instead, a cost effective line of high efficiency (90% AFUE) condensing natural gas furnaces will replace the hydronic systems in all 17 models. This furnace style uses PVC for the exhaust flue and to deliver outside combustion air directly to the unit. This eliminates the need for high and low outside combustion air vents in the furnace closet and insures the maximum amount of system location flexibility. Changing the heating system type did not affect the model duct designs.

#### Reducing Home Moisture After Plumbing Leaks

Florida H.E.R.O. surveyed, performed diagnostic tests, and made recommendations to G.W. Robinson on how to prevent moisture-related problems in several water damaged homes. Two homes had significant moisture problems with one home flooded several days before it was scheduled to show in the 2002 Gainesville Fall Parade of Homes. The "flood" in this home was likely a result of a material failure in a kitchen sink supply riser. The large plumbing leak, however, did provide researchers with the opportunity to initiate and monitor the "drying out" process.

Interior, exterior, and internal ambient moisture readings enabled the monitoring of this situation with a goal of preventing mold growth. To begin the process, all carpets and cabinets were removed from the home and discarded. Two commercial dehumidifiers and several fans were

installed to reduce the home's humidity. After 24 hours, moisture readings were taken at a variety of points throughout the home. Wall surface moisture readings ranged from 45% to 99%. After five days of continuous drying, no surface moisture reading exceeded 10.9% at any point in the home. The process and procedures employed seem to have been successful.

Eliminating the effects of a plumbing line leak and the resulting water damage proved more difficult in the second home where the lasting effect of the water damage was mostly odor. Based on recommendations from FSEC and Florida H.E.R.O., the home's water heater was disconnected, all water-damaged sheetrock, wood, and insulation removed and replaced, and the water heater reconnected. Though initially this fix seemed to work, the smell eventually reappeared. Because the odor was evenly distributed through the home, further investigation determined that the odor source was most likely airborne. The air handler, distribution system, and carpeting were fogged with "May-Clean" solution, whose active ingredients include "cleaning solutions and caustic acids." For now, this appears to have eliminated the home's odor problem. The home was sold and now is occupied, so additional data collection may be difficult.

#### High Bill Complaint

G.W. Robinson's sales manager expressed concern that the model center's monthly utility bills were significantly higher then they expected - more than \$300 a month! To locate the source of this high electric usage, Florida H.E.R.O. arranged a site survey with the mechanical contractor and conducted a two-week temperature/humidity study. Since the home had been individually performance tested for both whole house infiltration and duct leakage rates, the detective work was fairly simple. After determining that the mechanical equipment was correctly functioning and properly charged, researchers tested the flow rate of the outside air intake with an Energy Conservatory exhaust fan flow meter. Higher than anticipated readings, led researchers to test the return air plenum temperature. With an indoor temperature of 77° and an outdoor temperature of 93°, the air temperature in the plenum measured 84°. The in-line damper was adjusted to reduce the volume of outside air introduced.

While investigating this problem, researchers also noted that sales staff continually overrode the programmable thermostat, typically after returning from lunch. Indoor temperature readings as low as 71° were recorded in the model. All findings were reported to the builder and subsequent measurements have indicated that utility bills have dropped.

# Standardized HVAC Installations: Florida H.E.R.O. Duct Designs

Prior to this, the distribution system was field "designed" by the duct mechanic. Florida H.E.R.O. developed duct designs for all of the community models. To insure that mechanical design specifications are correctly interpreted by the HVAC installer, Mr. Robinson has agreed to allow the mechanical contractor to conduct a final review of all architectural CAD drawings before each house project begins. With the designer and installer in agreement on installation parameters, placing the design emphasis on performance excellence and standardization of supply and return register size, HVAC installation has proven to be more timely and the installer's profits enhanced.

#### Florida Green Building Certification

Florida H.E.R.O. researcher Ken Fonorow met with University of Florida Urban Horticulture Extension Agent, Wendy Wilber, at the Cobblefield model center to survey and complete the

FGBC checklist required by the green certification process. Green Features are listed in Table 13

# Fluorescent Lighting

Florida H.E.R.O. used an infrared thermometer to demonstrate to the builder the operating temperature differential between an incandescent and compact fluorescent bulb. After viewing operating temperature differentials of 75°, the builder indicated an interest in replacing as many bulbs as possible with CFL bulbs. The incandescent bulb measured 158°, while the CFL bulb measured 83°

# **Green Housing**

"Green" or sustainable housing is defined as energy efficient housing with added features such as disaster resistance, improved indoor air quality, universal design, resource efficient products and materials, and low water landscaping. BAIHP collaborates with the Florida Green Building Coalition (FGBC), and other organizations to develop or define green home standards, participate in educational programs, and assist in demonstration houses and related activities.

# Florida Green Building Program

BAIHP staff has been extensively involved with the Florida Green Building Program administered by the Florida Green Building Coalition (FGBC), Inc. (www.floridagreenbuilding.org). The intended result of this involvement has been to create Building America homes that include additional "green" or sustainable attributes like those listed above, and to promote the incorporation of various Building America principles to the home building community at large.

The primary tool used to incorporate "green" concepts into homes built by BAIHP partners is the Florida Green Home Designation Standard, developed and maintained by the Florida Green Building Coalition, Inc. with significant support and technical assistance from BAIHP staff. Several BAIHP partner builders have constructed homes that have achieved the designation including Fallman Design and Construction, Pruett Builders, the City of Orlando, and WCI Communities. Each of these builders constructed at least one certified home as a model or showcase to educate the public about the benefits of green construction. In all homes, BAIHP staff assisted with outreach, implementation, and certification. The standard has been incorporated in affordable homes, with several achieving the designation.

The standard also has proved useful to other Building America teams when they work with Florida partners who are interested in achieving green and sustainable housing. One example is the Lakewood Ranch community in Sarasota/Bradenton, FL, which recently began requiring all builders to build all homes to the Florida Green Home Designation Standard. Much of the technical assistance has been provided by CARB, but FSEC staff has been involved with each builder to ensure minimum requirements are achieved, and to assist with development of submittal packages.

To increase awareness and interest in building homes to Building America and green standards, BAIHP researchers have made several presentations to local government decision-makers, and staff. These were delivered to individual government agencies and organizations such as Rebuild America. Presentations have also been given at state and national conferences. The presentations

focused on how green homes benefit the community at large, and how various developer, builder, and home buyer incentives can be created to reflect these benefits, and to reward individual efforts.

BAIHP staff developed and delivers training to individuals interested in how to use the Florida Green Home Designation Standard to achieve the outreach, implementation, and certification phases of green housing. The course has been taught at least biannually since 2001 and attendance averages 12 students per class. The course is now required by the Florida Green Building Coalition for anyone aspiring to certify homes to the Florida Green Home Designation Standard. Several builders and subcontractors have also attended the class to gain insight on green construction.

#### National Green Building Program

FSEC staff members have been involved with the LEED Homes Committee of the US Green Building Council. Efforts are underway to work with local green building programs to formulate a national standard. FSEC researchers have participated in biweekly conference calls, and have attended 3 in person meetings - one of which was hosted by FSEC in February 2004.

During the fifth budget period, BAIHP research received media attention in the Orlando Sentinel for work with green housing (*See Appendix M for reproduction of articles*):

- Orlando Sentinel, Sunday, February 8, 2004. "The Green Revolution: A Florida First. Part 1 of a 4-part series." "Blueprints for the home planet."
- Orlando Sentinel, Sunday, February 15, 2004. "The Green Revolution: Interior Motives.
   Part 2 of a 4-part series." "Health worries hit home." See *Appendix M* for reproduction of articles.
- Orlando Sentinel, Sunday, February 22, 2004. "The Green Revolution: Applying Principles. Part 4 of a 4-part series." "Pioneer spirit." See *Appendix M* for reproduction of articles.

#### Habitat for Humanity-BAIHP Partnership

Americus, Georgia (HFHI) and Habitat affiliates nationwide Category A, 1 Home (Lakeland HFH) Category B, 265 Homes Category C, 260 Homes

The Building America-Habitat for Humanity partnership, formed in 1995 at Habitat's Environmental Initiative Kickoff, has brought BAIHP into the design, construction, and evaluation process of over 500 Habitat homes across the nation built by 50+ Habitat for Humanity affiliates in more than 20 states. BAIHP activities with Habitat (including those conducted under the Energy Efficient Industrialized Housing Project) are listed in Table 14.

BAIHP energy efficiency recommendations for Habitat homes need to meet 4 criteria to be successfully integrated into Habitat's construction process. They must be:

- Cost effective
- Volunteer friendly
- Readily available in current market
- Easily maintained and repaired

In the fifth budget period BAIHP conducted training, provided design assistance to HFH affiliates, and continued development of the "HabiBOPS" program begun in the fourth budget period, BAIHP's outreach to Habitat affiliates has shifted away from assistance to individual affiliates and toward regional and national initiatives. Researchers continue to provide one-on-one design assistance to affiliates who request help. In addition, group training sessions were conducted at conferences and "blitz" builds with organizations like the Southface Energy Institute, Oak Ridge National Laboratory, and Energy Efficient Building Association members.

# Technical Assistance to Habitat for Humanity International (HFHI) *Americus, GA*

Partially because of Building America (and other DOE supported organizations) involvement with Habitat over the years, HFHI adopted Energy Star as one of their two Best Construction Practices for all U.S. affiliates. Best Practices are used to evaluate affiliate status. This represents a major commitment to energy efficiency from the highest ranks of Habitat. Habitat affiliates are encouraged to consistently achieve Best Practices and the demand for Energy Star ratings for Habitat affiliates is likely to surge as a result.

During the 5<sup>th</sup> budget period FSEC researchers met with Habitat for Humanity International staff at HFHI headquarters in Americus, Georgia to discuss HabiBOP and a new Habitat initiative tentatively named "Habitat Better Built." This new program will incorporate an energy package (HabiBOP, Energy Star Rating, local program, etc.), green building concepts, outside air ventilation, and combustion safety-related criteria tailored for small, affordable homes. A program draft was submitted in 2002 and the US EPA Energy Star Home Program committed to developing the technical option packages through ICF. ICF and BAIHP discussed the project and anticipated work beginning in April 2003.

The BAIHP-HFHI draft included a request to analyze additional Builder Option Packages (BOPs) for various Climate Zones as test runs for adding BOPs that emphasize envelope improvements over expensive equipment improvements. This is where the progress stalled and HabiBOPs remains a strong area of research need. The Jacksonville affiliate, HabiJAX, volunteered to pilot the HabiBOP Program in Year 5.

Т	Sable 14 Habitat for Humanity Activity with Ba	AIHP (and	EEIH prior to 9/099)
Year	Project/Location	State	Houses/Description
02-03	Jimmy Carter Work Project		
(June)	Energy Details, Program Development, and		
	Volunteer Training		
	Calhoun County HFH, Anniston AL 35 Near Energy Star (c)		35 Near Energy Star (c)
	Troup-Chambers County HFH, LaGrange	GA	22 Energy Star (B)
02-03	HabiBOPs Energy Star Plus Program	USA	Collaboration between BA,
	Provides Habitat appropriate (small houses)		EPA, and Habitat
	Builder Option Packages to fast track affiliate		International for nationwide
	adoption of energy efficiency. Includes duct application. Pilot		application. Pilot
	system and whole house testing protocol as		tentatively set for Fall,
	well as IAQ and green building elements.		2003. Launch anticipated in

	Table 14 Habitat for Humanity Activity with Ba	AIHP (and	d EEIH prior to 9/099)
Year	Project/Location	State	Houses/Description
			2004.
2003	Habitat Better Built Program Programmatic backbone for integrating energy programs such as HabiBOPs with IAQ and green building elements. Will replace the Green Team and provide for energy/environment program validation, affiliate communications via web and printed materials, and affiliate reporting.	USA	Collaboration between Habitat International, BA, and other supporting organizations for nationwide application. May launch using existing site built BOPs in 2003.
02-03	Zero Energy House		
	Loudon County HFH & Oak Ridge National Lab BA installed approx 40 sensors to evaluate the performance of ZEB features including HPWH, PV, and waste water heat recovery. Data will be online soon.		
	Loudon County HFH, Lenoir City	TN	1 ZEH (A)
2003	Jacksonville Habitat for Humanity		
(Fall)	Largest U.S. affiliate; plans to build Energy Star in 2003 and BA in 2004. Pilot for HabiBOPs Program. <i>HabiJAX</i> , <i>Jacksonville</i>	FL	New partnership in Feb
02-03	<b>DESIGNHabitat House</b> – Energy Efficient	AL	3 BA – Provided design
02 03	Prototype developed by Auburn University and the Alabama Association of Habitat Affiliates. Multiple reproductions expected in 2003-04.	7112	review, analysis, rating, and technical support. (B)
02-03	Design Assistance and Energy Analysis FL: Pasco, Orange, and Brevard Counties NM: Albuquerque OH: Clark, Geauga, Lorain, Marion, & Morrow Counties; Firelands. OK: Central Oklahoma PA: Greene County TX: Lubbock, Smith County		
97-03	Regional Training with Habitat for Humanity International & HFH Regional Offices  Southeastern HFH Conference 1996 HFHI 20 <sup>th</sup> Anniversary 1997 Florida HFH Conference 1998 Syracuse, NY 1999 Southeastern HFH Conference 1999 Affordable Comfort 2 day HFH Training 1999 Florida HFH Conference 2000		

П	Table 14 Habitat for Humanity Activity with B.	AIHP (and	d EEIH prior to 9/099)
Year	Project/Location	State	Houses/Description
	Portland, OR 2000		
	New York City, NY 2000		
	Southeastern HFH Conference 2002		
2002	Florida Affiliates Construction Round Table	FL	Energy code changes
2002	<b>Training</b> for 20 Ohio affiliates eligible for 1 <sup>st</sup> Energy Grants	ОН	Full Day training on reaching Energy Star and Beyond
2002	Greater Denver Habitat	CO	6 Building America (A)
2002	Joint Proposal for development of Home Owner Manuals	USA	BA with HFHI Was not funded.
2002	BA Roofing Experiment		6 Roof assemblies with
	Lee County HFH, Mt. Myers	FL	energy monitoring (c)
01-02	Comprehensive Survey	USA	Collaboration of HFHI and
	Energy Practices in Habitat Affiliates		BA to assess state of Energy Efficiency in U.S. Affiliates
01-02	Lakeland Habitat, Lakeland	FL	2 Building America (A) 6 BA Pending Cert (A) 3 Energy Star (B)
00-01	Design Assistance and Energy Analysis AL: Birmingham MS: Jackson	AL	1 Energy Star Cert (B)
2001	Easter Morning Build		23 Energy Star (B)
	Sumter County Habitat, Americus	GA	On Site Training and testing
2000	Jimmy Carter Work Project		Volunteer and Homeowner
	New York City HFH, Harlem	NY	Training with HFHI
	Sumter County HFH, Americus	GA	Produced 23 Ratings (C)
98-01	Broward County HFH	FL	40 Energy Star (B)
99-03	Brevard County HFH	FL	20 Energy Improved (C)
99-01	<b>Energy Fact Sheets</b>	USA	BA reviewed/contributed to
	Developed by organizations supporting HFHI.		various documents
97-00	Easter Morning Community	GA	125, Most Energy Star (B)
,, 00	Sumter County HFH, Americus	0.1	120, 111000 2110185 21111 (2)
98-03	Greater Houston HFH	TX	97-65 Energy Star Houses (B) 98-100 Energy Star Houses 02-began striving for BA (B)
97-00	Greater Canton HFH, Canton	ОН	20, Energy Improved (C)
99-01	Durham County HFH, Durham	NC	20, Energy Star (B)
98-99	<b>Design Assistance and Energy Analysis</b> CA: Long Beach HFH		
		•	

]	Table 14 Habitat for Humanity Activity with BAIHP (and EEIH prior to 9/099)			
Year	Project/Location	State	Houses/Description	
	FL: Indian River, Lake, & Sumter Counties,			
	MI: Grand Rapids HFH			
	NY: Albany, Syracuse, & Yonkers			
	VA: Lynchburg HFH			
1997	Jimmy Carter Work Project	TN, KY	50 Energy Improved (C)	
	Energy Affordable House			
95-97	Greater Houston HFH	TX	65 Energy Improved (C)	

Structural Insulated Panel Construction Study, Plains, GA At the request of HFHI, BAIHP tested a home built by Home Front, Inc. in Sarasota, Florida. The house scored an 87.6 on the HERS scale (Figure 15). Built with structural insulated panels (SIP), which contain a polystyrene core faced on both sides with a thin concrete board. The exterior finish is stucco with Hardy board trim. A structural steel wind-frame welded to steel plates imbedded in the slab was engineered to withstand hurricane force winds. The panels passed Dade County large missile impact and wind load testing.



Figure 15. Habitat SIP house built in Plains, Georgia.

Interior ducts are housed in a central corridor and connect to a heat pump in a central closet. Return air is drawn from each room through extra registers on the duct chase. A whole house fan at one end of the chase provides ventilation during shoulder seasons.

# 2003 Jimmy Carter Work Project (2003 JCWP)

Habitat International Director of Construction and Environment requested FSEC assistance for all three Carter Project affiliates: Calhoun County (AL) and LaGrange (GA). The JCWP affiliate in Valdosta (GA) did not request BAIHP assistance; however, a former Energy Monitor working at the Valdosta site organized an informal corps of volunteers to tackle air sealing and insulation details. The construction manager and executive director made the 2003 JCWP an example of high performance, high quality housing for affiliates and other builders in the region and consequently asked BAIHP for assistance in reviewing construction techniques.

*Calhoun County HFH*: The Calhoun County HFH affiliate (Anniston, Alabama) built 35 near Energy Star homes during the 2003 JCWP.

BAIHP worked closely with the mechanical contractor and the construction supervisors prior to the build to bring the initial HERS ratings of 78 up to 86. Though the houses had been slated to be Energy Star, a miscommunication resulted in the air conditioning efficiency being SEER 10 instead of SEER 12. In Anniston's mixed-humid climate the difference was enough to drop HERS ratings below the 86 target. However, the homes are much more efficient than the previous convention and many volunteers were exposed to energy efficient design and construction as well as combustion safety design (*Figure 16*). Radon mitigation systems were provided by an Alabama environmental group.

Troup-Chambers HFH (LaGrange, Georgia): The executive director for this affiliate adopted the Energy Star goal and spearheaded the construction of 22 Energy Star homes during the 2003 JCWP (Figure 17). Four plans were rated and scores ranged from 86.5 to 88.5. BAIHP consulted with the affiliate on window specifications, insulation levels, AC efficiency, and air sealing details particularly with regard to the air handler closets which were previously built with return plenums open to the attic. The affiliate plans to continue building using the JCWP specifications.

#### Habitat for Humanity Affiliates

BAIHP's technical assistance to Habitat affiliates has shifted away from assistance to individual

affiliates, and toward regional and national initiatives including

- Ohio's First Energy grant program for Energy Star affiliates,
- Building America level affiliates in Lakeland (FL), Houston, and Loudon County (TN), the latter being an ORNL partnership to build zero energy Habitat houses with FSEC monitoring assistance.

A cumulative list of affiliates receiving direct design assistance from BAIHP is shown in *Table 14*. Work conducted with individual Habitat affiliates, independent of national initiatives, is presented here, organized by state.



Figure 16 Homeowner Sandy Sedano installs rigid insulation (part of the energy package) on her new home during the 2003 JCWP at the Anniston (AL) site.



Figure 17 2003 Jimmy Carter Work Project house in LaGrange GA – one of 22 Energy Star homes built in one week.

Alabama: Auburn HFH

David Hinson from the Auburn University College of Architecture contacted BAIHP about a prototype "DESIGNhabitat" home. Three Energy Star homes have now been built with the local Habitat affiliates in Auburn. The prototype will be offered to affiliates statewide through the Alabama Association of Habitat Affiliates (AAHA) and non-profit Design Alabama. AHA requested indoor air quality and combustion safety testing plus design input on the prototype home in 2002 and 2003. The design features vernacular touches that enhance energy efficiency such as the screened front porch, operable transoms over doors (for ventilation and return air flow), metal roofing, and large overhangs (Figure 18). A sealed combustion



Figure 18 Transom return air pathway with operable louvers blends in with the vernacular aesthetics of this DESIGNhabitat Energy Star home built in conjunction with Auburn University's College of Architecture.

closet for the gas water heater, sealed and tested ducts, and high efficiency heating and cooling complete the energy package.

#### Alabama: Birmingham HFH

In 2001, BAIHP researchers tested and rated 3 homes for this affiliate and provided the local construction manager with energy analysis and recommendations. Birmingham HFH continues to Energy Star homes in 2004 - many with HUD approved safe room construction.

Alabama: Calhoun County HFH

Please see 2003 JCWP above, in the summary of work conducted with HFHI.

#### Florida: Jacksonville (HabiJAX) HFH

This affiliate, located in Jacksonville, Florida, is one of Habitat's most productive alliances. In anticipation of HabiJAX involvement in the HabiBOP pilot program, BAIHP completed preliminary HERS ratings on planned homes. Follow-up test results indicate that HabiJAX is a good candidate for the program, particularly after the construction manager agreed to incorporate a ventilation strategy and energy efficient lighting into their home designs.

#### Florida: East Orange County HFH

After attending courses and seminars taught by BAIHP staff over several years, this affiliate's construction manager began building interior duct systems. One of those homes was tested in April and found to be well separated from the unconditioned attic above as desired.

Florida: Lakeland HFH

This affiliate has constructed 8 Building America level houses since 2002 (*Figure 19*). During this budget period, the affiliate ramped up construction and trained a new group of construction volunteers completing 8 more homes in the first quarter of 2004. Testing is underway and these will be the first Habitat homes put through the BA Benchmark exercise by BAIHP.



Figure 19 Habitat for Humanity energy efficient home in Lakeland, Florida.

Florida: Alachua HFH

Florida H.E.R.O. has worked with Alachua Habitat for Humanity for many years. Currently the affiliate is building a subdivision called Celebration Oaks. Summary of specifications is provided in *Table 15*.

Table 15 Alachua Habitat for Humanity Specifications for Celebration Oaks

Component	Specification
Conditioned Area	~1100 (2 built, 6 in progress, 64 units total)
HERS Rating	NA
Cooling and Heating	SEER 12 Air Conditioning with homeowner
	choice of heat pump or standard gas furnace
	heating, Air handler in the conditioned space.
Ventilation	Filtered passive fresh air ventilation.
Duct System	Duct system engineered using Manual D
	calculations, sealed with mastic, performance
	tested for air tightness
System Capacity	Cooling and heating systems sized using
	Manual J calculation procedure
Water Heating	Standard Gas (considering tankless gas)
Walls	ICF Construction with wood frame roof and
	interior walls
Ceiling	R-30 cellulose insulation
Windows	Double pane Low-E vinyl frame

Georgia: Atlanta HFH

Energy simulations were conducted for insulated concrete form (ICF) homes in Houston and Atlanta. Comparative studies could be conducted in both cities since the same floor plans will be used to build ICF and wood frame homes in those areas. Simulation results from the homes were evaluated to develop suggested improvements that would bring the homes to Energy Star levels. The Houston affiliate is planning a 100-home development and is looking for home performance strategies that would allow them to reach Energy Star at a minimum. Simulations using the measured test data were conducted and recommendations made for their consideration.

The Atlanta home will incorporate substantial thermal mass with concrete ceilings and concrete

interior walls. Simulations on the thermal mass benefits were completed and reported. These simulations focused on the use of thermal mass to reduce the size of the heating, ventilation, and air conditioning systems.

Georgia: LaGrange (Troup-Chambers) HFH

Please see 2003 JCWP above.

# Georgia: Sumter County HFH

This affiliate attended several courses and seminars taught by BAIHP staff in recent years. As a result, in 2000 the Sumter construction manager began building interior duct systems. One of those systems was tested in March 2002, as part of the Air Handler Air Tightness Study, and found to be connected to the unconditioned attic above. These results were similar to findings in BAIHP's sister project on Interior Duct Systems. After discussions at the April construction roundtable, modifications were made to the construction approach which became part of their standard building practice for the affiliate.

As of 2003, Sumter County HFH is no longer building houses because all remaining qualifying residents have declined partnership.

# Ohio Affiliates

A utility grant program in Ohio spurred a broad interest among HFH affiliates in reaching Energy Star level. Affiliate homes built to the Energy Star standard in the utility's service area will receive a grant that equals the cost of the home. Several affiliates acquired the Example Energy Star Packages from HFHI's web site and called to discuss them. In response to this interest, HFHI conducted a workshop in early July 2002 attended by sixty people. Subsequently, all affiliates (~30) attending the course have built and had certified at least one Energy Star home. Each has collaborated with a local certified HERS rater. Several affiliates contacted BAIHP to clarify aspects of the process and only one affiliate experienced difficulty with the certifying process and received direct support from BAIHP.

# Louisiana Affiliates

FSEC arranged a partnership with Superior Environments in Metarie to provide support to the Baton Rouge HFH affiliate's April Energy Star home "blitz build." Four high efficiency homes were built during the 2002 blitz build. Though all home met Energy Star status, documentation has not yet been received that the homes were registered. (Please see *Table 16*.)

Table 16. HERS scores for Baton Rouge Habitat Energy Star homes.

House ID#	Address	Score	Est. Utilities
118	635 N. 17 <sup>th</sup> Street	88. 7	959
119	58320 Long Street	87.2	1122
120	58330 Long Street	87.2	1364
121	58340 Long Street	87.2	1120

#### Nevada Affiliates

FSEC was contacted by Portland Cement Association (PCA) to collaborate on an HFH house planned for the 2003 Builders' Show in Las Vegas. This collaboration was a joint effort between BAIHP, PCA, and the Las Vegas Habitat for Humanity.

New Mexico: Albuquerque HFH
BAIHP completed an initial home design
analysis for the Albuquerque HFH which was
revised with feedback from the affiliate. Final
recommendations were submitted to
Albuquerque HFH to assist them in reaching
Energy Star status.

Tennessee: Loudon County HFH
In partnership with Oak Ridge, BAIHP
prepared to instrument a zero energy home
(ZEH) built by Loudon County (TN) HFH their fourth (Figure 20). BAIHP previously
instrumented and collected data on ORNL's
behalf from Loudon County's first ZEH
which showed results of \$80 net annual



**Figure 20** Local sponsors in front of 2nd ZEH built by Loudon County HFH in partnership with ORNL. FSEC provided monitoring for the 1<sup>st</sup> and 4<sup>th</sup> ZEHs.

electric cost and an ACEEE paper was authored by ORNL and FSEC. The affiliate has provided valuable feedback on the SIP construction process to other interested affiliates. The fourth ZEH, like the first one, features SIP construction, a PV array, a heat pump water heater with damper to harvest cool dehumidified air in the summer, high performance windows, optimum orientation, overhang shading, and interior ducts. The model also features poured walls in the walkout basement with a side by side comparison of damp-proofing products. Data is available on-line at www.infomonitors.com.

#### Texas: Ellis County HFH

This affiliate reports that they have been building Energy Star homes and now are interested in moving toward a Zero Energy Home similar to the Loudon County HFH project in Tennessee.

#### Texas: Houston HFH

In 2001, BAIHP completed a preliminary evaluation of the concrete homes built in partnership between Houston HFH and the Portland Cement Association. Staff tested and rated the homes in January 2002 and made recommendations for reaching beyond Energy Star to the Building America standard. Later that year, the affiliate's construction manager reported that they were now implementing BAIHP energy efficiency, durability, and indoor air quality recommendations. Final home design recommendations included construction of a passive ventilation system and an interior duct system. In 2004, this affiliate reported that all homes (~100) built since FSEC's 2002 recommendations have exceed Energy Star (rated by local utility) and have passive fresh air ventilation ducted to the air handler with a separate, soffit-mounted filter.

# **Heat Pipe Technology**

Gainesville, Florida

Florida H.E.R.O. met with Chuck Yount, National Sales Manager, and the residential engineering staff to discuss the requirements and anticipated performance of their stand-alone dehumidification system, the BKP series. This system has the ability to provide outside air and maintain positive pressurization, and it can be used in conjunction with a condensing section to reject heat generated through dehumidification. During the 4<sup>th</sup> budget period, Florida H.E.R.O. suggested the use of this technology to several contractors who build large homes.

# HKW Enterprises (Lewis Place Association, Ltd., Meadowbrook Development Inc., Millpond Development Corp., and Joyner Construction.)

Gainesville, Florida Category B, 333 Homes

Awards: NHBA Energy Value Gold Medal Award

Florida H.E.R.O. worked with HKW Enterprises and its subsidiaries to incorporate Building America specifications in

- 1 apartment complex with 112 units (Lewis Place)
- 2 town house developments with 210 units (Williamsburg and Monticello),
- 1 single family home built by Joyner Construction.

Lewis Place was the first Energy Star low income apartment complex in the country and it incorporated an interior duct system (Figure 21) with a comprehensive air sealing protocol that included cellulose wall insulation with a gasket between the top plate and the drywall. The units also featured direct vent gas water heaters for good indoor air quality. The Williamsburg and Millpond townhouse developments and the single family home built by Joyner Construction were built with similar features.



Figure 21 Interior duct system under construction at Lewis Place – the first Energy Star apartment complex in the country.

#### **Homes of Merit**

Marathon, Florida Category B, 14 Homes

In 2002, Florida H.E.R.O. performed multiple diagnostic tests and conducted a site survey on a mobile home with mold problems in Marathon, Florida. Florida H.E.R.O. determined that the mechanical system was significantly oversized, and the home was operating under negative pressure during system operation. The owner left the central system fan in the "on" position, further exacerbating the indoor humidity problem. Measured indoor relative humidity levels were about 70%, consistent with outdoor humidity levels. Since this case has gone into litigation, researchers have not had the opportunity to determine the final outcome.

In 2001, Florida H.E.R.O. met with plant personnel and LaSalle Air Systems at Lakeland Homes of Merit factory to discuss Energy Star compliance for model homes and HUD code factories. The researcher also performed duct tests on several models at the Bartow manufacturing plant,

assisted in development of material and system specifications, and conducted the Energy Star Energy Star Manufactured Home Plant Certification at the Lake City and Bartow plants.

#### Kit HomeBuilders West

Caldwell. Idaho

Kit Home Builders West was the builders of the Zero Energy Manufactured Home in response to an RFP issued by the Bonneville Power Authority in partnership with BAIHP staff in Washington and Idaho. See Zero Energy Manufactured Home in the Research section of this publication.

#### Marlette Homes, NOGI Gardens

Seattle, Washington

Technical Assistance by BAIHP Contractors Washington State University Energy Program, Oregon Office of Energy and Idaho Department of Water Resources, Energy Division

Awards: HUD Secretary's Gold Award for Excellence

Energy Value Housing Award

Nogi Gardens is a 75-home community located in southeast Seattle The project contains the first two-story, HUD Code attached "townhouse homes." (*Figure 22*) All the homes have been built by Marlette Homes in Hermiston, OR to Super Good Cents/Energy Star specifications. A blower door test of the building envelope showed 5.0 ACH at 50PA, average for a manufactured home in the Pacific Northwest. Duct leakage is very low, due to Marlette's use of mastic and duct risers.

#### Miami-Dade HOPE VI Project

Miami (Dade County), Florida Technical Assistance by BAIHP Researchers Rob Vieira and Eric Martin



Figure 22 Nogi Gardens, America's first HUD Code attached town houses.

This project was a community revitalization program aimed at lessening poverty density by demolishing dilapidated public housing and replacing it with new, less dense housing. In this HUD-sponsored inner city redevelopment project, about 860 public housing units were to be torn down and replaced with 450 new units. The new units would have included duplexes, townhouses, and single-family homes.

As part of a sustainability team, FSEC participated in the initial design charette which reviewed project home designs, made architectural recommendations on wall and roof assemblies, exterior finishes, and other energy-related design and construction features.

During 2002, FSEC provided assistance to Miami-Dade Department of Environmental Resources Management when they emphasized the importance of Building America principles

and techniques to the Miami-Dade Housing Authority. The Housing Authority conducted a mandatory value-engineering meeting to ensure that their Hope VI Project would meet the available budget. FSEC staff, as well as other stakeholders, took part in housing discussions and analysis to ensure that the Building America principles and techniques specified early in the project would be considered and not engineered out of the project.

Unfortunately, this project never got past the design stage due to a lack of cooperation among existing residents of the area.

# **Nez Perce Fish Facility**

Cle Elum, Washington

Three SGC homes were built at the Nez Perce tribal fish facility in Cle Elum, WA. One of these homes is equipped with Energy Star appliances and lighting; all three homes are heated with Insider heat pumps. Monitoring equipment was installed in Year 2. In Year 3, preliminary blower door testing indicated a high leakage rate. During Year 4, tests found significant duct leakage due to failure of butyl tape at risers on 2 year old home. (See also Section III Research Zero Energy Manufactured Home.)

#### **Oakwood Homes**

Moultrie, Georgia Hillsboro, Texas Kileen, Texas Technical Support by BAIHP Researcher David Beal

BAIHP assisted Oakwood Homes with one problem home investigation between April 2003 and March 2004. This large HUD code manufacturer previously requested an FSEC duct installation review and consultation on ways to make the home's systems work better together. In 2002, plant visits were made to the Oakwood plant in Moultrie, Georgia and to the Hillsboro and Kileen, Texas plants. Recommendations for appropriate duct system design and manufacture were reported to Oakwood Homes.

An Energy Gauge USA analysis of Energy Star and non-Energy Star homes in Boston, Minneapolis, and Indianapolis was performed. Researchers determined that Oakwood Homes could meet Energy Star standards if they increased installed gas heating and cooling system efficiencies, and floor and roof insulation levels. These results were communicated to Oakwood management via email.

#### **Palm Harbor Homes**

Category B, 13 Homes

Category C, 1,645 Homes (North Carolina factories)

Category D, 32,000 Homes

Technical Assistance by BAIHP Researchers Subrato Chandra, Neil Moyer, Dave Chasar, and David Beal

Awards: 2004 Energy Value Housing Award

First under the Energy Efficient Industrialized Housing Program (EEIH) and now under BAIHP, FSEC collaborates with Palm Harbor Homes (PHH) offering building science advice, energy

ratings, and conducting diagnostic testing including infrared building and duct air tightness thermal imaging camera inspection. As a result, PHH now incorporates added return air transfer ducts to minimize pressure imbalances in the conditioned space and measures leakage of every duct system to ensure losses below 3% (Qn<sub>total</sub>) at every factory.

FSEC provided assistance to Bert Kessler (PHH VP of Engineering) with submission of an NAHB nomination for the 2004 Energy Value Housing Award.

Energy Star Plant Certification for Palm Harbor Factories nationwide

With FSEC guidance, PHH Plant City produced the world's first two HUD-code Energy Star homes in 1997 (*Figure 23*).

Since then, EPA has implemented an Energy



Figure 23 A Palm Harbor Energy Star home manufactured in Plant City, Florida.

Star factory certification procedure which involves testing in both the factory and at the home sites. The procedure verifies consistent factory production of Energy Star level manufactured homes.

Nine Palm Harbor factories have completed certification (*Table 17*) under the new Energy Star guidelines for manufactured homes.

**Table 17 Energy Star Certified Palm Harbor Plants** 

Plant Location	Certification Date		
Plant City, FL	April 2002 (4 <sup>th</sup> Budget Period)		
Sabina, OH	June 2002 (4 <sup>th</sup> Budget Period)		
Austin, Buda, Ft. Worth,	June 2003 (5 <sup>th</sup> Budget Period)		
and Burleson, TX			
Boaz, AL	September 2003 (5 <sup>th</sup> Budget Period)		
Albemarle, NC	December 2003 (5 <sup>th</sup> Budget Period)		
La Grange, GA	December 2003 (5 <sup>th</sup> Budget Period)		

# Energy Star Ratings using EnergyGauge USA

In the fifth budget period, FSEC rated two PHH modular homes produced in Texas. Prior to that, FSEC staff conducted several Energy Gauge ratings and related energy analyses for PHH Plant City (FL) and performed two energy analyses comparing standard HUD code specifications to PHH energy improved homes sited in Detroit, Morgantown (WV), and Missoula (MT).

# EnerGMiser Energy Management System

Researchers conducted an analysis of the PHH EnerGMiser Energy Management System and quantified the energy savings over base-case HUD code homes in 40+ US cities. Energy savings ranged from 28% to 42%. The results of these analyses are listed at the PHH corporate web site at <a href="https://www.palmharbor.com/our homes/home features/energy management system">www.palmharbor.com/our homes/home features/energy management system</a>.

# Factory in Albemarle, North Carolina

FSEC contacted the North Carolina engineering manager for information on Palm Harbor's

typical model construction specifications in order to begin Energy Star qualifying procedures. Two PHH model analyses for three different climate zones were run to assess initial energy efficiency. These tests were rerun once specific window SHGCs were received from PHH.

On February 24 and 25, 2003, FSEC conducted a plant visit to direct and oversee Energy Star certification tests on six floor models. Tests were completed by FSEC and by factory personnel with FSEC oversight. All models passed the 3% leakage limit. To complete the certification, three additional site installed homes will be tested for compliance.

FSEC staff also worked with the plant engineer on builder option packages (BOPs) versus software options as a means to qualify homes for Energy Star. It was determined that qualifying homes in Energy Star zones 3 and 4 will be feasible using BOPs, but EG USA will be needed to certify at least some of the zone 2 homes.

# Factory in Austin, Texas

PHH initiated certification procedures for Energy Star per the EPA/MHRA guidelines. Staff completed the reporting and certification on two PHH Austin homes in the Houston area for Energy Star compliance. One home passed and the other failed due to belly board installation problems. (*Figures 24 and 25*) These belly board problems have since been addressed and the Austin plant and the remaining three Texas plants are currently being certified for Energy Star production.





Figure 24. Another belly tear found during inspection.

Figure 25 Worst belly tear near plumbing penetration.

#### Factory in Plant City, Florida

#### Energy Star Plant Certification

Researchers initiated certification procedures for Energy Star per the EPA/MHRA guidelines. FSEC reviewed the Design Approval Inspection Agency (DAPIA) packages and design procedures. The PHH Plant City factory was certified in February 2003 and registered one Energy Star home in Polk County, Florida.

FSEC met with the plant engineer on September 16 and 17, 2002 to analyze several new models for Energy Star eligibility. The analysis was conducted using EG USA software (v-1.32). Researchers assisted the plant engineer with a combination of EG USA software and BOPs, so that all plant models over several states could reach Energy Star levels.

#### Insider Heat Pumps

In 2001, five model homes at PHH-Plant City were tested for return air performance. Two of the homes were modular with Insider heat pumps. Performance results and recommendations were submitted to the plant engineer.

Staff retested two modular homes with Insider heat pumps and determined that leakage in the condenser fan compartment was depressurizing the homes. Further testing on other Insider installations is needed to uncover the scope of this problem and plans are in progress to find the best corrective course of action. BAIHP will visit PHH Plant City and observe the installation when the next Insider heat pump is requested. Researchers will look for installation problem areas and perform additional home tests.

#### Technical Assistance

Diagnostic tests were conducted in 2002 on a home in Odessa, Florida manufactured by PHH-Plant City. This visit was requested by PHH after they received a homeowner high-utility bill complaint. Inspections with the infrared (IR) camera found no insulation problems and duct blaster and blower door tests revealed airtight duct and envelope systems. Other than an oversized air conditioning system, there were no obvious reasons for the high bills. The homeowner was satisfied with the investigation and apologized for their written complaint.

# Factory in Sabina, Georgia

PHH signed an Energy Star Partnership Agreement to begin certification of the Sabina Plant. Two model home plans were analyzed, each with a gas furnace and a heat pump, using EnergyGauge USA software. The plant certification visit and site-installed home ratings were done in Spring 2002 and certification paperwork was forwarded to the EPA for plant registration. PHH is planning a 54-unit development in Wilmington, Ohio. Modifications made at the Sabina Plant should be very helpful for the Wilmington endeavor.

#### **Penn Lyon Homes**

Selinsgrove, Pennsylvania Technical Assistance by BAIHP Contractor University of Central Florida, Industrial Engineering Department

In March of 2004, Penn Lyon Homes (Selinsgrove, PA) began a large scale plant wide test of a prototype Status and Control System (STACS) developed by BAIHP researchers at the UCF Constructability Lab. The system is a real time shop floor labor data collection and reporting system. Production workers use wireless laser scanners (*Figure 26*) to report their current work



Figure 26 Scanning drywall activities with new STACs device.

assignment.

STACS reporting is web based and provides both real time manufacturing status and summaries of historical production performance. While labor represents a relatively modest fraction of production cost, typically 10-15%, it has a profound impact on operations, including product quality, cycle time, material waste, and labor productivity. The test will continue through the summer of 2004, and results will be used to develop labor models using linear regression and neural nets.

See also, Avis American Homes (Technical Assistance section) and Status and Control System (STACS) (Section III, Research).

# Podia Construx/Rainbow Springs Construction

Gainesville, Florida Category B, 22 Homes Technical Support by BAIHP Subcontractor: Florida H.E.R.O.

Florida H.E.R.O. worked with David Sullivan, owner of Podia Construx, his sales staff, project management, and principal sub-contractors to incorporate Building America concepts into the communities of Rainbow Springs, Hidden Lake, and Ocala Waterway.

Podia builds mostly concrete block homes with a continuous, interior layer of ¾" unfaced rigid wall insulation and unvented attics. Spray foam insulation is applied to the underside of the roof deck and is sometimes used for wall insulation. Some of Podia's homes are performance tested for duct and whole house air tightness. The homes also feature SEER 13 heat pumps or SEER 13 air conditioners coupled with standard gas furnaces. All homes have filtered outside air ventilation and double pane Low-E vinyl frame windows.

Podia tried replacing roofing felt with Tri-Flex material for moisture transmission reduction on home, but after complaints from the roofers regarding a lack of footing on the slick material, the Tri-Flex was removed and replaced with standard felt paper.

#### **Condensation Complaint**

In response to a homeowner's concern about excessive condensation on interior windows, Florida HERO performed a site survey of ambient, interior, surface, and subsurface moisture readings to determine the cause. This home has Icynene sprayed on the underside of the roof sheathing and an outside air duct. The outside air duct damper had been shifted to the closed position. The damper was reopened and the moisture related complaints were eliminated.

#### **Sandspur Housing**

Maitland, Florida Category B

Since 2002, FSEC staff have been working with Sandspur Housing, the largest affordable home builder in the nation. Sandspur constructs approximately 4,000 apartment units per year, primarily in Florida and Georgia. The company's primary interest in Building America is in receiving assistance for designing low energy-use units with good indoor air quality and

resolving recurrent moisture problems in Florida's hot-humid climate. Contact with Sandspur was initiated by BAIHP subcontractor Florida H.E.R.O. in Gainesville, Florida.

Sandspur Housing staff were taken on a tour of the David Hoak demonstration home to show specific equipment and the role it plays in an overall systems engineering approach. After the tour, discussions continued on the Landing Community analysis. This allowed personnel to view firsthand some of the Building America principles and practices so that they could explain these concepts to others in the Sandspur organization.

BAIHP has worked with Sandspur in three Florida cities: Naples, Orlando, and Gainesville.

# Naples, Florida

For Camden Cove, Sandspur's community in Naples, BAIHP researchers conducted an energy analysis on all individual units and several apartment buildings slated for construction in 2003 and 2004. Information from Sandspur's building plans was combined with Florida H.E.R.O.'s field experience in Sandspur's Gainesville apartment complex Harbor Cove Community. Results indicated an opportunity to cost-effectively reduce energy use/cost in a 16-unit apartment building by more than 20% while improving indoor air quality and durability. Since Sandspur was already building fairly tight duct systems, savings potential in this area was already being achieved. Additionally, heating and cooling loads in multi-dwelling buildings are lower than similar size and construction single family detached housing because there are fewer exterior surfaces.

Energy efficiency recommendations included:

- Switching to 75% fluorescent lighting
- Reducing duct leakage to the outside to 3% ( $Qn_{OUT} \le 0.03$ )
- Reducing window area to 6% of floor area
- Window shading strategies to provide overall solar heat gain coefficient of 0.2
- Installing ducts inside the conditioned space
- SEER 13.0 cooling systems
- White metal roofing or radiant barrier
- Programmable thermostats
- Ceiling fans in all bedrooms and main living areas

Air quality improvement strategies focused on including:

- Pleated return air filters rated with an Minimum Efficiency Reporting Value (MERV) of 11
- Filtered mechanical ventilation of 7.5 CFM/person + 0.01 CFM/ft<sup>2</sup>
- Supplemental dehumidification
- Quiet, energy efficient bathroom exhaust fans with timer switches ( $\leq 0.3$  watts/ft<sup>3</sup>)
- Quiet, energy efficient vented kitchen range hoods in each unit

A summary of all analysis results and building design features was prepared and submitted to Sandspur Housing. Two meetings were held to review the recommendations.

#### Orlando Moisture Investigations

FSEC staff tested four Sandspur-built apartment units and installed datalogging equipment in six

units at the Landings Community in Orlando where some units had reported moisture problems. Measured envelope leakage was typical for new construction, and all but one unit had very tight duct systems. Dataloggers (stand alone temperature RH loggers) were deployed in the air handler of each unit to record interior moisture levels. Three weeks of data were plotted for six apartments as temperature, relative humidity, and dew point. Ambient weather data from the nearby Hoak house datalogger was included and compared favorably with published Orlando airport weather.

To continue investigating the cause of excess moisture in the apartment units, datalogging equipment was installed in six additional units. To remedy problems, prototype schemes were evaluated such as utilizing a humidistat in conjunction with thermostat, and installation of a dedicated dehumidifier. Data analysis will be completed in 2004.

# Gainesville, Florida Brookside Apartment Complex

During the 5<sup>th</sup> budget period, work was completed on testing and rating all 176 units in Sandspur's Energy Star apartment complex *Brookside* in Gainesville, FL. Apartment features are given in *Table 18*. Each apartment was individually tested for envelope and duct air tightness as well as flow through the passive outdoor air system by Bob Abernethy, FSEC technician, in collaboration with Florida H.E.R.O. Results are listed in *Table 18* below. The complex consists of one to four bedroom models grouped into two-story buildings of eight to 16 units.

**Table 18 Brookside Apartments Characteristics** 

Component	Description Description	
Conditioned area	1 Bedroom unit =717 sq. ft.	
	2 Bedroom unit = 990 sq. ft.	
	3 Bedroom unit = 1313 sq. ft.	
	4 Bedroom unit = 1582 sq. ft.	
HERS Score	86.1 - 87.7	
Mechanical and System	Interior air handler	
	Fresh air ventilation	
	Engineered and right sized systems	
	Engineered duct design	
Fresh Air Ventilation	4" fresh air duct provides 34 to 45 cfm to house side	
	of HVAC filter when mechanical system is running.	
	Manual damper provided.	
Heating	Hydronic heat coils fed by a conventional gas water	
	heater in an exterior closet	
Cooling	SEER 12 AC - was SEER 10	
	1 and 2 Bedroom units = 1.5 Ton - was 2-2.5 Ton	
	3 and 4 Bedroom Units = 2 Ton - was 2.5-3 Ton	
Ducts	Mastic sealed and tested	
Duct Leakage	CFM25 <sub>OUT</sub> < 5% of AHU flow	
Wall insulation	Unfaced fiberglass batt (first cost savings of	
	\$0.22/sq ft and reduced site labor)	
Windows		
Glazing & Frame		

# **Southern Energy Homes**

Addison, Alabama Category D, 12,803 Homes Technical Assistance by BAIHP Researchers Neil Moyer and David Beal Trip Report

During the 1<sup>st</sup> budget period, BAIHP held a meeting to introduce Building America to the industry. Representatives from Southern Energy Homes attended in hopes of finding solutions to moisture problems they were experiencing in coastal areas. In 2000, BAIHP researchers conducted building science diagnostics in several moisture damaged homes in coastal Louisiana and found contributing factors to be duct leakage and inadequate return air pathways from bed rooms



**Figure 27** Southern Energy Homes quality control engineer conducts in-plant duct leakage test.

Southern Energy Homes took steps to achieve substantially leak free duct systems in all their homes. They switched from UL 181 approved tapes to mastic and fiberglass mesh for forming component connections in all their duct systems and began testing duct systems during production (*Figure 27*).

In 2002 FSEC received a request to certify the Southern Energy Homes (SEH) factory in Addison, Alabama for Energy Star compliance. A plant visit in August 2001 examined opportunities to enhance manufacturing productivity. Three model homes were tested for Energy Star certification, recommendations were made, and Energy Star plant certification paperwork submitted to US EPA.

In 2003 discussions continued with SEH plant personnel for conducting an analysis at one of their factories using the UCFIE simulation tool. On January 27 and 28, FSEC conducted site visits and performed diagnostic tests on several problem homes and submitted recommendations in a trip report in February. Based on these recommendations, FSEC conducted duct test training for factory personnel in four Southern Energy Homes factories.

In May of 2003 FSEC certified a Southern Energy Homes factory for EnergyStar production. FSEC conducted diagnostic field visits to Southern Energy homes in December 2003 and January of 2004 and provided recommendations in trip reports.

#### **Spain Construction**

Gainesville, Florida Category B, 33 Homes

Florida H.E.R.O. worked with Spain Construction this reporting period to address a homeowner comfort complaint and to assist the builder's mechanical contractor in designing a distribution

system in a new Willowcraft community custom home. Diagnostic tests and Manual J calculations performed for the homeowner complaint determined that the mechanical system was oversized by one ton. In addition to the air handler filter, the researcher also located a second filter at the return grill. The homeowner was unaware of this filter, so its replacement significantly improved the system airflow. Florida HERO recommended the introduction of outside air to the return side of the system to facilitate positive pressurization and to slightly increase the load and diminish some of the effects of oversizing.

The builder has improved his specifications from standard code compliance (SEER 10, single pane windows, etc.) to HERS ratings of 87.5 - 89.4 for 100% of his homes. They feature SEER 13 air conditioning, double pane vinyl frame with low-E glass (SHGC of .34), air handler in conditioned space, R-30 ceiling and R-13 wall cellulose insulation. A few homes had ducts in conditioned space.

#### **Stylecrest Sales (Coleman HVAC Systems)**

Stylecrest Sales, formerly called Coleman HVAC Systems, is a major provider of mechanical system components to the manufactured housing industry. IN helping various home manufacturers resolve duct leakage issues, BAIHP has worked extensively with the engineering staff at Stylecrest to resolve such problems as dimensional coordination of duct components, assembly procedures, and standards in duct joining recommendations.

BAIHP researchers also met with Stylecrest Sales to discuss Energy Star plant/home certification procedures and collected cost data for a variety of HVAC system sizes. In 2004, FSEC visited a moisture damaged home in Port Fouchon (LA) at the request of Stylecrest that was built by Southern Energy Homes using Stylecrest components. (See Section III, Research, Moisture Damaged Homes.)

#### **Timeless Construction**

Long Island, New York Technical Assistance by BAIHP Researchers Subrato Chandra and Dave Chasar

This custom builder planned to build a large energy efficient custom home in New York with photovoltaic (PV) grid-connected panels. Discussions began on optimizing electrical energy use and including solar water heating panels for household water. The builder planned to use gas appliances wherever possible and a floor radiant heating system (pump energy is one-third that for a fan air distribution system). FSEC recommended a solar water heating system with gas backup and forwarded information on two solar water heater designs available from Duke Solar. FSEC also provided several choices in heat recovery ventilator (HRV) units which would provide 200 CFM of outside air.

New construction drawings were received and EnergyGauge USA analysis results were discussed with the builder and Alten Design, since PV grid-interconnect requirements and architectural changes were needed to accommodate the PV panels. FSEC's PV group laid out a 7 kW PV system that included 4.5 kW's of flat roof panels (unique for a residential application) and sent information to the architect. This activity ended in 2002 with no home construction.

# **Tommy Williams Homes**

Gainesville, FL

Category A, 19 Homes completed, 231 pending

This builder has gone from Florida energy building code minimum homes to being committed to build over 250 homes in two new sub-divisions that meet the BA goal of a HERS score of 88.6 or above. Each home will be serviced with a "right-sized" Seer 14 heat pump with a variable speed air handler, double pane low-E windows with a SHGC of .36 or less, passive OA system and a programmable thermostat. Each home will be performance tested and commissioned.

# **Top of the World Retirement Community**

Gainesville, Florida

Category B, 212 Homes

Technical Support by BAIHP Subcontractor: Florida H.E.R.O.

Florida H.E.R.O. worked with project managers in charge of *On Top of the World Central*, a retirement community in Ocala developed by Sidney and Kenneth Colen who have built 15,000+homes for senior citizens and have a commitment to developing communities that meet the needs and desires of that unique population.

Project managers of *On Top of the World Central* have every home performance tested for duct and whole house air tightness. Other features of the homes are summarized in *Table 19*.

This is the largest plotted sub-division in Florida, with over 24,000 homes slated to be built. Top of the World has gone from code minimum construction to Energy Star.

**Table 19 On Top of the World Characteristics** 

Component	Specification
Conditioned area	1120-2093 sq. ft.
HERS Score	86-89
Mechanical and System	Engineered and right sized systems
	Engineered duct design
Heating	Standard 80% AFUE furnace
Cooling	SEER 12 AC
Ducts	Mastic sealed and tested
Duct Leakage	CFM25 <sub>OUT</sub> < 5% of AHU flow
Wall	Block with steel interior framing
Windows	Double pane

# **Trinity Construction Corporation**

Coral Springs, Florida

Trinity Construction Corporation is a large shell contractor serving Florida homebuilders. Faced with increasing demands for higher quality, lower cost and more timely delivery, Trinity is actively exploring innovative alternatives to conventional concrete block construction, the predominant homebuilding technology in the central and south Florida market. Trinity operates a pre-cast concrete panel production facility, in South Bay, Florida where concrete panels are pre-cast (Figure 29), transported to the construction site, and quickly assembled using a construction crane (Figure 30). The UCF Housing Constructability Lab (HCL) was asked to assist Trinity in improving the current panelizing process by incorporating lean production principles such as "just in time" materials handling.

Preliminary research involved extensive observation and analysis. Value stream mapping, a process to isolate waste and production efficiency opportunities, identified activities that contributed value to the customer as well as activities that added little or no value. Material handling and rework were primary contributors to the 47% of labor consumed by non-value added activities. Once construction started, the flow of value-added



Figure 29 Panel forms on forming bed.



Figure 30 Setting pre-cast concrete wall panel.

activity was routinely interrupted. Poor access to materials and tools, rework, ill-defined process flows, and workforce/1<sup>st</sup> line supervision issues were contributing factors. To address these issues, BAIHP researchers utilized lean production principles - challenging non-value added activities and removing the obstacles to continuous production flow. Recommendations addressed issues of organization/communication, structured procedures and work flow, material handling, and off-line sub-assembly.

Table 20 Panel	Productivity in	Square Foot of	Wall per I	Labor Hour
----------------	-----------------	----------------	------------	------------

Process	"Tested	Potential	Pilot	Productivity
Phase	Sample"	Process Results	Test Process	Increase During Test
	Process			<del>-</del>
Layout	53	152	91	72%
Prep	52	149	79	52%
Pouring	146	211	296	103%
Lifting	75	440	75*	0%
Total	17	49	25	47%
*Not altered during pilot test.				

To test the recommendations, Trinity allowed BAIHP researchers to perform a 3-day pilot test. The test involved a single house consisting of 25 panels. The panels had a total of 21 window and door openings and a gross wall area of 3,119 ft². The first day was used to organize and train the test production team. The second and third days were dedicated to production. All 25 panels were produced. Productivity increased (*Table 20*) for all observed activities. Lifting productivity was not observed. Conservatively assuming that lifting activity will remain at historical levels, overall labor productivity increased by 47% during the Pilot Test. If lifting productivity is assumed to increase at the average rate observed for the other activities, overall productivity increase of the Pilot Test would be 68%. Not all recommendations could be realized during the test. Some equipment and personnel issues could not be resolved on a short-term test basis. This suggests that the true potential is significantly greater than that observed during the Pilot Test – possibly approaching 200% increase in labor productivity. Corresponding cycle time reductions are estimated to be 20-25%.

The BAIHP research team recommended that Trinity precede with implementation of the lean production recommendations. In addition to the technical recommendations, the research team also made recommendations involving worker empowerment, dealing with the heat and sun, and material/equipment availability. Potential future research areas include covers for the production area, on-site factories in new home developments, and factory installed wall insulation. This successful pilot test has given Trinity the opportunity to develop a competitive advantage in the housing construction market and a solid foundation to gain dominance.

# Vincent Village

Richland, Washington

Vincent Village is a 49 home rental community, located in Richland, WA. All of the homes are small, single section HUD Code homes, heated and cooled by Insider heat pumps. Half the homes were built to Super Good Cents standards, the other half were not. Metered utility data indicate average yearly savings of \$241 for the SGC homes. (See also *Appendix D*, *WSU*)

#### WCI Communities, Inc.

Palm Beach Gardens, Florida

Category A, 1 House

Technical Support by BAIHP Researcher Eric Martin

Awards: 2004 SEBC Green Demonstration Home Aurora Award

2004 SEBC Green Production Home Aurora Award 2004 SEBC Green Home Grand Aurora Award

2004 Energy Value Housing Award, Silver Medal, Custom /Hot-Humid Climate

During the fourth budget period, in November of 2002, BAIHP staff members were planning to meet with WCI to discuss a partnership. Because of their corporate environmental mission, WCI plans to build a significant number of homes to the Florida Green Home Designation Standard and has requested the help of Building America to ensure a systems engineering approach, to conduct efficiency monitoring, and to offer staff training. WCI constructs approximately 2,000 homes per year across south Florida. In 2002 they committed to having houses incorporate a variety of green principles. In some WCI communities, every home will meet the Florida Green Standard.

FSEC received sample home plans and conducted an energy analysis using EG USA. Recommendations were adopted by WCI (*Table 21*) for a model "green home" in the Evergrene Community (*Figure 32*) in Palm Beach Gardens (FL). BAIHP monitored progress on the prototype and installed monitoring instrumentation in April 2003 (fifth budget period).

The home and the instrumentation were completed in August 2003. A device called WebDAQ was installed, which acts as a server to provide an internet web page to display real time data as part of WCI's community education approach. WCI maintains a website dedicated to the home at www.greengeneration.org.



Figure 32 WCI Home in Evergrene Community, Palm Beach Gardens (FL), HERS Score = 92.

In September 2003, WCI held a grand opening at Evergrene. Staff from BAIHP and the DOE Atlanta Regional Office attended the event which included tours of the home and a program of distinguished speakers such as local government and business leaders.

This prototype "green home" received the highest score to date on the Florida Green Home Designation Standard. With a HERS score of 92, it is estimated to save 31% compared to the Building America benchmark home and 38% compared to the HERS reference home on a whole house basis.

In February 2004, FSEC staff visited the Venetian Development in Venice, FL developed and built by WCI Communities, Inc. Over 1,000 homes will be constructed in Venetian, and all will meet the requirements of the Florida Green Home Designation Standard.

Table 21 WCI Evergrene Community - Green Home Model Specifications

Conditioned Area	1460 sq ft		
HERS Score	92		
Envelope			
Above-grade Wall	ICF - first floor; 2X6 with Icynene - second floor		
Attic	Unvented, insulated at roof deck w/Icynene		
Roof	Tile		
Windows	Laminated Impact Resistant with SHGC = 0.42		
Equipment			
Ducts	Sealed with mastic; Located in unvented (Insulated) attic		
Heating & Cooling	Variable speed SEER 15 with strip electric heating		
Thermostat	Programmable thermidistat		
Water Heater Conventional gas unit with EF=0.62			
Lighting	CFL and fiber optic lighting with occupancy and daylight sensors		
Appliances Energy Star			
Indoor Air Quality	y Extensive VOC source control through paint, cabinet, and counter top selection		
Ventilation Passive fresh air duct to mechanical closet; Whole house filtration with UV sterilization			
Green Features			

**Table 21 WCI Evergrene Community - Green Home Model Specifications** 

Lumber	All lumber certified sustainable, treated lumber is ACQ, other lumber is engineered		
Water Conservation	Dual flush toilets, automatic faucets, drought tolerant landscape, micro irrigation, rainwater harvesting.		
Resource Efficiency	Eco-friendly flooring and finishes Construction waste management plan		

In addition, WCI constructed another "ultra green" model. WCI consulted BAIHP during the initial planning stages, and this home was expected to have higher performance and contain more green features than the Evergrene Community home. WCI took the initiative to develop in-house expertise and capabilities in this area and needed much less support from BAIHP. BAIHP did involve IBACO, another BA Team, to help develop an advanced lighting design.

# III BAIHP Research

# BAIHP RESEARCH OVERVIEW

BAIHP conducts research with Industry Partners in manufactured and site built housing and using the laboratory facilities at the Florida Solar Energy Center.

# Research Context for Hot-Humid Climate

The primary opportunities for improving energy efficiency can be generalized into two categories: increasing equipment efficiency and reducing equipment loads. The latter of these contributes to improving comfort, durability, and indoor air quality also.

In hot humid regions, the primary building energy use (Figure 33) is air conditioning (AC) with heating making up only a small portion of total. As in other climates, water heating constitutes the second largest residential energy draw. Refrigerators follow just ahead of other household appliances such as stoves and dryers.

The primary loads on residential AC systems (Figure 34) are appliance generated heat, window radiant heat gain, attic and duct related heat gain, infiltration (primarily latent heat gain), and wall heat gain coming in last.




Figure 33 Distribution of Residential Energy Consumption measured in 171 Florida homes shows typical energy profile for homes in hot-humid climates. Source: Parker, D. S., 2002. "Research Highlights from a Large Scale Residential Monitoring Study in a Hot Climate." Proceedings of International Symposium on Highly Efficient Use of Energy and Reduction of its Environmental Impact, pp. 108-116, Japan Society for the Promotion of Science Research for the Future Program, JPS-RFTF97P01002, Osaka, Japan, January 2002. (Also published as FSEC-PF369-02, Florida Solar Energy Center, Cocoa, FL.)




Figure 34 Typical components of annual residential cooling load in hot-humid climates.

Source: Florida Solar Energy Center web site: http://www.fsec.ucf.edu/bldg/fyh/priority/Index.htm

By systematically evaluating the savings potential technologies and construction techniques, research provides the home building industry with vital information needed to meet the Department of Energy's industry challenges of building high performance homes. BAIHP Research presented here is grouped into three categories:

- Manufactured Housing Research
- Site Built Housing Research
- Field and Laboratory Building Science Research.

# A. Manufactured Housing Research

BAIHP has found that using the systems engineering approach to help Industry Partners solve building science related problems develops a strong working relationship and increases the likelihood of the Partner incorporating concepts central to achieving Building America goals such as sealed and tested ducts, right sizing air conditioning, and moisture management. BAIHP's work with the manufactured housing industry illustrates this principal.

BAIHP conducted research for manufactured homes in both field and laboratory which is reported in the following summaries:

- Building Science and Moisture Problems in Manufactured Housing
- BAIHP Field Visits to Moisture Problem Homes
- Manufacturers Participating in Building Science Research
- Side By Side Study Of Energy Use And Moisture Control Comparing Standard Split System Air Conditioning And A Coleman® Prototype Heat Pump, Bousier City, LA
- WSU Energy House
- Zero Energy Manufactured Home (ZEMH)
- Manufactured Housing Indoor Air Quality Study
- Manufactured Housing Laboratory Ventilation Studies
- Manufactured Housing Energy Use Study, North Carolina A&T
- Portable Classrooms
- Duct Testing Data from Manufactured Housing Factory Visits

# **Building Science and Moisture Problems in Manufactured Housing**

Papers:

Subrato Chandra, Danny Parker, David Beal, David Chasar, Eric Martin, Janet McIlvaine, Neil Moyer. Alleviating Moisture Problems in Hot, Humid Climate Housing. Position Paper for NSF Housing Research Agenda Workshop, UCF Feb. 12-14, 2004.

Moyer, N., Beal, D., Chasar, D., McIlvaine, J., Withers, C, & Chandra, S. (2001). "Moisture Problems in Manufactured Housing: Probable Causes and Cures." ASHRAE - IAQ 2001 Conference Proceedings, San Francisco, CA.

Manufactured homes have a permanent steel chassis attached below the floor and are constructed in a factory (*Figure 35*) to meet a national code maintained by the U.S. Department of Housing and Urban Development (HUD). After production, homes may travel a few hundred miles, hauled by truck, before final setup. The homes are setup by placing blocks under the steel I-beams and anchoring the beams firmly to the ground. A skirting covers the blocks and steel frame in a fully setup home (*Figure 36*).

Manufactured homes are typically heated or cooled by a system of ductwork, which delivers hot or cold air from the air handler unit (AHU). The ductwork can be in the attic or in the belly cavity of the home. The ducts are typically made of aluminum or fiberglass trunk lines which supply air to the floor registers through in-line boots or flex ducts. The boots or ducts terminate at perimeter registers on the floor. Supply duct leaks represent one of the biggest causes of moisture problems in manufactured homes. (Figures 37 and 38). Poor design and construction leave holes at the AHU connection to the main trunk, and where the boots connect to the trunk, supply registers, end caps, cross-over duct



**Figure 35** Palm Harbor HUD Code Manufactured Housing factory – production line.



Figure 36 Completed HUD Code Manufactured Home, Palm Harbor Homes

connections, and other connection points. When the AHU blows air, some air leaks into the belly and eventually to the outside through belly board tears. This loss of air creates a negative pressure inside the house and a positive pressure in the belly. The negative pressure pulls outside or attic air into the house through cracks and crevices which connect the inside of the house to the outside or to the attic. During northern winters, this outside air is cold and dry and its entry increases occupant discomfort and heating energy use.

During summer in the Southeastern US, the air is consistently at or above the dewpoint of 75. If a homeowner keeps their home thermostat set below this 75 F dewpoint, the moisture laden outside air condenses as it comes into contact with the cold inside surfaces. If it condenses behind an impermeable surface such as vinyl flooring or wallpaper, serious mold, mildew, and floor buckling problems can result.




Figure 37 Pressure field and unintentional air flow created by supply duct leaks.

Many manufactured and site-built homes have only a single return and, therefore, very little return air transfer from the bedrooms (basically via the undercut at the bottom of interior doors). When interior doors are closed, rooms off the main body (e.g., bedrooms) become pressurized and the main body of the house depressurizes. Even though negative pressures are usually only one to three pascals (Pa) - they can cause serious problems in a home.

Researchers use a calibrated fan called a ductblaster to measure duct leakage. The ductblaster is attached to the return grill or the crossover duct opening (*Figure 39*) and all supply registers are masked off and the fan is turned on. Once the house ductwork reaches –25 Pa, airflow through the fan is read (in CFM). The resultant measure is the total duct leakage. In good airtight ductwork, total duct leakage (CFM@25 Pa) should be less than 6% of the homes square footage.




Figure 38 Cross section showing foundation support, crossover duct, and one type of ventilation system in a manufactured home.

A second duct leakage test measures leakage to the outside. This leakage is calculated by depressurizing the entire house to -25 Pa with a blower door, then adjusting the ductblaster flow so there is no pressure difference between the house and the ducts. This measurement is a true indicator of duct air loss to the outside and is used in energy calculations for estimating the energy loss from leaky ducts. In good duct systems, duct leakage to the outside (in CFM) is less than 3% of the home's square footage.




Figure 39 Floor and belly area with supply ducts. These ducts supply conditioned air to all rooms through floor vents, a common duct system layout in manufactured homes.

The battery of tests run in a problem house typically includes measuring the airtightness of the house with a blower door, depressurizing the house to -50 Pa. At that time, the house to belly and belly to crawlspace pressures also can be measured. Researchers also test pressure differentials caused by AHU operation and closed interior doors. An additional measurement of duct leakage, called pressure pan, is conducted on some houses to pinpoint specific registers which might have large leaks. In this measurement the house is first depressurized to -50 Pa and all the register vents are unmasked. Then the registers are covered one by one and the pressure difference between the covered register and the house is measured. A zero reading indicates no leakage at that register. Readings over one Pa indicate a sizeable leak that should be repaired.

#### **BAIHP Field Visits to Moisture Problem Homes**

Papers: Moyer, N., Beal, D., Chasar, D., McIlvaine, J., Withers, C, & Chandra, S. (2001). "Moisture Problems in Manufactured Housing: Probable Causes and Cures." ASHRAE - IAQ 2001 Conference Proceedings, San Francisco, CA.

A significant number of new manufactured houses built to HUD code and located in the hot, humid Southeast have exhibited moisture problems. Soft wallboards, buckled floors, damaged wood molding, and extensive mold growth are the most common symptoms. These problems do not respond to the standard service and repair strategies for water intrusion. (Please see Appendix B for sample problem home inspection trip reports.)

# Summary of 1<sup>st</sup>-4<sup>th</sup> Budget Period Field Visits to Moisture Problem Homes

At the request of six manufacturers, 69 such moisture damaged homes were investigated from 1999 to the end of reporting year four (through March 31, 2003) to determine likely causes. In Year 4 alone, 18 homes were investigated by FSEC. One-time blower door, duct tightness, and pressure differential measurements were performed on all homes. Field data on ambient, crawlspace, belly and house temperatures, plus relative humidity levels were collected on a few of the homes. Recommendations and reports were prepared for the manufacturers' service, production, and design staff. Field repairs were performed in most of these homes. A general theme was found in the houses investigated.

- Air conditioner thermostat settings (typically 68 to 73 F) set below the ambient dew point.
- Negative pressures across the envelope from high supply duct leakage (CFM @25Pa >10 per 100 square feet of conditioned floor area), inadequate return air paths, interior door closures, exhaust fans, or a combination thereof.
- Inadequate moisture removal from disconnected return ducts, continuous fan operation (air handler or ventilation), inadequate condensate drainage, oversized air conditioners, or a combination thereof.
- Moisture diffusion from the ground into the house because of poor site drainage, inadequate crawl space ventilation, tears in the belly board, or a combination thereof.
- Vapor-retardant in the wrong location (i.e., vinyl or other impermeable wall or floor coverings located on the colder surfaces).

Recommended solutions provided to the manufacturers to eliminate moisture problems included:

- Maintain air conditioning thermostat settings above the ambient dew point (at least 75 F).
- Eliminate long-term negative pressures created by air handler fans or ventilation equipment.
- Tightly seal all ductwork and provide adequate return air pathways.
- Enhance moisture removal from the conditioned space by correct equipment sizing and maintenance.
- Eliminate ground source water and provide an adequate moisture barrier for the floor assembly.
- If possible, remove vapor barriers located on the wrong surfaces.

Research continues to determine if these steps will be sufficient to prevent problems even when vapor barriers are incorrectly located in homes in the hot, humid climate. Preliminary results are encouraging. One manufacturer has not reported a single new moisture problem in any of the homes produced since 2000 in a factory that previously had a significant number of problem homes. Steps taken by the factory were inclusion of airtight duct systems (a zero net-cost increase), right-sized cooling systems (a negative cost), return air ducts from all bedrooms (a cost of about \$15), installation of a ground vapor barrier (no change from previous practice).

# <u>Summary of 5<sup>th</sup> Budget Period Field Visits to</u> Moisture Problem Homes

BAIHP researchers at FSEC received fewer requests in the 5<sup>th</sup> budget period for assistance with moisture damaged homes (Table 22), reflecting improvement of duct construction and sealing, addition of return air pathways from bedrooms, and reduction of vapor impermeable interior surfaces. Additionally, service personnel who have attended BAIHP training and participated in field work with BAIHP are more prepared to resolve problems without assistance. Service personnel report installing passive return air vents in bedrooms, providing appropriate moisture barriers, and sealing duct leaks to resolve humidity, comfort, and moisture damage call backs.



"tide line" on the support column.

When service personnel have been unable to resolve a problem, they request assistance from BAIHP researchers who attend a service call and conduct various diagnostic tests to identify factors contributing to the moisture, comfort, or high energy bill problem. (MHRA has been providing similar services on a fee basis to the industry also.) After BAIHP researchers complete a field visit, a trip report is issued detailing the findings and recommendations, include basic building science background material.

Table 22 5 <sup>th</sup> Budget Period – FSEC Field Visits				
to Problem Manufactured Homes				
Manufacturer	Location	Date		
Fleetwood Homes	Florida (2 homes)	August 03		
	Florida (2)	November 03		
	Texas (1)	December 03		
	West Virginia (1)	March04		
Cavalier Homes	Florida (1)	November 03		
Southern Energy Homes	Kentucky(1)	December 03		
	Texas (1)	January 04		
Style Crest	Louisiana (1)	February 03		
20 NIEEM Brogram	Field Visits in			
20 NEEM Program Manufacturers	Washington, Oregon,	April 03-March 04		
Manufacturers	and Idaho (19)			
<b>Total Homes</b>	29			

It has been BAIHP's experience that corrective measures from repeated moisture problem Diagnostics have been incorporated into the production process, resulting in thousands of improved manufactured homes. These are noted in Category D of Table 2.

A common problem that remains unresolved involves the combination of abundant crawl space moisture (Figure 40 and 41) and poorly vented skirting (Figure 42). In the hot-humid coastal

regions, this combination raises vapor pressure across the belly to critical levels. This was evident in several of the homes visited this year. As a result of this field research, BAIHP has designed a study that will be initiated in the summer of 2004 to evaluate the moisture flow characteristics of crawl space conditions.

# WSU Field Visits to Problem Manufactured Homes

In offering technical support to owners of over 100,000 homes built since 1990, the BAIHP staff in the Northwest answers questions from homeowners, manufacturers, retailers and others. In

The 5th budget period, staff from Washington, Oregon and Idaho responded to over 90 phone calls and conducted 19 field visits. The number of field visits to problem homes has significantly decreased over the history of the program, in large part because of manufacturers' and installers' increased adoption of the NEEM Super Good Cents/Energy Star (SGC/E-Star) specifications which include duct air tightness specifications (duct leakage is a major contributor to pressure and air flow related moisture problems), and the requirement that manufactured home installers be certified in Washington and Oregon.

BAIHP staff participated in quarterly meetings of the Washington State Manufactured Housing Technical Working Group, which coordinates the certification of manufactured housing set-up crews.

While butyl duct tape is no longer allowed under current NEEM SGC/E-Star specifications, a consistent issue in the field continues to be excessive duct leakage, due in large part to failures of duct tape. These findings were brought to the attention of the NFPA-501 Manufactured Housing Standards Committee, resulting in a successful proposal to revise the duct sealing specifications to eliminate the use of duct tape in favor of better performing mastic and fiberglass mesh in the NFPA-501 standard. See a summary of supporting research findings in BAIHP Duct Data Compilation.



flow pattern away from house.



Figure 42 HUD Code required perforations in skirting may not allow adequate volumes of ventilation, creating higher than usual vapor pressure difference across the floor assembly even though the ground cover and belly board are in good condition.

### Manufacturers Participating in Building Science Research

### Blue Sky Foundation

Blue Sky Foundation, in coordination with FSEC, conducted an evaluation of energy efficiency and the moisture damage potential in 16 North Carolina homes in the summer of 2001. Blue Sky foundation proposed that the energy and moisture evaluation focus on the building envelope integrity, HVAC duct systems, and the moisture impact of unvented space heaters. All of the homes in the study were manufactured models located in Carteret and Craven counties, each located on the North Carolina coast. Field teams gathered additional energy and moisture information from homeowners.


Only three of the 15 tested homes recorded moisture and/or mildew problems. Because of the small sample size, the results are mostly anecdotal and would need to be evaluated within a larger data set. Planning for this is underway. Data from the summer field program as well as the final report are now on the BAIHP website (<a href="www.baihp.org">www.baihp.org</a>) under *Publications*.

#### Cavalier Homes

BAIHP visited one Cavalier Home in Florida for a moisture damage investigation in response to home owner complaints of persistent air flow problems and floor damage. BAIHP made recommendations to correct the installation of the duct system and supply registers, repair the rodent barrier to make it air tight, do site work to reduce flooding under house, place a ground cover if site work done, increase crawl space venting, and replace damaged flooring with plywood.

Fleetwood Homes
During the 5<sup>th</sup>
budget period,
BAIHP continued
to support
Fleetwood's
service department
making six visits
to moisture
damaged homes in
Florida (4), Texas
(1), and West
Virginia (1).

Six Fleetwood homes, all in Florida, were tested for moisture and mold damage from April 2002 through March 2003, the 4<sup>th</sup> budget period. All of the homes had



**Figure 43** Testing Results from Fleetwood Homes Plant in Alma, Georgia illustrate that tape sealed ducts can result in total duct leakage under Qn = <6%. This initial tightness, however, is often eroded by adhesive failure.

damaged flooring due in part to a lack of ground cover and poor crawlspace ventilation. Damage to the floor in one home was exacerbated by a plumbing leak. Only one home had moisture damage to the wallboard material, and this home showed a history of thermostat settings below 72 F. A report for each home was submitted to Fleetwood for corrective measures. One additional high bill complaint in Cobb, Georgia was investigated during this reporting period.

In 2002, four Fleetwood factories in Southern Georgia were visited to investigate possible causes of moisture related building failures found in homes installed in hot, humid climates. The factories were located in Douglas, Alma, Pearson, and Willacootche. (*Figure 43*.)

# Homes of Merit

In 2002, researchers performed multiple diagnostic tests on a home located in Marathon,




Figure 44 Wall assembly used in moisture transmission experiment.

Florida that was experiencing "mold problems." Researchers determined that the mechanical system was significantly oversized and that the home was operating under negative pressure when the system was operational. The home's owner exacerbated humidity problems by leaving the fan in the "on" mode. On-site relative humidity readings showed that indoor and outdoor relative humidity were the same, approximately 70%.

### Palm Harbor Homes

(See also, Palm Harbor Homes in Section I, Technical Support).

Palm Harbor Homes, James Hardie®, and FSEC performed two separate drywall assembly tests to determine the cause of some moisture damage occurring in homes sheathed with Hardipanel. Hobo dataloggers recorded temperature and relative humidity measurements inside the assembled panels on eight different wall panel configurations. (*Figure 44*)

Results determined that the unprimed, unwrapped sheathing performed best. The painted drywall assemblies allowed the greatest moisture movement - or wall assembly drying. (*Table 23*) The vinyl-covered drywall held moisture longest, recording the slowest drying time. Adding perforations to the vinyl reduced the drying time.

Table 23 Hardipanel exterior wall configurations									
Test Panel	Drywall	Insulation	Wall Wrap	Sheathing					
#1	vinyl	unfaced	none	primed					
#2	vinyl	unfaced	none	unprimed					
#3	vinyl	unfaced	house wrap	primed					
#4	perforated vinyl	unfaced	none	primed					
	House wrap glued to								
#5	drywall	unfaced	house wrap	primed					
#6	vinyl	unfaced	Thermo Ply	primed					

Table 23 Hardipanel exterior wall configurations									
#7	painted	unfaced	none	primed					
#8	painted	unfaced	none	unprimed					

In 2002, two Palm Harbor homes with comfort problems were tested in Ocala and Okahumpka, Florida and one high bill complaint was investigated in Odessa, Florida. Duct leakage testing and infrared imaging revealed a duct disconnect near the attic crossover in the Ocala home. Inspections with the IR camera found no insulation problems in the Odessa home. Ductblaster and blower door tests revealed airtight duct and envelope systems. Other than an oversized air conditioning system, there were no obvious reasons for the high bills.

# Southern Energy Homes

(See also, Southern Energy Homes in Section I, Technical Assistance.)

During Year 2001, 12 homes were field tested in the Houma, Louisiana area. Some of the homes had new moisture damage. Others were rechecks of previous moisture problems already repaired by SEH personnel. FSEC inspectors reported improper repairs and recommended additional dealer and staff training. An additional five homes were field tested in Houma during the 4th reporting period, with another home in Mississippi and one in Alabama also field tested.

During the 5<sup>th</sup> budget period, BAIHP visited two Southern Energy Homes in Texas (1) and Kentucky (1).

Side By Side Study Of Energy Use And Moisture Control Comparing Standard Split System Air Conditioning And A Coleman® Prototype Heat Pump, Bousier City, LA Research led BAIHP Researchers Dave Chasar, Neil Moyer, and Chuck Whithers

Papers:

Withers, C., Chasar, D., Moyer, N., and Chandra, S. "Performance and Impact from Duct Repair and Ventilation Modifications of Two Newly Constructed Manufactured Houses Located in a Hot and Humid Climate", Thirteenth Symposium on Improving Building Systems in Hot and Humid Climates, May 20-22, 2002 Houston, Texas.

In 2001, the BAIHP team conducted research on two homes to define how tight ducts and a prototype Coleman® heat pump (proprietary technology) affect energy use and moisture control in a hot, humid climate. FSEC, in collaboration with Fleetwood Homes, York International Manufactured Housing Division (now Stylecrest Sales), and Coleman®, monitored two nearly identical side-by-side homes in Bossier City, Louisiana. The homes contained different air conditioning systems. House A used a standard split air conditioner, while House B used the Coleman® prototype unit (a more efficient, two-speed split air conditioner).

Figure 45 shows the reduced power draw of the two-speed compressor (green, dotted line) over a 24-hour period on September 2, 2000. With the unit operating at low-speed for most of the day, the cooling energy savings were 28% when compared to the energy use in House A. Average daily cooling energy was reduced by about 12% over the monitored period. An added benefit of the two-speed air conditioner was 20% greater moisture removal on days with an outdoor dewpoint above 60 F.




Figure 45 Power draw over a 24-hour period, September 2, 2000.

Savings from Duct Repair and POS Ventilation: In addition to comparing one house to the other, the BAIHP team also compared home performance before and after ductwork and ventilation system changes were made.

To make the comparison, duct and other leaks were sealed in both houses until the two were equally airtight. The ventilation method in each home also was changed from exhaust-only to a positive pressure system (POS). With exhaust-only ventilation, bathroom fans removed stale air from the home which caused fresh air to be pulled in through the building envelope. To simulate occupant use, two bath exhaust fans were operated by a timer for three hours in the morning and six hours in the evening.

In contrast to exhaust ventilation, the POS system introduced a small amount of fresh air on the return side of the air conditioning cooling coil. A POS system was installed in each home at the same time the ducts were repaired. Subsequent monitoring looked at the effects of this alternate ventilation system. Tightening the ducts and installing a POS ventilation system resulted in an 18% and 37% cooling savings in the two homes. Only about 2% of these savings were attributable to the ventilation system change, the remaining savings are a result of duct repair.

### **WSU Energy House:**

Olympia, Washington

Technical Assistance by BAIHP Contractors Washington State University Energy Program, Oregon Office of Energy and Idaho Department of Water Resources, Energy Division

This 2600 ft<sup>2</sup> home was built beyond SGC standards and incorporates Energy Star lighting and appliances. The home (*Figure 45*) has received significant national exposure through WSU campus and alumni newsletters, tours, the BAIHP website, and local and trade media including an article in the Automated Builder magazine and a feature by KING 5 News of Seattle.

WSU staff uses the house to try out innovative technologies and testing methods.

In the 5th budget period, BAIHP staff developed a moisture case study based on research at the WSU Energy House, published under a separate Building America project. The WSU Energy House has been monitored since 2000. Collected monitoring data includes weather, temperature, humidity, CO<sub>2</sub>, CO, and eight differential pressures. Energy use data is being collected for water heating, laundry, fireplace and heating, ventilating, and air conditioning (HVAC). Data from the house is available on the BAIHP web page (under Current Data) and has been presented to the building science, indoor air quality (IAQ) and HVAC research communities at conferences sponsored by ASHRAE, Air



Figure 45 WSU Energy House in Olympia, WA

Infiltration and Ventilation Center (in the UK), HUD/NIST, NFPA, and BTECC. (See also *Appendix D, WSU*)

Working with Ecotope, ASHRAE, and the Energy Conservancy, BAIHP staff conducted "Delta Q" and "nulling" duct leakage tests in 2001. Follow up pressure tests and analysis of test data conducted in 2002 indicate these tests are effective methods of measuring duct leakage in manufactured homes, and may be included in the upgrades to the National Fire Protection Association-501 standards for manufactured homes.

Blower door and duct leakage testing indicate very good whole house and duct airtightness (2.4 ACH50 and 61.6 CFM50<sub>out</sub>). Tracer gas testing demonstrated that the use of a furnace-based intake damper does not change the leakage rate of the home.

# **Zero Energy Manufactured Home (ZEMH)**

Nez Perce Fish Hatchery, Idaho Category A, 1 home

BPA, working with BAIHP staff in Idaho and Washington, provided funding for the most energy efficient manufactured home in the country. The RFP was sent to 18 Northwest manufacturers; Kit HomeBuilders West of Caldwell, Idaho was selected as the manufacturer of the home. BAIHP staff solicited 24 industry partners to provide energy efficient building



Figure 46: Zero Energy Manufactured Home, on site at the Nez Perce Fish Hatchery

components, including Icynene wall, floor and roof insulation, a low-cost HUD-approved solar system, sun-tempered solar design, and Energy Star© windows, appliances and lighting. Partners include Building America Team members such as Flexible Technologies, Icynene and LaSalle. Complete list of specifications provided in *Table 24*.

The ZEMH (*Figure 46*) was built in Year 4 along with a control home. The ZEMH was displayed at the 2002 Spokane County Interstate Fair before siting at the Nez Perce tribal fish facility near Lewiston Idaho. Blower door and duct leakage tests at the plant and on-site indicate that this is the tightest home ever tested by BAIHP staff.

Working with FSEC and BPA, BAIHP staff installed monitoring equipment for the ZEMH. Monitoring began in the 5th budget period and includes the following:

- Total electric use from grid
- Resistance elements in heat pump
- Heat pump compressor and fan motors
- Water heating equipment, including gallons used
- PV energy production (ZEMH)

TABLE 24 Zero Energy Manufactured Home (ZEMH) and Base Case Home (Control)

Component	ZEMH	Base
Wall Structure	2x6 ft, 16 in on center	Same
Wall Insulation	R21 foam-spray	R21 batt
Floor Structure	2x8 ft, 16 in on center	Same
Floor Insulation	R33 (R22 Foam + R11 batt)	R33 Blown Cellulose
Vented crawl space wall	R14 foil faced foam	None
Roof/Attic Structure and Finish	16 in on center 40 lb roof load 4/12 pitch metal roofing	24 in on center Standard 30 lb roof load Same pitch and finish
Roof/Attic Insulation	R49 foam	R33 blown cellulose
Window/Floor area ratio	12%	Same
Windows	Vinyl Frame, Argon filled, low-e, Energy Star Approved	Same
Window Shading	Dual blinds, heavy drapes, awnings	Single blinds, light drapes
Doors	U=0.2 metal, foam w/thermal break	Same
Solar	Solar ready design (mounts, flashings and electrical chase) 4.2 kW peak rated PV system with a 4 kW inverter and 12 kWh battery array	None
HVAC	2 ton unitary air-source heat pump 12 seer, 7.8 HSPF	Same
Zone heat	150 W Radiant Panel in kitchen	None
Ducts and cross over	R8 crossover Flex Flow crossover system Mastic with screws More efficient duct design	R8 crossover Sheet metal elbows Standard foil tape
Lighting	100% Energy Star T8 and CFL fixtures	T12 and Incandescent fixtures
Appliances	Energy Star washer and dryer, refrigerator, dishwasher	Standard equipment
Whole House Ventilation	Heat Recovery Ventilator w/HEPA, continuous operation (turned off in 8/04)	Quiet (low-sone) Energy Star exhaust fan, continuous operation
Spot Ventilation	Energy Star bath fans, std. Kitchen fan	Quiet (low-sone) bath fans, std. Kitchen fan
Ceiling Fans	Energy Star with dimmable CFL	Standard with Incandescent

TABLE 24 Zero Energy Manufactured Home (ZEMH) and Base Case Home (Control)

Component	ZEMH	Base
		bulbs
Domestic Hot Water	PV controlled, active anti-freeze solar water system, with 80 gallon storage, and 64 ft <sup>2</sup> of collector area solar preheat tank (pre-plumbed), 40 gallon standard tank EF=0.93	EF=0.88 standard electric
Air Sealing	Wrap with tape flashing Marriage line gasket (new product) Penetrations sealed with foam insulation	Wrap without tape flashing Standard practice marriage line sealing
Air/Vapor Barrier	Walls and Ceiling: Painted Drywall Floor: Floor decking	Same

Data logger collects 15 minute data from wired sensors and transmits daily to the host computer at FSEC via modem. Summary data reports are available at <a href="www.baihp.org">www.baihp.org</a> under "Current Data." Plug-type loggers were installed in mid March 2003 to sub-meter the energy use of the refrigerator, freezer and clothes washer in each home, as well as the radiant heat panel and HRV in the ZEMH. Data from these loggers was collected by occupant readings in mid-December 2003

### *Preliminary findings*

Measured net energy use of the ZEMH 6% is lower than the base home, not normalized for occupant behavior. This also does not take into account the fact that the ZEMH's PV system was only fully operational for one month.

The ZEMH required 45% less space heating energy, possibly due to improved building envelope measures, and the lack of consistent HRV operation.

The measured envelope leakage in the ZEMH was 2.0 ACH50, much lower than the base home (indeed, lower than any other NEEM home tested in the field) and substantially tighter than typical HUD code homes.

The ZEMH total duct leakage was 46% lower than the base home; leakage to the outside was 405% lower than the base home. The BAIHP staff speculates that the unprecedented low leakage to the outside value is the result of the ducts in the ZEMH being located within the conditioned space, and effectively within the pressure envelope of the home, surrounded as they are by foam insulation.

The solar water heating system in the ZEMH provides most, if not all of the hot water needed during the summer months, and roughly 45% of the total hot water demand. The PV system with net metering provides 38% of the total ZEMH energy use.

The project highlights the importance of occupant choices and behavior on the performance of energy efficient housing. Based on the preliminary monitoring data and occupant surveys, the behavior patterns of the ZEMH occupants are not themselves "energy efficient". These patterns

create the appearance of a less efficient home. On the other hand, the behavior of the ZEMH occupants may shorten the payback for the innovative technologies of the ZEMH.

BAIHP staff also performed a benchmarking analysis on the ZEMH, as part of the overall benchmarking effort. The ZEMH reached a level of 60% above the NREL prototype, which indicates the difficulty of obtaining a high benchmarking score.

# **Manufactured Housing Indoor Air Quality Study**

Plant City, Florida

In the spring of 2003, BAIHP initiated a study with Palm Harbor Homes (PHH) to evaluate the energy savings from a Building America Manufactured Home, compared to a standard Palm Harbor Home.

These two homes were built in the fall and set up on PHH's model center in Plant City, Florida.

The monitoring plan called for measurements of volatile organic chemical (VOCs) levels, air conditioning energy use and associated indicators such as indoor and outdoor conditions. Both homes have split system air conditioners, SEER 15 in the BA model, and SEER 10 in the Base Case model.

The two homes were instrumented in November, however, due to a PHH phone service conflict, no data was taken during this budget period. Data collection is expected to commence in May of 2004.

VOC measurements were conducted in collaboration with LBNL. The VOC data revealed significantly higher VOC levels in the Building America home than in nearby control models of a similar age. Normally, PHH would move furniture in from a previous model, but in an effort to ensure high quality in the BA model, PHH purchased all new, all wood furniture. This is believed to be the source of VOCs in the BA model. BAIHP and LBNL researchers will work to verify what caused the elevated VOC level in the next budget cycle.

### **Manufactured Housing Laboratory – Ventilation Studies**

FSEC, Manufactured Home Laboratory

Paper: Moyer, Neil, Chasar, Dave

Moyer, Neil, Chasar, Dave, Hoak, Dave, Chandra, Subrato, "Assessing Six Residential Ventilation Techniques in Hot and Humid Climates," Proceedings of ACEEE 2004 Summer Study on Energy Efficiency in Buildings, American Council for an Energy Efficient Economy, Washington, DC, August 2004. (Also available online at <a href="www.baihp.org">www.baihp.org</a> under Current Data and Publications)

### Ventilation Study

The MHLab (*Figure 47*) is a research and training facility of 1600 ft<sup>2</sup>. This Energy Star® manufactured home has two separate heating and cooling systems:

- 1. An overhead duct system connected to a package unit air conditioner with electric resistance heating.
- 2. A floor-mounted duct system connected to a split system air conditioner, also with electric resistance heating.

Only the floor mounted duct system was used in these ventilation experiments.

#### Introduction

Ventilation is a HUD code requirement. The goal of ventilation is to add fresh air to the home. This may be accomplished by supplying outside air to the house or mechanical system, exhausting air from the house (which consequently pulls air into the house through joints in the walls, floor, and ceiling), or a combination of the two.

Supply based ventilation tends to slightly pressurize the home whereas exhaust based ventilation does the opposite slightly depressurizing the house. The disadvantage of supply based ventilation is that it forces conditioned air into the floor, wall, and ceiling cavities, possibly leading to condensation or mold growth in cold climates and during the heating season. Likewise the disadvantage of exhaust systems is that they pull unconditioned outside through the floor, wall, and ceiling cavities into the conditioned space. possibly leading to condensation, mold growth, or uncomfortably high indoor humidity levels in hot and hot-humid



Figure 47 Manufactured Housing Laboratory at FSEC (above and below) was site for study of six residential ventilation systems.



climates and during the cooling season. The six residential ventilation strategies evaluated are described in *Table 25*.

### House Operation and Experimental Procedure


Occupancy Simulation: Automated, computer controlled devices, such as appliances, showers, and lighting, simulate the sensible/latent heat generation and carbon dioxide (CO<sub>2</sub>) production of a family of four persons with periodic showers, cooking and cleaning.

The simulated latent occupancy load from breathing, bathing, cooking, and laundry was achieved by adding 14 to 15 pounds of water per day based on documentation of "average" household operation based on ORNL research conducted by Jeff Christian. Water vapor was injected into the space using a vaporizer at a rate of approximately 0.4 lbs per hour continuous and an additional 0.4 lbs per hour during the evening hours.

**Table 25 Ventilation Strategies Studied in the MHLab** 

Case (Name)	Strategy	Description
#1	No mechanical	Base Case scenario included only the heating and cooling system of the
(None).	ventilation	home with no outside air (OA) ventilation.
# 2	Spot ventilation	Bathroom and kitchen exhaust fans. Operation scheduled for 30 minutes
(Spot)	(exhaust only)	after a simulated moisture producing event such as a shower or oven use.
# 3 (OA)	Outside air (supply based)	Dedicated, filtered outside air duct to return plenum when the heating or cooling system is operating. Quantity of ventilation air provided depends on air handler run-time.
# 4 (Dehumid)	Outside Air plus 10/20 Cycle and Dehumidification (Supply Based)	Same as #3, except with an added air handler fan controller (10-minute "on" - 20-minute "off" minimum duty cycle). Provides scheduled ventilation when no cooling or heating is called for. A stand alone room dehumidifier (set to approximately 50% RH) located in vicinity of the return air grill.
# 5 (10/20 Cycle)	Outside Air plus 10/20 cycle (Supply Based)	Same as #4, except without the room dehumidifier.
# 6 (ERV1) (ERV2)	Energy recovery ventilator (ERV1, ERV2)	Two different enthalpy transfer media were used. Outside air was drawn in through the ERV at a rate to meet the ventilation requirements.
# 7 (Hstat)	Outside Air plus Humidistat (Supply Based)	This is a modified air handler fan speed control. When dehumidification is needed, the air handler fan is operated at lowest speed for enhanced latent control. A higher speed is selected when sensible cooling is needed. Ventilation air supplied via an outside air duct, with air handler fan operation controlled as in #4.

*Ventilation Rate:* Researchers conducted whole house air tightness tests using sulfur hexafluoride as a tracer gas for a decay analysis (*Figure 48*) to determine if each ventilation strategy met the ASHRAE 62-2 Ventilation Standard during the test period. The spot ventilation strategy (#2) did not meet the standard on a daily basis as the runtime was not long enough. The outside air method (#3) was marginal in meeting the standard. Strategies #4-#7 met the standard.



**Figure 48** Results of tracer gas decay testing indicating operational infiltration (house not under test pressure) rates measured for each ventilation strategy. ASHRAE Standard 62.2 was the target ventilation rate, not met by *Spot* or *OA* strategies. *Note: Wind speed averaged over 2 hour infiltration test.* 

Whole House and Duct Air Tightness: The average whole house air leakage (CFM50) was 1224 (ACH50 of 5.4). The target normalized duct leakage is  $Qn \le 6\%$ , where Qn = CFM25/conditioned area, this is the same as the duct leakage target in the Manufactured Home Energy Star program. The total duct system leakage in the MHLab  $Qn_{total} = 5\%$  (CFM25<sub>total</sub> = 75) with leakage to the outside measured to be  $Qn_{(out)} = 3\%$  (CFM25<sub>out</sub> = 45), well under the leakage target.

Interior temperature and relative humidity: A digital thermostat maintained interior temperature at 75 degrees Fahrenheit. Interior temperature and relative humidity sensors are located on the same wall as the thermostat, at approximately the same height from the floor. Dedicated interior relative humidity control was only available with the dehumidifier strategy, and was a byproduct of cooling coil operation in the other strategies.

### Cooling/ventilation power usage

With all mechanical ventilation systems, additional energy use from both increased conditioning loads and fan (if present) power is expected. The split system with the floor duct system is a 12 SEER system with a rated cooling capacity of 30.2 kBtu. The ventilation strategies that required the use of the air handler fan, an energy recovery ventilator, or the dehumidifier had the energy use added to the cooling energy. The dehumidifier strategy did use the most energy for cooling; however, it should be noted that this test occurred during the hottest ambient conditions.

Table 26 Average Ambient and Building Conditions

	Case 1	Case 2	Case 3	Case 4	Case 5	Case 6	Case 6	Case 7
	None	Spot	OA	Dehumid	10/20	ERV1	ERV2	Hstat
Indoor Temp (°F)	74.5°	74.5°	74.7°	74.9°	74.0°	74.1°	74.4°	74.8°
Indoor Temp Max (°F)	75.0°	75.2°	75.5°	76.0°	75.0°	74.9°	75.4°	76.0°
Indoor RH (%)	49.2%	45.7%	49.5%	47.9%	49.1%	47.8%	47.2%	45.7%
Indoor Dewpoint (°F)	52.4°	54.2	54.5	53.9	53.7	53.1	53.0	52.4
Outside Temp (°F)	78.6°	78.6°	78.4°	82.1°	79.8°	79.3°	80.8°	79.2°
Outside RH (%)	89.2%	79.5%	87.7%	83.4%	87.0%	90.0%	86.9%	88.1%
Δ Temp (°F)	4.3°	4.0°	3.7°	7.1°	5.8°	5.1°	6.5	4.4
Δ Dewpoint (°F)	18.6°	20.7°	19.5°	22.4°	21.4°	22.7°	23.3°	22.6°
Solar Rad. (kWh/m <sup>2</sup> )	53.5	107.3	68.9	76.3	86.8	66.3	101.9°	77.1°
Rainfall (Inches)	3.6	0.5	4.7	0.1	4.0	5.1	3.2	4.9
Condensate (lbs)	617	905	920	1131	1118	1034	1685	1282
Δ P WRT Out (Pa)	-0.2	0	0.1	0.4	0	-0.2	-0.2	0.1
Minimum RH	42.1%	38.8%	45.8%	46.2%	46.3%	44.2%	39.3%	39.7%
Maximum RH	53.3%	55.2%	53.2%	51.0%	58.4%	64.8%	53.0%	61.4%
Mean RH	46.1%	49.2%	49.5%	47.9%	49.0%	47.8%	47.2%	45.7%
RH Standard Deviation	1.272	1.471	1.673	0.845	1.231	2.194	2.108	3.07
RH Range	11.2%	16.3%	7.4%	4.8%	12.1%	20.6%	13.7%	21.7%

# **Findings**


The cooling energy required to maintain the 75°F interior set-point appeared to vary as a result of the temperature difference across the envelope (Table 26). A linear regression analysis was performed to compare energy use of the ventilation strategies as a function of temperature difference across the envelope (Table 27). The power use at the average temperature difference of five degrees Fahrenheit is shown in bold.

- Case 4, the dehumidifier system, has the highest average power at 1592 watts.
- Case 7 (humidistat controlled fan speed or Hstat) is second highest at 1485 watts.
- Case 5 (10/20 cycle controller) used the least power at 1315 watts.

As might be expected, interior relative humidity had the least variance with the dehumidification system with a low of 46% and a high of 51% (*Table 26 and Figure 49*). The best performing system, Case 4 (10/20 cycle plus dehumidifier), was able to maintain the relative humidity at a nearly constant level for almost 80% of the test period. The next best performer was Case 2 (spot ventilation). Humidity levels during the test period are graphed in *Figure 49*.

Table 27 Cooling and ventilation power (watts) usage as a function of temperature difference across the building envelope

ΔTemp	Case 1	Case 2	Case 3	Case 4	Case 5	Cas	se 6	Case 7
(°F)	None	Spot	OA	Dehumid	10/20	ERV1	ERV2	Hstat
-5	487	499	475	499	411	459	367	526
0	924	911	949	1046	863	915	880	1006
5	1361	1324	1424	1592	1315	1370	1393	1485
15	2236	2150	2372	2685	2219	2280	2418	2443



### Conclusions

The operation of a correctly sized air conditioning system with a supplemental dehumidification system to pre-condition the outside air and provide additional dehumidification of the space appears to provide the best interior humidity control (Table 26, in bold) with only a slight increase in energy usage – about 200 watts (Table 27). This is represented by Case 4 of this study. Only this strategy was able to maintain the interior humidity conditions in a range of less than 5% (Table 27, in italics).

Though all of the strategies did provide some humidity control over the test period, it is most likely a result of the run time afforded by the correctly sized air conditioning system and the consistent simulated interior sensible load. When an air conditioning system operates for extended periods of time, the removal of moisture from the air stream is enhanced (Khattar, Swami & Ramanan 1987).

Additional testing with other ventilation strategies in the MHLab will be undertaken in the next budget period.

### Manufactured Housing Energy Use Study, North Carolina A&T

Paper Pending:

W. Mark McGinley, Alaina Jones, Carolyn Turner, Subrato Chandra, David Beal, Danny Parker, Neil Moyer, and Janet McIlvaine. Optimizing Manufactured Housing Energy Use. Symposium on Improving Building Systems in Hot and Humid Climates, Richardson, Texas, May 17-19, 2004.

Side-by-side monitoring of two manufactured homes at North Carolina Agricultural and Technical State University (NCA&TSU), evaluated the value of a variety of energy saving technologies and techniques. (Figure 50 and Table 28) Home instrumentation measured energy consumption as well as interior and exterior climatic conditions. The "standard home," designed and built to basic HUD code requirements, represented the control home. Modified to use at least 50% less energy, the "energy home" met Building America standards. Cooperating researchers at NCA&TSU and FSEC investigated energy feature performance and compared actual energy used to energy modeling program predictions. In-situ energy performance data provided researchers with interesting information on both issues.

Each model contained 1,528 ft<sup>2</sup> of living area with nearly identical floor plans. Though the homes were unoccupied during the testing, home lighting and water heating use was simulated



Figure 50 Side-by-side monitoring of manufactured homes at NCA&TSU.

with timers. A datalogger in each home recorded: (1) the interior and exterior temperature and humidity along with solar radiation and wind speed, (2) the home's total power consumption, (3) the air conditioning/heat pump compressor, air handler fan, and electric resistance heater use (primary heater in the standard house, backup or emergency heater for the energy house), and (4) water heating and water usage data.

The energy house features combined higher insulation values, improved windows, centralized and airtight duct design, high efficiency heat pump, and a solar water heater. Feature-by-feature construction differences are highlighted in Table 28.

Table	28 Specifications of Standard and I	Energy Construction
Characteristic	Standard House	Building America House
square footage	1528	1528
floor insulation	R-11	R-22
wall insulation	R-11	R-13
ceiling insulation	R-20	R-33 + roof deck radiant barrier
windows	single pane with interior storm	low-E double pane
exterior doors	storm door on front	storm door on all
marriage wall seal	fiberglass pad	sof-seal gasket
heating system	resistance electric	heat pump HSPF 7.5
cooling system	central air conditioning SEER10	central heat pump SEER12
system size	3 tons	2 tons
water heating	electric water heater – 40 gallon	solar water heater – 66 gallon
duct joints	industry standard	sealed with mastic
duct leakage	*CFM5out = 145	CFM25out = 83
house leakage	**ACH50 = 10	ACH50 = 9
*Cubic feet per minute	**Air changes per hour	

Data collection on the two homes began in early January 2001 and continued through this reporting period. Palm Harbor Homes in Siler City manufactured both homes, the results for program year three and four are detailed below.

### Year 4 Side-by-Side Monitoring Results

During Phase 2, modifications were made to the solar water heating system in the energy efficient housing unit to help improve the performance this system. Further, a number of the incandescent light bulbs in the energy unit were replaced with compact fluorescent bulbs. These changes were staged to allow an evaluation of the effect of each measure on the home's energy use.

Based on investigative results, it can be concluded that:

• Changes in the building envelope, HVAC and duct systems, and fenestrations in the energy home met researchers' 50% energy use reduction goal. Measured annual energy savings for heating and cooling energy was 58%, and 53% for heating, cooling, and hot water production.

- Care should be exercised in the manufactured housing unit setup or relatively minor construction deficiencies can significantly reduce a home's energy efficiency. Many of these items are invisible to the homeowner; therefore procedures must be developed to ensure that deficiencies do not occur during setup.
- The Energy Gauge energy analysis program appears to give a reasonably accurate prediction for expected energy use reduction in a typical manufactured housing configuration. The predicted energy savings for the housing units evaluated in this investigation ranged from 54% to 63%, while the measured values ranged from 53% to 58%. Version 2.0 of the Energy Gauge Program provided a more accurate energy savings prediction than the older software versions.
- An increase in pipe and tank insulation can increase not only the energy efficiency of a solar water heater by reducing stand-by losses, but also can reduce the cooling load in a manufactured housing unit and increase the overall energy efficiency of the water heating unit. Even small amounts of exposed piping can significantly affect the energy efficiency of the water heating system.
- While providing essentially the same lighting levels, replacing incandescent lamps with compact fluorescent bulbs not only reduces lighting energy use, but also reduces the home cooling load.

The total measured energy used by each of the housing units for cooling and heating are shown in tables below. *Table 29* shows the energy used for heating and cooling the standard housing unit from January through August of 2002. The standard home datalogger was struck by lighting in mid-August 2002. Data after this point was not included since only partial data is available and performance comparisons were not possible. *Table 30* shows a summary of the cooling and heating energy used by the energy housing unit. *Tables 31 and 32* list the energy use for hot water production for the standard and energy units, respectively.

Table 29 Cooling and Heating Energy Use, Standard House Actual Values (kWh)												
	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG
Phase 1	492.4	447.6	648.6	1741.1	2495.3	849.6	628.8	384	566.3	990.8	852.9	1066
Phase 2					2120.2	1717.1	1227.6	502.0	438.0	939.4	1079.4	511.2

	Table 30 Cooling and Heating Energy Use, Energy Star House											
	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG
Phase 1	337.3	205.7	150.8	452.8	1087.3	472.8	426.9	184.8	528.3	891.5	850.9	671.6
Phase 2					680.7	537.1	378.1	241.9	311.8	603.0	668	626.6
			Table	31 Don	nestic H	ot Wate	r Use, S	tandaro	d House			
	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG
Phase 1	197.8	267.7	250.2	212.6	0	0	217.6	244.9	258.1	227.5	207.9	213.5
Phase 2					294.6	280.9	283.2	264.9	280.2	192.2	200.3	85.2

Table 32 Domestic Hot Water Use, Energy Star House												
	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG
Phase 1	133.4	176.2	204.2	189.9	0	0	245.5	184.4	183.0	141.2	152.3	126.6
Phase 2					251.1	212.0	202.8	145.9	157.3	74.8	80.3	83.0

Also listed in each table are the monthly energy use values measured during the first phase of this investigation, January through August 2001. Please note that the energy housing unit data

prior to August 2001 is suspect due to duct and HVAC system problems later corrected. The entire data set, including, temperature, relative humidity, solar radiation, and power use is listed on the FSEC web site www.infomonitors.com.

The total energy used for water heating and central cooling over the period of August 1 through August 15 was 363.5 kWh for the energy home and 596 kWh for the standard home. This represents a 40 % reduction in energy use between the two homes.

The total energy used over the period of August 1 through August 15 for water heating was 27.13 kWh for the energy house and 85.18 kWh for the standard home. This represents a 68% reduction in energy use with the solar water heating system and compares well with the June and July reductions of 63% and 60%, respectively. Consistent findings indicate that the tank and piping insulation has reduced the standby tank losses and improved the solar water system efficiency.

In the energy housing unit, three of the 100 watt incandescent lamps that were on the evening four-hour timed duration were exchanged for 25 watt compact fluorescent lamps on June 4th. This change did appear to have a small effect on the cooling load in the energy housing unit. The relative cooling energy used by each of the housing units from June, 2002 through August 2002 showed a small change. The percentage reduction in cooling energy used by the energy housing unit increased from about 30% to 38%. However, it is difficult to isolate the effects of the improvements in the solar water heating system insulation and the effects of the compact fluorescent bulbs. In any event, these effects appear to be much smaller than that produced by the hot water system changes.

*Year 3 Side-by-Side Monitoring Results:* 

Heating system savings (2001 to 2002) were a remarkable 70% during Phase 1. Cooling energy

season savings were 36%, less than heating but still very substantial. The combined heating, cooling, and water heating savings were 52% for a 9-month period. (*Figure 51*)

In addition to the energy monitoring effort, NCA&TSU researchers investigated the feasibility of replacing the conventional framing/envelope used in manufactured/industrial housing with alternative systems. Included in this evaluation, was an analysis of the energy impact of using aerated autoclaved concrete (AAC) flooring systems and structural insulated panels (SIP) to supplant traditional wall and roofing systems. The economic viability of using AAC blocks for structural




Figure 51 Heating season consumption and savings for side by side study of Energy Star Manufactured Housing.

skirting/foundation around the model units also was evaluated.

# Analysis' results determined:

- The best manufactured home energy performance can be achieved using the SIP wall and roof systems with the AAC plank. This performance can be further enhanced with an R-8 unvented crawl space. Though a manufactured home performs best with these alternative systems, the cost to include them may not make economic sense.
  - AAC planks can be designed to replace both the steel frame and flooring systems for HUD code manufactured housing units and modular units. These planks also can be modified to incorporate built-in insulated ducts.
  - AAC planks are pre-manufactured and require less assembly labor than a typical stick framed unit, but including the plank flooring would increase framing costs by 28%. The heavier weight of an AAC system might exacerbate high framing costs. Similarly, comparative analysis results found that replacing a conventional framing system with a SIP system would increase framing costs by 66%.
  - At the current prices for energy and wood products, neither the AAC plank system nor the SIP systems are as economically effective as improvements in the current conventional HVAC systems, steel and wood framing, sheathing systems, and air barriers with respect to improving energy performance.
  - The use of AAC planks has the potential to be economically viable in the modular housing market, especially if used with sealed crawl space foundation systems, where their improved resistance to moisture degradation would be very important.
  - SIP wall and roof systems also could prove to be economically viable if the price of wood energy increases, and the SIP manufacturing costs decrease through large volume purchases.
  - The proposed AAC planking system presents a system that is significantly less affected by water and moisture degradation and may be effective in reducing manufactured housing units' susceptibility to flood damage. These systems also are not susceptible to termite attack.
  - The savings from reduced transportation damage from greater durability and increased floor system stiffness were not addressed in this investigation. It wouldn't take many days of damage repair (at about \$300/person-day for personnel costs related to transportation) to vastly improve the economics of these alternative systems.

#### PORTABLE CLASSROOMS

Portland, OR; Boise, ID; Marysville, WA

### **Project Overview**

This is primarily a WSU (with subcontractors Oregon and Idaho) and Pacific Northwest National Lab (PNNL) task. Other partners include FSEC, UCFIE, the State Energy Offices of Oregon and Idaho, school districts in Portland, Oregon, in Boise, Idaho and Marysville, Washington, regional utilities, manufacturers, and other stakeholders in the Pacific Northwest.

The objective of this task is to promote the adoption of energy efficient portable classrooms in the Pacific Northwest that provide an enhanced learning environment, high indoor air quality, and both substantial and cost-effective energy savings. BAIHP staff focus on four main goals: (1) offering technical assistance to portable classroom manufacturers, school districts, and

related organizations, (2) field assessment, monitoring, and analysis of innovative building technologies and energy saving features to determine their value, (3) facilitation of collaborative agreements among regional utilities, northwestern portable classroom manufacturers and materials and equipment suppliers, as well as school districts, and state education departments and their affiliates, and (4) conducting and creating educational opportunities to advance the widespread adoption of energy efficient portable classrooms in school districts nationwide.

The experiences working on the energy efficient portable were instructive, particularly in the identification of flaws in portable classroom design. The difficulties that BAIHP staff encountered demonstrate the importance of well-defined commissioning protocols, documentation, and coordination among all personnel that service and install HVAC equipment.

## Findings:

- Portable classrooms in the Pacific Northwest are occupied about 1225 hours per year, or about 14% of the total hours in a year.
- The average number of occupants in the standard 28' x 32' portable classroom provide an internal heat of about 480 kWh/year, or 8% to10% of space heating requirements.
- Most of the heat loss in portable classrooms manufactured after 1990 occurs by air leaking through the T-Bar dropped ceilings, because they have no sealed air/vapor barrier. This newly created phenomenon occurred with the incorporation of the less expensive dropped T-Bar ceiling in place of the more expensive sheet rock used in older portables. Air leakage also is increased because of unsealed marriage lines now used as a low cost method of meeting the state attic ventilation requirements.
- Since all portables tested in the project used a simple seven-day programmable thermostat, the HVAC systems operate during vacations and holidays.
- Energy codes in Washington, Oregon, and Idaho are high enough to make beyondcode envelope measures non cost-effective.
- Older portable classrooms under removal consideration could be retrofitted with new energy efficiency measures at much less cost than purchasing a new portable classroom. Installing low-E, vinyl framed windows, insulated doors, T-8 light fixtures, and caulking and sealing air leaks can all be cost-effective when refurbishing older portable classrooms. HVAC system replacement in older portable classrooms will be the biggest single cost item, ranging from \$4500 to \$6500.
- CO<sub>2</sub> sensors appear to be unreliable as a control strategy. Those installed by field crews and monitored by dataloggers in this study did not match the readings shown by the CO<sub>2</sub> sensors which controlled the ventilation systems.

Based on data analysis from years one through four, the following measures were recommended. New portable classroom procurement, setup, and commissioning as well as existing classroom retrofit guidelines produced by the BAIHP study can all be found in Appendix A.

### Recommendations:

- Install 365 day programmable thermostats in all existing portables and specify these thermostats for new construction.
- In portable classrooms constructed with T-Bar dropped ceilings, install an air/vapor barrier above the T-Bar system on the warm side of the insulation. Completely seal all edges and overlaps.

- If roof rafter insulation is used, seal the marriage line at the roof rafter joint with approved sealant such as silicon caulk or foam. Make sure there is adequate ventilation between the insulation and the roof.
- Conduct an audit of older portables scheduled for disposal to determine if retrofitting would be more cost effective than purchasing a new unit.
- Install occupancy sensors to control the ventilation system.
- Specify that new portables contain windows on opposing walls.
- Specify that new portable units contain exhaust fans on the opposite side of the classroom from the fresh air supply.

### **School Partnerships**

Washington Schools - Pinewood Elementary

An 895 ft<sup>2</sup> portable classroom (P5) was sited at the Pinewood Elementary School in Marysville Washington in August 2000. This unit exceeded current Washington State Energy Code standards with upgraded insulation in the floor, roof and walls, low-E windows, and a sensor-driven ventilation system that detects volatile organic compounds (VOCs). A second portable, built in 1985, and also located at Pinewood Elementary (P2), served as the control unit. (*Figure 52*.)

Energy use comparisons of the two classrooms show that the energy efficient portable used considerably more energy than the control portable. This was attributable to several factors:

- Incorrect wiring of the exhaust fan, causing it to run continually. The fan was rewired in 2000 during the summer break. Once corrected, energy use in the portable declined.
- Incorrect
   programmable
   thermostat settings
   which were not
   programmed to turn



**Figure 52** 64 Energy efficient portable classroom at Pinewood Elementary School in Marysville, Washington

# Marysville Classroom Heating System Comparison




Figure 53 Graph comparing heating system use of the Pinewood control portable (P2-Blue) with the energy efficient portable (P5-Red). Note the energy efficient portable's high energy use during the Christmas holidays due to incorrectly configured heating system controls.

- the heating and cooling system off during holidays and vacations. Though energy use was reduced when the portable was unoccupied, use was still excessive (*Figure 53*).
- Higher air leakage in the energy efficient portable than the control portable. Blower door testing found 19 ACH at 50 Pa in the energy efficient classroom compared to nine ACH at 50 Pa in the control classroom. Follow-up blower door, smoke stick, and APT pressure tests indicated that the predominant leakage path tracked through the T-bar ceiling and into the vented attic due to an ineffective air barrier in the energy efficient portable. The control portable contains taped ceiling drywall.
- No initial HVAC commissioning by the HVAC supplier or the school district.
- Significant HVAC system alterations (including rewiring, ventilation system VOC sensor replacement with a CO<sub>2</sub> sensor, and modifications to other aspects of the HVAC control system) during 2001 by maintenance staff and the HVAC supplier, unbeknownst to BAIHP staff. Calibration testing done by scientists at the Florida Solar Energy Center on the CO<sub>2</sub> sensors showed significant drift in output results. This made data collected virtually unusable.



Figure 54 Ventilation system testing at North Thurston School District.

- The use of plug-in electric heaters during the winter of 2001 by the resident teacher because of room comfort problems. This led to significant room temperature variations and monitoring data showed high plug-load energy use.
- Poor fresh air flow design with the fresh air intake and exhaust fan positioned so they create a "short circuit" of fresh air, bypassing the students and teacher.

BAIHP staff proposed the following recommendations to Pinewood Elementary:

- Well-defined commissioning protocols, documentation, and coordination among all personnel that service and install the HVAC equipment. This is a critical component of efficient and healthy classroom operation and should include outside airflow rate measurements to assess adequate ventilation and control testing to insure correct system operation.
- Design changes to the portable classroom manufacturer, including the use of a structural insulated panel system (SIPS), tighter ceiling barrier and sheetrock ceilings, elimination of the vented attic, and relocation of the exhaust fan to the wall opposite the supply air vent.
- Removal of current HVAC controls and replacement with both an occupancy sensor-driven control for the ventilation system and a heating system programmable thermostat. Staff also proposed a classroom on/off switch to simplify the system turnoff during unoccupied summer and school vacations.
- Location of exhaust fans in future portables on the wall opposite the supply air vent.
- Window installation on opposing sides of the classroom to increase daylight penetration and to assist in passive cross-ventilation.

Based on the above recommendations, WSU researchers worked with Marysville school facility manager and customer representatives from Snohomish Public Utility District to assist them in setting new construction specifications for 13 portable classrooms they will procure during the next reporting period. Marysville School District will specify a completely sealed ceiling barrier, a new model heating/ventilation system, a 365 day programmable thermostat, window placement on opposite sides of the classroom, and exhaust fan placement on an opposite wall from the fresh air supply.

Washington Schools - North Thurston School District

BAIHP staff also worked with the North Thurston School District to troubleshoot a portable classroom in Lacey, Washington. (*Figure 54*) The classroom was experiencing high energy use and poor indoor air quality. BAIHP staff tested the classroom, made recommendations including opening the supply dampers, installing a wall side vent to better ventilate the classroom and discussed the specification development process with district staff. The North Thurston School District now is including most of the measures listed in the new procurement guidelines for their future portable classroom purchases. The school district will investigate the feasibility of installing an air/vapor above the T-bar dropped ceiling and will record costs for making these improvements.

Idaho Schools - Boise School District Retrofit

BAIHP staff located a portable classroom at the West Boise Junior High School in the Boise Idaho School District, occupied by a teacher who was interested in having the classroom monitored and retrofitted. The teacher also is an Idaho State legislator active in education issues, which staff members believe will increase the chances of implementing the final recommendations. (*Figure 55*)

BAIHP staff performed a baseline audit, and installed monitoring equipment to track the classroom's energy use during 2000. In 2001, the classroom was retrofitted with an efficient HVAC system (controlled by CO<sub>2</sub> sensors), lighting, and envelope measures. The classroom was then reaudited, and monitored for the remainder of the year. BAIHP staff worked with Pacific Northwest National Laboratories (PNNL) on the pre- and post-retrofit audits, and installation of the monitoring equipment. In their capacity of providing energy management services to the school district, the local utility Avista Corporation, collected lighting and occupancy data.



Figure 55 Weather monitoring system installation in the Boise portable classroom.

Monitoring data indicates a 58% reduction in energy usage post-retrofit. Blower door tests indicate a reduction in air leakage from nine ACH at 50 Pa to five ACH at 50 Pa. Data also revealed that heating use actually increased on weekends and holidays because of lack of internal heat gain and because the HVAC control systems are not programmed to shut off on weekends and holidays. The total retrofit cost was \$9,892.

Monitored data suggests that the  $CO_2$  sensor that controls the HVAC system is not correctly configured. The system does seem to react to an increase in  $CO_2$  levels early in the day, but does

not remain on; CO<sub>2</sub> levels only begin to significantly dissipate after one o'clock PM. BAIHP researchers have noted the difficulty of correctly configuring these sensors in other monitored classrooms.

### Oregon Schools

Oregon BAIHP staff worked with the Portland Public School District to procure two energy efficient classrooms. These were constructed to BAIHP staff specifications and included increased insulation, high efficiency windows, transom windows for increased daylighting, a high efficiency heat pump, and efficient lighting. Staff videotaped the construction of one classroom.

Monitoring equipment was installed by PNNL staff. Estimates using the software Energy-10 indicated a total energy consumption of 9200 kWh, or \$583 per year at Portland energy rates. Measured results showed the Oregon portable used about 6600 kWh for the monitored period.

Incremental costs for the energy efficiency measures were \$6,705 over Oregon commercial code, including approximately \$2,500 for the HVAC system. This suggests a simple payback of 10 to 12 years.

Initial blower door tests found air leakage rates of 11.3 ACH at 50 Pa. BAIHP staff also identified significant leakage through the T-bar dropped ceiling and up through the ridge vents. Other monitoring results indicated that the same HVAC control problems exist with the Oregon classroom as with the others studied in this project.

The Energy Efficient model outperformed code level models in the Portland area. The older the classroom, the more energy consumed. Even when compared with new code level models from the same year, the Energy Efficient model used 35% less energy. Conventional code level classrooms do not include energy efficient measures which greatly increases the unit's operating costs. Classrooms built more than 10 years ago, use twice as much energy as the efficient model. Those older than 20 years consume more than three times the amount of energy. From this study, researches determined that high performance classrooms can save anywhere from \$200 to \$1000 dollars a year in energy costs compared to older, less efficient portables.

A survey sent to teachers and maintenance staff indicates a high degree of satisfaction with the efficient portables; the teachers were most impressed with the improved indoor air quality and increased light levels due to the daylighting windows.

### Historical Data Collection

In Idaho, Oregon, and Washington, BAIHP staff worked with local utilities and school districts to obtain historic energy use data on portable classrooms. This data will be used to compare energy usage from the energy efficient portables monitored in this study.

In Idaho, BAIHP staff worked with Avista Corporation's energy manager to collect historic data on 14 portable classrooms in the Boise School District. The classrooms each were equipped with discrete energy meters; as a result, BAIHP staff was able to obtain energy usage data for the past three to four years. A procedure was developed to collect information on portables at each school in cooperation with the physical facilities manager and each school lead. Historic data collection continues. Site visits and walk-through audits are planned for these 14 buildings.

WSU will continue to coordinate with PNNL and FSEC on instrumented data collection on the portable classrooms being monitored in Boise, Idaho, Marysville, Washington, and in Portland, Oregon. WSU will work with Idaho to potentially procure and test one prototype classroom with SIPS. Evaluate and analyze the collected data and prepare articles for presentation and publications.

### **Duct Testing Data from Manufactured Housing Factory Visits**

Paper: McIlvaine, Janet, David Beal, Neil Moyer, Dave Chasar, Subrato Chandra. Achieving Airtight Ducts in Manufactured Housing. Report No. FSEC-CR-1323-03.

Over the past 10 years, researchers at FSEC have worked with the Manufactured Housing industry under the auspices of the U.S. Department of Energy (DOE) funded Energy Efficient Industrialized Housing Program and the Building America (BA) Program (www.buildingamerica.gov). FSEC serves as the prime contractor for DOE's fifth Building America Team: the Building America Industrialized Housing Partnership (BAIHP) which can be found online at: www.baihp.org.

Data and findings presented here were gathered between 1996 and 2003 during 39 factory visits at 24 factories of six HUD Code home manufacturers interested in improving the energy efficiency their homes. Factory observations typically showed that building a tighter duct system was the most cost effective way to improve the product's energy efficiency.

BAIHP and others recommend keeping duct system leakage to the outside (CFM25<sub>out</sub>) equal to or less than 3% of the conditioned floor area, termed Qn<sub>out</sub>. However, most homes seen in a factory setting cannot be sealed well enough to perform a CFM25<sub>out</sub> test. Results of many field tests suggest that CFM25<sub>out</sub> will be roughly 50% of total leakage (CFM25<sub>total</sub>). Thus, to achieve a Qnout of less than 3%, manufacturers should strive for a CFM25<sub>total</sub> of less than 6% of the conditioned area (Qn<sub>total</sub>).

Researchers measured total duct leakage and/or duct leakage to the outside in 101 houses representing 190 floors (single wide equals one floor, double wide equals two floors, etc.). Ducts systems observed in these tests were installed either in the attic (ceiling systems) or in the belly (floor systems). Researchers tested 132 floors with mastic sealed duct systems and 58 floors with taped duct systems.

Of the 190 floors tested by BAIHP, the results break down thus:

For mastic sealed systems (n=132):

- Average  $Qn_{total} = 5.1\%$  (n=124); 85 systems (68%) achieved the  $Qn_{total} \le 6\%$  target.
- Average  $Qn_{out} = 2.4\%$  (n=86); 73 systems (85%) reached the  $Qn_{out} \le 3\%$  goal.

For taped systems (n=58)

- Average  $Qn_{total} = 8.2\%$  (n=56); 19 systems (34%) reached the  $Qn_{total} \le 6\%$  target.
- Average  $Qn_{out} = 5.7\%$  (n=30), more than twice as leaky as the mastic average; 5 systems (17%) reached the  $Qn_{out} \le 3\%$  goal.

The results show that, while it is possible to achieve the BAIHP Qn goals by using tape to seal duct work, it is far easier to meet the goal using mastic. What isn't illustrated by the results is the longevity of a mastic sealed system. The adhesive in tape can't stand up to the surface

temperature differences and changes or the material movement at the joints and often fails. Mastic provides a much more durable seal.

Typical factory visits consist of meeting with key personnel at the factory, factory observations, and air tightness testing of duct systems and house shells. A comprehensive trip report is generated reporting observations and test results, and pointing out opportunities for improvement. This is shared with factory personnel, both corporate and locally. Often, a factory is revisited to verify results or assist in the implementation of the recommendations.

The most commonly encountered challenges observed in the factories include:

- Leaky supply and return plenums
- Misalignment of components.
- Free-hand cutting of holes in duct board and sheet metal.
- Insufficient connection area at joints.
- Mastic applied to dirty (sawdust) surfaces.
- Insufficient mastic coverage.
- Mastic applied to some joints and not others.
- Loose strapping on flex duct connections.
- Incomplete tabbing of fittings.
- Improperly applied tape

Duct system recommendations discussed in this report include:

- Set duct tightness target Qn equal to or less than 6% total and 3% to outside.
- Achieve duct tightness by properly applying tapes and sealing joints with mastic
- Accurately cut holes for duct connections
- Fully bend all tabs on collar and boot connections
- Trim and tighten zip ties with a strapping tool
- Provide return air pathways from bedrooms to main living areas

Summary of BAIHP Approach to Achieving Tight Ducts in Manufactured Housing:

- Set goal with factory management of achieving Qnout<=3% using Qntotal<=6% as a surrogate measurement while houses are in production.
- Evaluate current practice by testing a random sample of units
- Report Ontotal and Onout findings; make recommendations for reaching goals
- Assist with implementation and problem solving as needed
- Evaluate results and make further recommendations until goal is met
- Assist with development of quality control procedures to ensure continued success

Finally, duct tightness goals can be achieved with minimal added cost. Reported costs range from \$4 to \$8. These costs include in-plant quality control procedures critical to meeting duct tightness goals.

Achieving duct tightness goals provides benefits to multiple stakeholders. Improving duct tightness diminishes uncontrolled air (and moisture) flow, including infiltration of outside air, loss of conditioned air from supply ducts, and introduction of outside air into the mechanical system. Uncontrolled air flow is an invisible and damaging force that can affect the durability of houses, efficiency and life of mechanical equipment, and sometimes occupant health. With improved duct tightness, manufacturers enjoy reduced service claims and higher customer

satisfaction, while homeowners pay lower utility bills, breathe cleaner air, and have reduced home maintenance.	

# B. Site Built Housing Research

BAIHP continues to foster the research the implementation of the systems engineering approach with site builders which includes the incorporation of multiple concepts toward achieving the Building America program goals of saving 40% of total energy use while improving durability, indoor air quality, and comfort. Industry Partners in this area of BAIHP rise above "business as usual" production to strive toward this goal. BAIHP assists the builders, much as described in Section II, Technical Assistance, but goes on to instrument and collect relevant data from the house in an effort to validate the approach taken by the builder and add to our knowledge base of how to achieve the Building America goals.

BAIHP conducted research for site built housing which is reported in the following summaries:

- Building America Prototype, Cambridge Homes
- Unvented Attic Study, Rey Homes
- Sharpless Construction, Hoak Residence Energy and Moisture Studies
- Eastern Dakota Housing Alliance (EDHA), Applegren Construction
- Zero Energy Affordable Housing, ORNL and Loudon County Habitat for Humanity

# **Building America Prototype, Cambridge Homes**

Orlando, Florida Category B Technical Support led by BAIHP Researcher Eric Martin

The partnership between BAIHP and production builder Cambridge Homes began late in 2001. Cambridge Homes had recently signed on with the EPA Energy Star Homes Program as a 100%

Energy Star builder and expressed interest in increasing energy efficiency even further, as well as adding some "healthy home" features to their product. Also, Cambridge Homes expressed interest in BAIHP helping them design and build in a way that would prevent moisture related problems and call backs. BAIHP began by conducting analysis on several typical home designs and presenting results and strategies in a number of meetings with the builder. BAIHP also arranged a special meeting with the American Lung Association of Central Florida to discuss achieving the ALA Health House designation on the showcase



Figure 56 The Augusta, Cambridge Homes Building America Prototype.

model. However, the builder decided not to pursue the health house designation at that time.

To implement Building America strategies outlined by FSEC researchers, Cambridge Homes constructed a "prototype house" (*Figure 56*) to ensure that the strategies mate well with their current building practices (*Table 33*). A variety of home plans were reviewed to select an appropriate demonstration home, as well as a standard-practice counterpart. During construction, both homes were outfitted with dataloggers and associated monitoring equipment.

The homes were built in Baldwin Park, a new Orlando subdivision being developed on land that was once home to the Orlando Naval Training Center. The development will be 30% larger than New York's Central Park, totaling approximately 1100 acres. Four hundred acres have been set aside for parks and open space, while 700 acres will be used for the construction of 3,000 homes, one million square feet of office space, and 200,000 square feet of retail space. Cambridge Homes is one of ten builders constructing homes in the community and plans to build 700 homes in Baldwin Park over the next five years.

Table 33 Cambridge Homes Specifications		
Component	Base Case (Covington)	Prototype (Augusta)
Conditioned Area	2446 ft2	2672 ft2
Envelope		
Above-Grade	CMU first floor	Same
Wall Structure	2X4 Frame second floor	
Above-Grade	R-3.5 rigid foam	R-3.5 rigid foam

**Table 33 Cambridge Homes Specifications** 

		_
Wall Insulation	R-13 Fiberglass Batt	R-13
Above-Grade Wall Sheathing	OSB	Same
Attic	Vented r-30 batt	Unvented r-19 Icynene
Roof	Owens corning shingle	Elk architectural shingle
Windows	Single pane, clear Metal frame	Double pane, low-e Metal frame
Infiltration (ACH50)	Not tested by FSEC	3.0
Equipment		
# Of Systems	2	1
Heating	Heat pump $HSPF = 8.65$	Same
Cooling	2.5 ton, 13 SEER 2 ton, 13 SEER	5 ton, 13 SEER
Thermostat	Programmable Standard	Programmable
Ventilation	None	Thermastor Ultra-Aire
Water Heater	50gallon Electric EF 0.88	Same
Lighting	10% fluorescent	100% fluorescent
Appliances	Standard	Energy Star
Hers Score	87	87.6

The demonstration home gave the builder firsthand experience with unfamiliar design elements, some of which have been incorporated into their standard practices. Such unfamiliar design elements included vapor permeable wall insulation, low-e windows, whole house dehumidifiers, unvented attics, and compact fluorescent lighting. FSEC researchers closely monitored the construction of the prototype and standard practice home, which was built to the Energy Star level. A duct test was performed in the prototype house during mechanical rough in to ensure leakage specs were met. Meetings also were held with the builder's HVAC contractor to discuss installation of the whole-house high efficiency dehumidification, filtration, and ventilation unit in the prototype model.

Upon completion of the home, duct testing was repeated to include inspection of the whole house dehumidification unit, and infrared camera analysis was conducted on the home. Data (*Figures 57 and 58*) collected from the two homes showed marked improvement in attic temperature (a primary cooling load) and indoor relative humidity control.

BAIHP performed training for Cambridge Homes' sales staff in March 2003. The training took place within the completed "prototype" model. Training focused on the advanced features of the Building America showcase model which Cambridge Homes began offering in April 2003.

### Comparison of Attic Temperatures Between Models




Figure 57 Comparison of attic temperatures between Cambridge Homes BA Prototype (Augusta) and Standard Cambridge Homes construction (Covington). Graph shows how sealed attic construction in Augusta results in lower attic temperatures than vented attic construction during cooling season in Orlando, FL.

### Comparison of First Floor RH Between Models




Figure 58 BA Prototype (Augusta) contains whole house dehumidification system. Plot shows daily cycling of the system resulting in a lower relative humidity in the prototype home than in the standard Cambridge Homes construction.

Late in 2003, Cambridge Homes began construction of a second home similar to the "prototype" model, which was purchased by a customer impressed with its attributes. FSEC staff conducted training for builder and sales staff in December 2003 to review design methodologies and lessons learned from the prototype model. A second meeting was held in January 2004 inspect progress of the home. Upon moving into the home, Cambridge Homes reports that the new homeowner is extremely happy with the home.

To assist Cambridge Homes with reducing callbacks and moisture reduction problems, FSEC researchers have also conducted "total" and to "out" duct tests on six other Cambridge homes to determine why the total duct leakage numbers were high (>10% of fan flow) despite low to "out" duct leakage. "Out" is defined as outside the conditioned space, including buffer spaces like an attic or garage. Consistent leakage was found around the boot to register grill connections. FSEC worked with Cambridge Homes and their HVAC contractor, DEL-AIR, to specify air tight register grills.

## **Unvented Attic Study, Rey Homes**

Orlando, Florida

Technical Assistance by BAIHP Researchers Eric Martin and Neil Moyer

Rey Homes, a production builder in Orlando, in 2001 pledged to build a community of 200 homes that meet both Energy Star standards (HERS = 86) and the Florida Green Home Designation Standard. Rey's partnership with FSEC began in October 2001 when researchers analyzed Rey's standard home designs and construction and made recommendations for complying with these standards.

In the fourth budget period, Rey built 2 homes in their Villa Sol community for side by side comparison of unvented attic construction, a BAIHP recommended strategy. FSEC installed monitoring equipment in both homes, one with an unvented attic and one with a standard vented attic including a set of moisture pins in each house to monitor the moisture content of roof trusses in addition to the usual complement of temperature, humidity, and energy use meters. Instrumentation was complete early in the fifth budget period; however, data collection was not successful due to equipment and site complications.

# **Sharpless Construction, Hoak Residence Energy and Moisture Studies**

Longwood, Florida

Category A

Technical Assistance led by BAIHP Researchers Subrato Chandra and Dave Chasar

This three-story, 4,250 square foot home was completed in February 2001 by Mr. David Hoak and Sharpless Construction in Longwood, Florida near Orlando. (*Figure 59*) FSEC assisted the owner and builder by recommending a package of features that produced an exceptionally energy efficient design at a reasonable cost. Because the building envelope design and mechanical equipment selection work together as a system, the home can be cooled with a much smaller air conditioner than is needed by most homes of this size in this climate.



Figure 59 Hoak residence in Longwood, Florida.

# **Envelope Features:**

High Performance Windows

Roughly 25% of the annual cooling load in a typical Central Florida home is introduced through the windows. Recent advances in window technology allow this load to be greatly reduced. The windows in this residence are particularly useful in Florida because they have a very low Solar

Heat Gain Coefficient (SHGC) to reduce direct solar gains, and a relatively high Visible Transmittance (VT) for natural daylighting.

### Unvented Attic

Most Florida homes have vented attics with batt or blown insulation applied just above the ceiling. This exposes the air conditioning ductwork to very high temperatures and magnifies duct leakage problems. Sealing the attic envelope and insulating at the roof deck, as shown in *Figure 60*, provided a semi-conditioned space for the ductwork. This reduced conductive heat gain and minimized the detrimental impact of duct leakage.



Figure 60 semi-conditioned space for the ductwork.

# Expanding Foam Insulation

A layer of expanding foam insulation

(*Figure 60*) was applied to the underside of the roof deck to create an unvented, semi-conditioned attic (R-22). The same insulation was applied to all above-grade walls (R-11). While the insulation R-values were standard, the foam created a nearly airtight seal and greatly reduced outside air infiltration.

#### Continuous Air Barrier

Infiltration of Florida's hot and humid outside air can have a big impact on energy use, building durability, and occupant health. The continuous air barrier, placed toward the outside of the building envelope, reduces this infiltration. Indoor air quality concerns were addressed by installing an energy recovery ventilator to introduce outside air.

The air barrier consists of a tightly taped housewrap installed over the exterior sheathing on all above-grade frame walls, and extruded polyurethane foam boards glued to the interior of the below-grade block walls. Expanding foam insulation provided an extra measure of airtightness at all above-grade exterior surfaces including the roof deck. Special care was taken to seal wall details such as corners, floor interfaces, and the roof junction. Blower door performance tests verified the home's level of airtightness (ACH50 = 2.0).



**Figure 61** Heat pump water heater.

# **Equipment Features:**

### 2-Speed, Zoned Heat Pump

The building envelope design features described above greatly reduced the required air conditioner size. Manual-J HVAC equipment-sizing calculations showed the need for only  $2\frac{1}{2}$  tons of heating and cooling capacity. In this case the owner opted for a two-speed compressor, which provides either  $2\frac{1}{2}$  or 5 tons of cooling or heating depending on the need.

The Hoak home air conditioning unit typically operated in the  $2\frac{1}{2}$ -ton mode until the late afternoon when it switched to the 5-ton mode for a few brief periods. In this home, energy use stays low because the low compressor speed operates the majority of the time. But, when quick cool-down or excessive loads require more capacity, the high speed compressor can meet the need.

Measured data indicated that the 5-ton mode operated about one in every four days during the three hottest summer months (June to August), usually for periods of 15 minutes or less. Even these short periods of high-speed compressor operation might have been avoided with proper use of a programmable thermostat. These results verify the Manual J sizing calculations and indicate that if a single speed HVAC system were installed, the optimum size would be  $2\frac{1}{2}$  to 3 tons.

### Variable-speed Air Handler

Two benefits of using a variable-speed motor for air distribution are better moisture removal and energy efficiency. During the cooling season, slower airflow across a cold coil allows for more moisture removal. Wintertime comfort also is enhanced with this operation, since the coil has more time to warm before the air is brought to full flow.

Indoor relative humidity tends to increase during the fall and winter months when air conditioning activity declines. Without a dedicated dehumidifier, the air conditioner is the only means of reducing indoor relative humidity. When there is a call for cooling - the low-speed

compressor in a variable speed system operates more consistently than a larger system and keeps relative humidity from rising to unhealthy levels.

### Heat Pump Water Heater

Solar water heating would have been the first choice for this home, but poor orientation and too many shade trees forced a search for other options. (*Figure 59*) Natural gas also was unavailable in the area. To avoid the inefficiency of electric resistance water heating, a 6,000 BTU/hour heat pump water heater (*Figure 61*). Heat pump water heater produced all the hot water needs for a four-person household from April to September.

The water heater was connected to a standard 80-gallon electric water heater. By locating the heat pump inside the home, homeowners gained a summertime benefit of additional cooling and year 'round dehumidification because the system removes moisture each time it operates.

### Energy Recovery Ventilator

The energy recovery ventilator acts as a conduit to flush out stale indoor air and replace it with outdoor air. As the indoor air is expelled, a heat exchanger recovers up to 80% of the energy used to heat or cool the air and transfers it to the incoming air stream. This unit also transfers a portion of the moisture between the airstreams, which is useful during periods of high outdoor humidity.

### Airtight Ducts

Attic and duct heat gain contribute to about 22% of the cooling needs of a typical Central Florida home when are ducts located in a vented attic above the insulation. While some home efficiency is lost by direct heat-gain through the duct insulation, a great deal more efficiency can be lost from unintended duct leakage from the ductwork into the vented attic. Duct leakage test results showed only 50 CFM of air was lost at 25 Pa of pressure differential in the Hoak residence. This leakage equates to 1.2% leakage per square foot of conditioned floor area - far below the leakage normally found in new Florida homes.

### Energy Monitoring:

Monitors on the Hoak residence include 11 attic temperature and relative humidity sensors, three indoor sensors, a Hobo event logger to record the dehumidifier cycling time, and a tipping bucket rain gauge with Hobo logger to monitor the combined condensate of the air conditioner, dehumidifier, and heat pump water heater. In 2002, Alten Design also assembled a new logger monitoring computer with the capability of reading data from two Campbell 21X loggers. This computer was configured with remote monitoring and control capacity so that Partners can program and maintain the system without traveling to the site.

# **Findings**

### Duct Leakage

Duct leakage test results showed the Hoak home air loss was only 50 CFM at 25 Pa or 1.2% leakage per square foot of conditioned floor area – far below the amount of leakage normally found in new Florida homes.

Total duct leakage is less than 10% of air handler flow (200 CFM). Blower door performance tests verified the home's level of airtightness at two air changes per hour at 50 Pa (ACH50 = 2.0). When including leakage around the supply grills, house leakage increased about 30%.

Slightly more than half of the house leakage (1479 CFM at 50 Pa) is located in the sealed attic space (760 CFM at 50 Pa).

### Cooling Energy

Initial data comparisons were made against data collected from a Lakeland, Florida residence (PVRes), designed by FSEC and monitored for more than a year. The PVRes home contained the most energy-efficient provisions researchers could devise, including a 5 kW photovoltaic system. Data collected at the Hoak home shows the cooling energy is nearly on par with the PVRes Home on a per square foot basis.

# Envelope

Weekly data logs of the Hoak home provided by Alten Design from the 14 Hobo temperature and relative humidity sensors and pressure tests through March 2003, confirm that air pathways between the unvented attic and outdoors still exist. Researchers suspect that these pathways may be the primary source of moisture intrusion into the unvented attic space. Several whole house pressure tests (smoke tests) were performed by Alten Design and FSEC to isolate these external sources of air infiltration. Identified leaks were sealed, though actions have shown some benefit moisture levels are still higher than desired.

In order to isolate areas of leakage, barriers will be placed in the house splitting the areas under test into easier to monitor individual zones.

#### Eastern Dakota Housing Alliance (EDHA), Applegren Construction

Grand Forks, North Dakota

Category A, 2 Homes

Category B, 5 Homes

Technical Support by BAIHP Researcher, Dave Chasar

Awards: North Dakota Housing Finance Agency's Champion of Affordable Housing

**Production Award** 

Paper Pending: Chasar, D., Moyer, N., Chandra, S., Rotvold, L., Applegren, R., "Cold Climate

Case Study; High Efficiency North Dakota Twin Homes," Performances of Exterior Envelopes of Whole Buildings IX International Conference, Clearwater

Beach, Florida, December 2004.

Eight dwellings have been built by EDHA on Selkirk Circle in Grand Forks, North Dakota (*Figure 62*) with the goal of achieving up to 50% energy savings over the 1993 Model Energy Code.

The two story dwellings include an insulated basement with air circulation to the main house, suitable for conversion to living space. Features of the Phase I and Phase II homes are summarized in Table 34.



Figure 62 Selkirk Twin Homes, Grand Forks, ND.

Phase I (March 2003) and Phase II (Feb 2004)

included two twin homes (duplexes) each. These and a theoretical base case house using local conventional construction and code minimums were modeled in DOE2 to determine energy savings and cost effectiveness.

Estimated combined gas and electric utility savings ranged from 25% on Phase I homes to 35% on Phase II homes over the base case. The homes also met the BA goal of 40% savings compared to the Benchmark house.

Table 34 Applegren Twin Home Specifications								
Component	Base Case	Phase I (March 2003)	Phase II (Feb 2004)					
Conditioned Area Of Each Dwelling	1840 ft2 (w/basement)	Same	Same					
Hers Score	85.2	89.7	92.2					
Envelope								
Above-Grade Wall Structure	2x6 wood frame	Same	2x4 wood frame					
Above-Grade Wall Insulation	R-19 fiberglass batt	Same	R-15 blown fiberglass					
Above-Grade Wall Sheathing	Plywood	Same	R10 XPS Foam Corners: R7.5+Plywood					
Basement Walls	R-11	Same	Same					
Vented Attic	R-49	Same	Same					
Windows	Double pane, low-e, Argon-filled, Vinyl slider frame	Casement (instead of slider)	Same as phase I					

Table 34 Applegren Twin Home Specifications							
Component	Base Case	Phase I (March 2003)	Phase II (Feb 2004)				
	U=0.34, SHGC=0.33						
Infiltration (ACH50) (Including Basement)	5 (assumed)	2.8 (average of 4 units)	2.4 (average of 4 units)				
Equipment							
Gas Furnace	60kbtu, AFUE=78	60kbtu, AFUE=92 w/sealed combustion	60kbtu, AFUE=92				
Air Conditioner	1.5 ton, 10 SEER	Same	Same				
Thermostat	Standard	Programmable	Same as Phase I				
Ventilation	None	70% efficient HRV	Same as Phase I				
Water Heater	40gallon, EF=0.88 Electric	40gallon, EF=0.62 Natural gas with power vent	Tankless, EF=0.83 Natural gas				
Lighting	10% fluorescent	85% fluorescent (linear and cfl) Note: only bathroom and dimmable fixtures were incandescent	Same as phase I				
Appliances	Standard	Energy Star Dishwasher Horizontal-axis washer Energy Star Refrigerator	Same as Phase I				

#### Moisture Issues

The low water vapor permeance of rigid XPS foam sheathing (1.1 perms) presents a dilemma in this climate where an interior vapor barrier (usually 6-mil polyethylene) is considered mandatory to minimize moisture diffusion from the conditioned space into the wall cavity. The installation of two vapor barriers leaves the wall vulnerable to moisture accumulation should water unintentionally enter the cavity. One recommendation calls for removing the interior vapor barrier and relying on two coats of latex paint on the interior to limit diffusion from the conditioned space into the wall. This option allows the wall to dry to some extent in both directions, but was not chosen by the builder.

#### Ventilation

A heat recovery ventilator (HRV) mounted in the basement provides controlled mechanical ventilation with an energy penalty estimated at \$45/year. The unit contains an 80-watt fan that introduces 75 CFM of outside air while exhausting a similar amount at a heat transfer efficiency of 70%. Attempting to meet the new ASHRAE 62.2 standard (ASHRAE 1999) would require 42 CFM of continuous ventilation. For these simulations however, the old ASHRAE guideline of 0.35ACH was used, calling for a continuous rate of 25CFM. The HRV can operate either continuously or on an intermittent 20 minutes on, 40 minutes off cycle. Intermittent operation was simulated to meet the old guideline.

#### Cost Analysis

One row in Tables 35 and 36 shows the cumulative effect of all measures added to the base case home. Estimated saving in this row includes the cumulative effect of all measures incorporated together in the DOE2 simulation. The heat recovery ventilator (HRV) is broken out from the other measures to provide a meaningful simple payback and first year cash flow figures for the other cumulative measures. The HRV is considered an essential component for the indoor air quality of these homes, but comparing it to a base case home without ventilation means no

relative savings are attained; thus this measure is added in a separate row. With the exception of the HRV all measures show a positive cash flow on a 6%, 30 year fixed rate mortgage beginning in the first year.

TABLE 35 Economic Assessment of Phase I Measures

Energy Measure	Annual Savings	Installed Cost	Simple Payback	First Year Cash Flow
Reduce infiltration to 2.8 ACH50	\$90	\$325	3.6	\$68
Upgrade to 92% direct vent furnace	\$52	\$600	11.5	\$11
Switch to Programmable Thermostat	\$23	\$130	5.7	\$11
Upgrade to Energy Star appliances*	\$61	\$730	12	\$12
Change to EF=0.62 power vented water heater	\$52	\$520	10	\$16
Increase from 10% to 85% fluorescent lighting	\$31	\$200	6.5	\$17
All Measures	\$309	\$2,505	8.1	\$135
Heat recovery ventilation @75cfm, 33% RTF	-(\$45)	\$1,400	N/A	(\$134)
All Measures with HRV	\$264	\$3,905	14.8	\$1

Notes: \* Energy Star appliances include refrigerator, dishwasher and h-axis clothes washer

The increased utility savings of Phase II over Phase I arise from two energy saving measures unique for this area: Extruded Polystyrene (XPS) foam sheathing with 2X4 framing and tankless gas water heating. Simple paybacks for these measures were 8.3 and 13.3 years respectively. Electric water heaters are the current norm in the Grand Forks area, but with electricity 26% below the national average and natural gas prices on the rise simple payback on the tankless model was relatively long. In addition, fluctuating natural gas prices complicate the economic analysis. Initial concerns of how the tankless water heater would perform in this extreme climate were met with positive feedback through the first winter, which was colder than normal, including an all-time record low of -44°F set at the Grand Forks International Airport on January 30, 2004.

TABLE 36 - Economic Assessment of Phase II Measures

Energy Measure	Annual Savings	Installed Cost	Simple Payback	First Year Cash Flow
Upgrade walls to (R10 sheath + R15 FG batt)	\$72	\$600	8.3	\$31
Reduce infiltration to 2.4 ACH50	\$106	\$325	3.1	\$82
Upgrade to 92% direct vent furnace	\$40	\$600	15.0	-\$1
Switch to Programmable Thermostat	\$18	\$130	7.2	\$6
Upgrade to Energy Star appliances*	\$60	\$730	12.2	\$12
Change to EF=0.83 tankless gas water heater	\$94	\$1,250	13.3	\$10
Increase from 10% to 85% fluorescent lighting	\$31	\$200	6.5	\$18
All Measures	\$421	\$3,835	9.1	\$158
Heat recovery ventilation @75cfm, 33% RTF	-(\$43)	\$1,400	N/A	(\$134)
All Measures with HRV	\$378	\$5,235	13.8	\$24

Notes: \* Energy Star appliances include refrigerator, dishwasher and h-axis clothes washer

<sup>-</sup> First year cash flow based on 30 year fixed rate mortgage with interest rate of 6%, down payment of 5%, and discount rate of 5%. A general inflation rate of 3% per year was applied to the upgrade cost of measures replaced at end of lifetime. Final value of equipment is determined by linear depreciation over lifetime. Interest paid on mortgage is considered tax deductible using a tax rate of 28%. Energy costs escalate at 3% per year. A property tax rate of 0.8% was applied to the energy upgrade cost and is inflated at 3% per year.

<sup>-</sup> First year cash flow based on 30 year fixed rate mortgage with interest rate of 6%, down payment of 5%, and discount rate of 5%. A general inflation rate of 3% per year was applied to the upgrade cost of measures replaced at end of lifetime. Final value of equipment is determined by linear depreciation over lifetime. Interest paid on mortgage is considered tax deductible using a tax rate of 28%. Energy costs escalate at 3% per year. A property tax rate of 0.8% was applied to the energy upgrade cost and is inflated at 3% per year.

#### Annual Energy Use

A performance comparison of the base case and improved structures is shown in Table 37. The increased heating design load in Phases I and II over the base case is caused by the addition of 75 CFM of ventilation introduced on a 20 minutes ON, 40 minutes OFF cycle, which the base case does not have. The DOE2 model predicts the need for very little cooling, however many new homes in this area are being built with central air conditioning.

TABLE 37 - Simulated Performance Comparison of Base Case and Improved Homes

	<b>Base Case</b>		Phase I		Phase II	
HERS	85.2		89.7		92.2	
<b>Total Annual Energy</b>	Cost	Savings	Cost	Savings	Cost	Savings
	\$1,079	_	\$815	25%	\$701	35%
	Annual	<b>Design Load</b>	Annual	Design Load	Annual	Design Load
	Cost	(kBtu/h)	Cost	(kBtu/h)	Cost	(kBtu/h)
Heating	\$458	29.8	\$366	33.4	\$294	30.7
Cooling	\$15	9.9	\$11	10.6	\$10	10.3
Hot Water	\$245		\$157		\$116	
H/C/WH Total	\$718		\$534		\$420	

Four more dwellings (two duplexes) are slated for completion in the summer of 2004. For more information on this project, see Cold Climate Case Study: High Efficiency North Dakota Twin Homes on www.baihp.org.

# Zero Energy Affordable Housing, ORNL and Loudon County Habitat for Humanity

Lenoir City, Tennessee Category A Research by ORNL with BAIHP Support

In partnership with Oak Ridge, BAIHP prepared to instrument a zero energy home (ZEH) built by Loudon County (TN) HFH - their fourth (*Figure 63*). See description in the *Technical Assistance* section of this report under *Habitat for Humanity*, *Tennessee*, *Loudon County*.

Data is available on-line at <a href="https://www.infomonitors.com">www.infomonitors.com</a>. A paper on the study was submitted to the Buildings IX conference by Jeff Christian (ORNL) and David Beal (BAIHP-FSEC).



**Figure 63** Local sponsors in front of 2nd ZEH built by Loudon County HFH in partnership with ORNL. FSEC provided monitoring for the 1<sup>st</sup> and 4<sup>th</sup> ZEHs.

# C. Field and Laboratory Building Science Research

BAIHP builds on a 20 year foundation of basic building science research at the Florida Solar Energy Center. This research generally focuses on issues important in hot-humid climates similar to Florida's but is relevant to our understanding of building science concepts manifest in all climatic regions. BAIHP has conducted field and laboratory building science research in these areas:

- Air Handler Air Tightness Study
- Air Conditioning Condenser Fan Efficiency
- Fenestration Research
- Reflective Roofing Research
- Return Air Pathway Study
- Heat Pump Water Heater Evaluation
- NightCool Building Integrated Cooling System

#### Air Handler Air Tightness Study

Central Florida

Research by FSEC Researchers Chuck Withers, Jim Cummings, and Janet McIlvaine

To determine the impact of air handler location on heating and cooling energy use, researchers measured the amount of air leakage in air handler cabinets, and between the air handler cabinet and the return and supply plenums. To assess this leakage, testing was performed on 69 air conditioning systems. Thirty systems were tested in the 2001 and 39 in 2002. The 69 systems were tested in 63 Florida houses (in six cases, two air handlers were tested in a single house) located in seven counties across the state - four in Leon County in or near Tallahassee, 17 in Polk County, three in Lake County, 13 in Orange County, one in Osceola County, two in Sumter County, and 29 in Brevard County. All except those in Leon County are located in central Florida. Construction on all houses was completed after January 1, 2001, and most homes were tested within four months of occupancy.

In each case, air leakage ( $Q_{25}$ ) at the air handler and two adjacent connections was measured.  $Q_{25}$  is the amount of air leakage which occurs when the ductwork or air handler is placed under 25 Pa of pressure with respect to its surrounding environment.  $Q_{25}$  also can be considered a measurement of ductwork perforation.

To obtain actual air leakage while the system operated, it was necessary to measure the operating pressure differential between the inside and outside of the air handler and adjacent connections. In other words, it was necessary to know the perforation or hole size and the pressure differential operating across that hole. By determining both  $Q_{25}$  and operating pressure differentials, actual air leakage into or out of the system was calculated.

#### Field Testing Leakage Parameters

Testing was performed on 69 air conditioning systems to determine the extent of air leakage from air handlers and adjacent connections. Testing and inspection was performed to obtain:

- $Q_{25}$  in the air handler,  $Q_{25}$  at the connection to the return plenum, and  $Q_{25}$  at the connection to the supply plenum.
- Operating pressure at four locations the return plenum connection, in the air handler before the coil, in the air handler after the coil, and at the supply plenum connection.
- Return and supply air flows were measured with a flow hood. Air handler flow rates were measured with an air handler flow plate device (per ASHRAE Standard 152P methodology).
- Overall duct system and house airtightness in 20 of the 69 homes.
- Cooling and heating system capacity based on air handler and outdoor unit model numbers.
- The location and type of filter.
- Dimensions and surface area of the air handler cabinet.
- The fractions of the air handler under negative pressure and under positive pressure.
- The types of sealants used at air handler connections.
- Estimated portion of the air handler leak area that was sealed "as found."

# Air Handler Leakage

Leakage in the air handler cabinet averaged 20.4 Q<sub>25</sub> in 69 air conditioning systems. Leakage at the return and supply plenum connections averaged 3.9 and 1.6  $Q_{25}$ , respectively. Using the operating pressures in the air handler and at the plenum connections, these Q<sub>25</sub> results convert to actual air leakage of 58.8 CFM on the return side (negative pressure side) and 9.3 CFM on the supply side (positive pressure side). The combined return and supply air leakage in the air handler and adjacent connections represents 5.3% of the system air flow (4.6% on the return side and 0.7% on the






Figure 64 Thermograph of air being drawn from the attic to the air handler in a Florida house

supply side). This is a concern, when considering that a 4.6% return leak from a hot attic (peak conditions; 120°F and 30% RH) can produce a 16% reduction in cooling output and 20% increase in cooling energy use (Cummings and Tooley, 1989), and this was only from the air handler and adjacent connections. (*Figure 64*)

#### "Total" Duct Leakage

Some important observations were made from the extended test data in 20 houses. Total leakage on the return side of the system (including the air handler and return connection) was 53 cfm with weighted operating pressure on the return side of about -100 Pa (including the air handler), operating return leakage was calculated to be 122 CFM, or 9.7% of the rated system air flow.

Total leakage on the supply side of the system (Q<sub>25s,total</sub>) was very large, at 134. The ASHRAE 152P method suggests using half of the supply plenum pressure as an estimate of the overall supply ductwork operating pressure, if the actual duct pressures are not known. For the 20 systems with extended testing, supply plenum pressure was 73.3 Pa. Based on a pressure of 37 Pa, actual leakage should be 167 CFM or about 13.3% of the rated air flow. To test the ASHRAE divide-by-two method, supply duct operating pressure measurements were taken from 14 representative systems. These averaged 35.9 Pa, compared to 65.7 Pa for the supply plenums for those same 14 systems. For these systems, the duct pressure was 55% of the supply plenum pressure - making the ASHRAE method a reasonable method for estimating central Florida home's supply ductwork operating pressures.

However, the ASHRAE method wasn't reasonable for estimating central Florida home's <u>return</u> ductwork operating pressures. For these 20 systems, 38% of the  $Q_{25r,total}$  was in the air handler and 62% of the  $Q_{25r,total}$  was in the return ductwork. Given an air handler pressure of -133 Pa, a return plenum pressure of -81.5 Pa, and return duct pressure of approximately -70 Pa, the weighted return side pressure was approximately -95 Pa. By contrast, the ASHRAE method predicted -41 Pa. Clearly, in systems with a single, short return duct plenum like those

commonly found in Florida, the actual operating pressure should be greater than the return plenum, maybe by as much as 1.2 times the plenum pressure.

Return side leakage is available on 58 of the 69 systems. Return leak air flow  $(Q_{r,total})$  combined for the air handler, return connection, and the return ductwork was found to be 152.4 CFM, or 11.8% of total rated system air flow for this group. For this larger sample,  $Q_{r,total}$  is considerably greater than for the 20 houses with extended testing. These alarming results show that even in these newly constructed homes about 12% of return air and 13% of supply air duct systems are leaking.

#### Duct Leakage to "Out":

In 20 homes, duct leakage to "out" was measured. (*Table 38*) On average, 56% of the leakage of the return ductwork and supply ductwork was to "out." "Out" is defined as outside the conditioned space, including buffer spaces like an attic or garage. The fraction of leakage that was to "out" varied by air handler location. For return ductwork, the proportion of total leakage to "out" is 81.4% for attic systems, 67.6% for garage, and 28.0% for indoors. For supply ductwork, the proportion of total leakage to "out" was in the range of 52% to 56% for all three locations.

Table 38 Portion of duct leakage to outdoors [ $(Q_{25,out}/Q_{25,total}) * 100$ ].						
Air Handler Location	Return	Supply	<b>Entire Duct System</b>			
Attic	81.4%	56.5%	63.2%			
Garage	67.6%	51.7%	56.0%			
Indoors	28.0%	52.6%	37.1%			

The attic return ductwork was the most predictive variable to "out" leakage findings. All of the return ductwork for attic units was located in the attic. Much of the return ductwork for other units was located in the house. As a consequence, the energy penalty associated with locating the air handler in the attic was greater than indicated in the computer modeling results in Table 39, since the modeling only considered the leakage of the air handler cabinet and the adjacent connections, and not the return ductwork leakage.

		0			or three loca ssure. Sam			
	Attic (cf	m)	Garage (	cfm)	Indoors (c	efm)	Combine	d (cfm)
Test	Total	Out	Total	Out	Total	Out	Total	Out
Q <sub>25,r</sub> [58]	61.9	50.4	93.3	63.1	67.8	19.0	75.7	44.9
Q <sub>25,s</sub> [20]	109.1	61.6	170.6	88.2	119.5	62.9	134.3	71.4
Q <sub>r</sub> [58]	118.1	96.1	194.4	131.4	134.6	37.7	152.4	90.4
Q <sub>s</sub> [20]	135.6	76.6	212.0	109.6	148.5	78.1	166.9	88.7

Table 39 shows that the operating supply leakage to "out" was large for all three air handler locations, averaging 89 CFM. The average operating return leakage to "out" was slightly larger, at 90 CFM. However, there was a large variation between air handler locations; 96 CFM for attic systems, 131 CFM for garage systems, but only 38 CFM for indoor systems. From an energy perspective, the attic systems experienced the greatest "real" energy penalties, because all of the return ductwork and air handlers were located in the attic. (Table 38) By contrast, a majority of the return leakage for the garage systems likely came from the garage (which is considerably cooler than the attic). For indoor systems, the return leakage to "out" most likely originated from the attic. However, since the return leakage was so much smaller, the energy impact was likely considerably less than both the attic and the garage systems.

Correlation of Supply Duct Leaks with Number of Registers: When analyzing the supply leakage in the extended test data, a surprising correlation was observed. This correlation indicated a systematic and consistent duct fabrication

problem across a wide range of air conditioning contractors. Figure 65 illustrates this correlation, showing that each supply duct has a remarkably predictable total duct leakage. The coefficient of determination is 0.86, indicating that 86% of the variability in total supply duct leakage was explainable by the number of supply registers. Figure 66 shows a similar relationship between supply leakage to "out" and the number of supply registers. In this case the coefficient of determination was 0.69, indicating that 69% of the variability in total supply duct leakage was explainable by the number of supply registers. Note that one of the two houses with 13 registers showed considerably less leakage than expected. In this case, supply ducts were located in the interstitial space between floors. When the house was taken to -25 Pa, it is probable (though not measured) that the interstitial spaces were substantially depressurized as well, so leaks in those supply ducts would show less air flow (i.e., less pressure differential = less leakage air flow) and therefore be under-represented.

The data suggest that a duct leakage problem occurs in nearly all new homes. Researchers identified three issues that create most of the leakage: (1) the connection of the supply register or return grill (Figure 68), (2) the boot (supply box) to sheet rock connection (Figure 67), and (3) number of supply registers. the flex duct to collar connection. The supply




Figure 65 Supply CFM25 "total" leakage versus the number of supply registers.




Figure 66 Supply CFM25 "out" leakage versus the

register or return grill leakage typically shows as supply leakage in the "total" test. It usually occurs when the register or grill does not fit snugly to the ceiling or wallboard. Issues two and three show up as leakage to both "out" and "total."

Figure 67 shows how flexible duct connections typically are made. In some cases metal tape is

used, but the tape wrinkles when applied to complex angles and over bumps associated with these connection types. Although small in size, these cumulative wrinkles at each connection allow air to pass through.

# Computer Modeling for Florida Energy Code Air Handler Multipliers:

FSEC researchers performed simulations and developed air handler multipliers for the Florida Energy Code using this study's simulation results. Researcher used the FSEC 3.0 model, a general building simulation program developed in 1992. This program provided simultaneous detailed simulations of a whole building system, including energy, moisture, multi-zone air flows, and air distribution systems.

In 2001, modeling had been performed to develop initial air handler multipliers. These multipliers were based on estimated  $Q_{25}$  and duct operating pressures. At the time of the 2001 modeling, there was essentially no data on air handler and connection leakage. Modeling for this project was performed again, but this time using the results of the 69 field tested homes.



Figure 67 Flexible duct to metal collar connection.



Figure 68 Gaps at the supply register to drywall joint

The modeling inputs used in 2001 and those from the current study are shown below. (*Table 40*) Note that the same  $Q_{25}$  and operating depressurization (dP) values was used for all air handler locations, since there was essentially no difference between the  $Q_{25}$  values for attic, garage, and indoor air handler locations when gas furnace units were removed from the analysis.

Table 40 Air handler (AH) and connection inputs for 2001 and current project computer modeling.								
2001 Q <sub>25</sub> AH Study Q <sub>25</sub> 2001 dP AH Study dP								
Return connection	8.7	3.9	-40	-86.1				
AH – depressurized portion	48.5	17.6	-42	-139.1				
AH – pressurized portion	9.6	2.8	43	106.5				
Supply connection	7.8	1.6	32	58.2				
Total	74.6	25.9						

While the  $Q_{25}$  leakage for the air handler and connections was about 65% less than earlier estimates, operating pressures were much higher. The air handler multipliers based on the current computer modeling results are presented in *Tables 41*, 42, and 43. Modeling of air handler energy use also was performed for the air handlers located outdoors, despite the fact that no field data was collected for outdoor units. The modeling input parameters were the same as the other

air handler locations as shown in *Table 40*. Note also that the air handler multipliers for the attic, indoors, and outdoors are normalized to the garage, since this location was considered the baseline. The final report for this study can be viewed online at: <a href="http://www.fsec.ucf.edu/bldg/pubs/cr1357/index.htm">http://www.fsec.ucf.edu/bldg/pubs/cr1357/index.htm</a>.

Table 41 Florida Energy Code AH Multipliers for South Florida.							
	Winter			Summer			
AH Location	Old	2001	new	old	2001	new	
attic	1.04	1.15	1.12	1.04	1.09	1.06	
garage	1.00	1.00	1.00	1.00	1.00	1.00	
indoors	0.93	0.91	0.94	0.93	0.91	0.92	
outdoors	1.03	1.08	1.06	1.03	1.03	1.01	

Table 42 Florida Energy Code AH Multipliers for Central Florida.							
	Winter	inter			Summer		
AH Location	Old	2001	new	old	2001	new	
attic	1.04	1.11	1.08	1.04	1.10	1.08	
garage	1.00	1.00	1.00	1.00	1.00	1.00	
indoors	0.93	0.92	0.94	0.93	0.90	0.92	
outdoors	1.03	1.09	1.05	1.03	1.02	1.01	

Table 43 Florida Energy Code AH Multipliers for North Florida.							
	Winter	Winter			Summer		
AH Location	Old	2001	new	old	2001	new	
attic	1.04	1.10	1.03	1.04	1.11	1.08	
garage	1.00	1.00	1.00	1.00	1.00	1.00	
indoors	0.93	0.93	0.94	0.93	0.91	0.92	
outdoors	1.03	1.07	1.02	1.03	1.02	1.01	

#### **Air Conditioning Condenser Fan Efficiency**

Florida Solar Energy Center, Laboratory Facilities

Cocoa, Florida

Research by BAIHP Researchers Danny Parker and John Sherwin

# **Purpose**

The purpose of this study is to develop an air conditioner condenser fan that reduces the electric energy use of the condensing unit (*Figure 69*). To accomplish this, researchers are designing and producing more aerodynamic fan blades and substituting smaller horsepower (HP) motors which achieve the same air flow rates as the larger, less efficient motors typically used.

# 4<sup>th</sup> Budget Period

During the 4th budget period, researchers developed baseline data for the fan power use in a standard condensing unit (Trane 2TTR2036) and tested a new prototype design: "Design A5" with five asymmetrical blades

Baseline data included condenser airflow, motor power, sound levels, and condenser cabinet pressures. Test results favorably compared with the manufacturer's test data. An experimental set of fan blades, "Design-A5," designed for a 1/8 hp motor at 850 rpm was numerically created and then successfully produced



Figure 69 Air conditioning condenser fan and diffuser.

using rapid prototyping. These prototype blades were substituted on the original condenser, and all test measurements were redone. Design-A5 was found to reduce power use by 20% (40 watts) with approximately equivalent airflow to the original condensing blade design.

# 5<sup>th</sup> Budget Period

During the 5th budget period, activities included re-calibration and improvement of the test equipment configuration, refinement of various designs, and patent filing.

Re-calibration and Improvement of Test Equipment Configuration

The air flow measurement equipment was re-calibrated by the Energy Conservatory in Minneapolis in accordance with ANSI/ASHRAE 51-1985 ("Laboratory Methods of Testing Fans for Rating."). Testing determined that the "flow cube" could be modified with settling screens and a flow straightener to yield a 5% absolute flow accuracy and a 2% relative accuracy from the test equipment. Also, the test configuration was moved indoors in order to better measure sound and also to reduce test variability from wind-related effects. Noise measurement protocol improved to comply with procedures used by the air conditioning industry.

Continued Testing to Refine the Identified Condenser Fan and Condenser Top Design All fans were re-evaluated after bringing the test apparatus into compliance with ANSI/ASHRAE 51-1985 ("Laboratory Methods of Testing Fans for Rating.") New fan prototypes "Design-D" and "Design E" were tested as well as a diffuser for a 27" fan and a specially prepared Electronically Commutated Motor (ECM) provided by General Electric.

All designs were also tested with the conical diffuser with 20-27% increases in measured flow from the low rpm designs, which use 8-pole motors. Sound measurements (*Table 44*) also showed large advantages with as much as a 4 dB reduction in fan sound level over the standard fan. The final test prototype with diffuser and fan is shown in *Figure 70*.

Table 44 Sound measurements for various fan and housing designs								
Тор	Fan	Motor	Flow	Power	Sound			
OEM/ Starburst	OEM	6-pole	2170 cfm	197 W	63.0 dB			
OEM-Foam	OEM	6-pole	2230 cfm	198 W	63.0 db			
Wire top	OEM	6-pole	2180 cfm	188 W	62.0 dB			
Wire-Foam	OEM	6-pole	2250 cfm	190 W	62.0 db			
OEM-foam	A5	8-pole	1945 cfm	145 W	62.0 dB			
Wire-foam	A5	8-pole	2110 cfm	146 W	60.0 dB			
WhisperGuard w/foam	A5	8-pole	2300 cfm	143 W	58.5 dB			

#### Presentation and Commercialization

In January, BAIHP researcher Danny Parker made a presentation at the DOE Expert meeting on HVAC and Fans in Anaheim, California and participated in productive meetings with Trane Corporation in May 2004 to discuss licensing of the technology under an existing non-disclosure agreement.

#### Patents Pending

U.S. Application Serial No. 10/400,888, Provisional applications 60/369,050 / 60/438,035 & UCF-449CIP; WhisperGuard (UCF-Docket No. UCF-458)

*Key Improvements from WhisperGuard Technology* Tested Performance with Trane TTR2036 Condenser:

- Provides 46 Watt reduction in fan power (144 W vs. 190 Watts)
- Increases condenser air flow by 130 cfm (6% increase in fan flow)
- Provides 102 W power reduction with ECM
   142 motor
- Reduce ambient fan-only sound level by 4-5
   dB
- ECM motor allows lower fan speeds for ultraquiet night operation, higher flows for maximum capacity during very hot periods (temperature based control)
- Attractive hi-tech diffuser appearance



Figure 70 Final test prototype with diffuser and fan.

#### Key Technologies Employed

- High efficiency 5-bladed asymmetrical fan moves air quietly at lower fan speeds
- Diffuser top for effective pressure recovery increasing air flow at slow speed ranges
- Conical center body reduces exhaust swirl
- Acoustic sound control strip to reduce tip losses and control tip vortex shedding

#### **Fenestration Research**

Florida Solar Energy Center, Laboratory Facilities Cocoa, Florida Research by BAIHP Researcher Ross McCluney

# American Society of Heating, Refrigerating, and Air Conditioning Engineers (ASHRAE) Technical Committee:

In 2002, BAIHP researchers wrote a statement of work for the development of a methodology to calculate solar spectral distributions incident on windows for various sun positions and atmospheric conditions. ASHRAE approved the project and sent it out for bid. Completion of this work project should make it much easier to determine the true solar heat gain through spectrally selective fenestration systems for varying atmospheric conditions and solar altitude angles.

#### Calorimetric Measurements of Complex Fenestration Systems

FSEC's research calorimeter will be used both indoors with the FSEC Vortek solar simulator and outside under natural solar radiation, on its Sagebrush solar tracker, for window solar heat gain experiments. The results of this testing will offer a way to test the solar gain properties of complex and other non-standard fenestration options for industrialized housing, such as exterior and interior shades and shutters, and those placed between the panes of double pane windows.

# Sagebrush Solar Tracker

The computer program running the calorimeter, the Sagebrush tracker, and both together is complete. It contains a user-friendly graphic interface and offers a wide variety of experimental opportunities. There are many channels for adding additional temperature sensors and the calorimeter/tracker can be operated with either the sun as a source - in a variety of tracking modes - or with FSEC's Vortek solar simulator.

To conduct outdoor testing, the Neslab chiller must be connected to the flow meter, the temperature sensors to the calorimeter, and the calorimeter mounted on the tracker. The Sagebrush tracker now is functional, responding properly to commands sent from the computer, rotating in altitude, and azimuth and stopping when the limit switches are encountered. A telescopic sight and level for positioning it outdoors in the proper orientation for accurate solar tracking has been designed and is near fabrication completion.

The Neslab chiller and remote controller have been connected to a Gateway laptop computer and a RS-485 serial interface card necessary to operate the calorimeter has been installed. Researchers can now send commands and receive data from the chiller. Although the calorimeter is designed to work directly with the existing FSEC hydronic loop used for testing solar collectors, the Neslab will give an independent, standalone capability to the calorimeter. (*Figure 71*)

The water flow meter purchased for measuring the flow into the calorimeter has been successfully connected to the Agilent (HP) 34970A data acquisition system and its measurements were incorporated into the calorimeter operating program. Temperature sensors also successfully connected to the data acquisition system, are reading properly, and have been incorporated into the calorimeter program. The program has coding to include a number of additional temperature channels once the temperature probes have been received and installed in the calorimeter. Another 20-channel input



Figure 71 Side view of calorimeter before it was mounted on the Sagebrush Tracker.

card is being purchased for the Agilent, to permit additional temperature readings. Knowing the flow rate and temperature difference, the heat delivered to the water by the calorimeter can now be accurately determined.

Now that all portions of the system are operational, researchers will configure the outdoor system, verify, and begin testing in Year 5.

#### Vortek Solar Simulator

In 2003, the Vortek Simulator was fired up and operated reliably on the calorimeter testing with FSEC's solar collector test apparatus. As expected, a few computer and other problems delayed initial data collection by a couple of days. However, these problems were corrected and testing proceeded normally.

During testing, the calorimeter was connected to the existing facility's hydronic loop, which was developed over a period of years to a temperature stability of 0.01 degrees centigrade. The irradiance level measured about 820 watts per square meter over an aperture of 0.557 square meters. The calorimeter was tested as though it were a flat plate collector, to obtain its efficiency curve. This was used to infer the thermal losses and solar heat gain coefficient of the eighth inch clear single pane of glass used for the test. The nominal wind speed was set by the laminar blower to five miles per hour. The coolant flow was run at levels of 0.2, 0.5, and 1.0 gallons per minute (GPM), and at varying inlet temperatures.

For all test runs, steady state conditions were established by observing the outlet temperature in a real-time plot as equilibrium was approached. During periods of non-equilibrium, the recorded data was used to measure the first-order system time constant, a function of the flow rate. The calorimeter time constant varied from 1.5 minutes at 1.0 GPM to 6.9 minutes at 0.2 GPM. These time constants were obtained by blocking the incident beam and watching the decay in outlet temperature.

#### Skylight Dome Transmittance

Researchers completed work on the skylight dome transmittance, adding a spherical shape to the cylindrical one previously used. The ray tracing programming was changed to eliminate reflection of rays approaching the dome from the inside, for comparison with the analytical model, which does not yet include internal reflections. The difference between the two computational approaches, at a  $30^{\circ}$  solar zenith angle is 1.7%, considered acceptable for rating skylight performance.

With both cylindrical and spherical dome models, transmittance at large solar zenith angles above 60 is substantially greater than for a horizontal flat plate. This is because most of the rays incident on the dome and entering the skylight are incident on the dome close to perpendicular, where dome transmittance is highest.

#### Energy Gauge USA and Energy Gauge FlaRes

BAIHP mapped a table of window and shade characteristic simulations that could be run with these two programs. These runs will be used to determine the energy use of various fenestration options for Florida residences and to guide the preparation of instructional materials.

#### Florida Market Transformation

From the beginning of the BAIHP program, researchers have provided technical background information and support to the Alliance to Save Energy and the Efficient Windows Collaborative to promote the sale and installation of energy efficient fenestration in hot climates (such as Florida) and other areas for both conventional and industrialized homes. BAIHP also provides

advice, technical information, and educational information to energy companies regarding window energy performance.

National Fenestration Rating Council (NFRC) Technical Committee
In 2002, BAIHP presented a final report at a Task Group meeting in Houston, on the NFRC-funded work to develop a draft standard practice for the rating of tubular daylighting devices. That project is now complete.

In 2001, BAIHP researchers performed a number of ray traces on a highly reflective cylinder of varying lengths, using the trace results to determine the cylinder's transmittances for different interior surface reflectivities (from 90% to 100%). These results generated a "default table" for determining the transmittance of this tubular daylighting component. Using simplified assumptions, and then multiplying the tube transmittance by the top and bottom dome transmittance results, researchers determined the total transmittance for a chosen sun angle. Based on the findings, BAIHP provided NFRC and the industry with a list of suggested research projects to test and develop this methodology further. One of these submitted projects was sent out for bid by ASHRAE in Year 4 and is expected to begin in Year 5.

# Tubular Daylighting Device SHGC and VT Value Calculations

Following a request from the TDD industry, a sequence of operations and a new computer program were written to access the Window 5 glazing database and obtain from it the spectral transmittance and front and back reflectance data for any sheet of glazing in that database which might be used in making the top dome of a tubular daylighting device. This permits determination of the input parameters needed to run TDDTrans. The computer program was posted for free download and is available by clicking on <a href="http://fsec.ucf.edu/download/br/fenestration/software/TddTrans-Beta/TDDTrans.exe">http://fsec.ucf.edu/download/br/fenestration/software/TddTrans-Beta/TDDTrans.exe</a>.


#### Access sequence:

- Download and run the Optics 5 program.
- Select the glazing to be used in the tubular daylighting device.
- Export its spectral data file as a standard ASCII text file.

#### **Reflective Roofing Research**

Florida Solar Energy Center Laboratory Facilities, Cocoa, Florida Research by BAIHP Researchers Danny Parker and John Sherwin

Improving attic thermal performance is fundamental to controlling residential cooling loads in hot climates. Research shows that the influence of attics on space cooling is not only due to the change in ceiling heat flux, but often due to the conditions within the attic, and their influence on duct system heat gain and building air infiltration. (*Figure 72*)



The importance of ceiling heat flux has long been recognized, with insulation a proven means of controlling excessive gains. However when ducts are present in the attic, the magnitude of heat gain to the thermal distribution system can be much greater than the ceiling heat flux. This influence may be exacerbated by the location of the air handler within the attic space - a common practice in much of the southern US. Typically an air handler is poorly insulated and has the greatest temperature difference at the evaporator of any location in the cooling system. It also has the greatest negative pressure just before the fan so that some leakage into the unit is inevitable.

The Flexible Roof Facility (FRF) is an FSEC test facility designed to evaluate five roofing systems at a time against a control roof with black shingles and vented attic (*Figure 73*).

# 5<sup>th</sup> Budget Period Experiments

The testing evaluates how roofing systems impact summer residential cooling energy use and peak demand. In the summer of 2003, the roofing systems tested are listed in *Table 45*. Cell numbering is from left to right beginning with the second cell in from the left.

Table 45	5 Roofing systems tested at the FSEC Flexible Roofing Facility, Summer of 2003
Cell#	Description
1	Galvalume®* unfinished 5-vee metal with vented attic (2 <sup>nd</sup> year of exposure)
2	Sealed attic with proprietary configuration
3	High reflectance brown metal shingle with vented attic
4	Galvanized unfinished 5-vee metal with vented attic (2 <sup>nd</sup> year of exposure)
5	Black shingles with standard attic ventilation (Control Test Cell)
6	standing seam metal with vented attic (2 <sup>nd</sup> year of exposure after cleaning)

<sup>\*</sup> Galvalume is a quality cold-rolled sheet to which is applied a highly corrosion-resistant hot-dip metallic coating consisting of 55% aluminum 43.4% zinc, and 1.6% silicon, nominal percentages by weight. This results in a sheet that offers the best protective features characteristic of aluminum and zinc: the barrier protection and long life of aluminum and the sacrificial or galvanic protection of zinc at cut or sheared edges. According to Bethlehem Steel, twenty-four years of actual outdoor exposure tests in a variety of atmospheric environments demonstrate that bare Galvalume sheet exhibits superior corrosion-resistance properties.

All had R-19 insulation installed on the attic floor except in the configuration with the sealed

attic (Cell #2) which had R-19 of open cell foam sprayed onto the bottom of the roof decking. The measured thermal impacts include ceiling heat flux, unintended attic air leakage and duct heat gain.

Cell #2 had a proprietary configuration which is not reported upon in this report.



Figure 73 Flexible Roof Facility in summer of 2003 configuration.

A major thrust of the testing for 2003 was comparative testing of metal roofing under long term exposure. Given the popularity of unfinished metal roofs, we tested both galvanized and Galvalume® roofs in their second year of exposure. Galvalume® roofs are reported to better




Figure 74 Estimated combined impact of duct heat gain, air leakage from the attic to conditioned space and ceiling heat flux on space cooling needs on an average summer day in a  $2,000 \text{ ft}^2$  home.

maintain their higher solar reflectance than galvanized types. Average daily mid-attic maximum temperatures for the Galvalume® and galvanized metal roof systems showed significantly better performance for Galvalume® product (17.5°F and 13.1°F cooler than the control dark shingle respectively).

Other than the sealed attic case, the white metal roof results in the coolest attic over the summer, with an average peak of only  $94.6^{\circ}F - 22.1^{\circ}$  cooler than the peak in the control attic with dark shingles. The highly reflective brown metal shingle roof (Cell #3) provided the next coolest peak attic temperature. Its average maximum daily mid-attic temperature was  $101.5^{\circ}F$  ( $15.2^{\circ}F$  lower than the control dark shingle cell). While the brown metal shingle roof's reflectance was lower than the two metal roofs and white metal roof we observed evidence that the air space under the metal shingles provides additional effective thermal insulation.

We also estimated the combined impact of ceiling heat flux, duct heat gain and unintended attic air leakage from the various roof constructions. All of the alternative constructions produced lower estimated cooling energy loads than the standard vented attic with dark shingles (*Figure 74*). The Galvalume® roof clearly provided greater reductions to cooling energy use than the galvanized roof after two summers of exposure.

One important fact from our testing is that nighttime attic temperature and reverse ceiling heat flux have a significant impact on the total daily heat gain, particularly for the metal roofs. The rank order in Table 46 shows the percentage reduction of roof/attic related heat gain and approximate overall building cooling energy savings (which reflect the overall contribution of the roof/attic to total cooling needs):

Table	Table 46 Roof cooling load reduction and overall cooling savings, Summer 2003 experiments						
Rank	Description	Roof Cooling Load Reduction	Overall Cooling Savings				
1	White metal with vented attic (Cell #6)	47%	15%				
2	High reflectance brown metal shingle with vented attic (Cell #3)	29%	10%				
3	Galvalume® unfinished metal with vented attic (Cell #1)	25%	8%				
4	Galvanized unfinished metal roof with vented attic (Cell #4)	16%	5%				

The relative reductions are consistent with the whole-house testing recently completed for FPL in Ft. Myers (Parker et al., 2001). This testing showed white metal roofing having the largest reductions, followed by darker constructions.

# 4<sup>th</sup> Budget Period Experiments

The Flexible Roof Facility (FRF), located in Cocoa, Florida, is designed to simultaneously evaluate five roofing systems against a control roof with black shingles and vented attic. (Figure 75) The test evaluated how roofing systems impact summer residential cooling energy use and peak demand. In the summer of 2002, six roofing systems were evaluated as described in *Table 47*.



Figure 75 Flexible Roof Facility in summer 2002 configuration. Cells are numbered from left to right starting with the second cell in from the left.

	Table 47 Roofing systems tested and associated energy savings at the FSEC Flexible Roofing Facility, Summer of 2002							
Cell #	Roof Material	Venti- lation	Roof Cooling Load Reduction	Overall Cooling Savings				
#1	Galvalume® unfinished 5-vee metal	vented	32%	11%				
#2	double roof with radiant barrier (ins roof deck)	sealed	7%	2%				
#3	high reflectance ivory metal shingle	vented	38%	12%				
#4	galvanized unfinished 5-vee metal	vented	22%	7%				
#5	black shingles (control cell)	vented	control	control				
#6	white standing seam metal	vented	7%	2%				

All roof cells had R-19 insulation installed on the attic floor, except the double roof configuration (Cell #2) which had a level of R-19 open cell foam sprayed onto the bottom of the roof decking. Measured thermal impacts included ceiling heat flux, unintended attic air leakage, and duct heat gain.

The sealed attic double roof system (Cell #2) provided the coolest attic space of all systems tested (average maximum mid-attic temperature was 81.1°F), and therefore had the lowest estimated impact due to return air leakage and duct conduction heat gains. However this cell also had the highest ceiling heat flux of all strategies tested, and recorded the most modest space cooling reduction (7%), relative to the control roof.

Metal roof testing was given more emphasis in 2002 due to the popularity of these products. Researchers tested both galvanized and Galvalume® roofs. Galvalume is a cold-rolled sheet with a highly corrosion-resistant hot-dip metallic coating application of 55% aluminum 43.4% zinc,




Figure 76 2002 estimated combined impact of duct heat gain, air leakage from the attic to conditioned space, and ceiling heat flux on space cooling needs on an average

and 1.6% silicon. These roofs are reported to better maintain solar reflectance than galvanized roofing systems. Average daily mid-attic maximum temperatures for the Galvalume<sup>®</sup> and galvanized metal roof systems were roughly similar (19.6°F and 17.3°F cooler than the control roof, respectively). The estimated total heat gain for these roof cells also was relatively close. The highly reflective ivory metal shingle roof (Cell #3) provided the coolest peak attic temperature of all the cells without roof deck insulation. Its average maximum daily mid-attic temperature was 93.3°F (23.4°F lower than the control dark shingle cell). While the ivory metal shingle roof's reflectance was slightly lower than the two metal roofs and white metal roof, researchers noted that the air space under the metal shingles provided additional effective thermal insulation.

Researchers also estimated the combined impact of ceiling heat flux, duct heat gain, and unintended attic air leakage from the various roof constructions. All of the alternative roofing treatments produced lower estimated cooling energy loads than the standard vented attic with

dark shingles. (*Figure 76*) The Galvalume® roof clearly provided a greater cooling energy use reduction than the galvanized roof. This also was true during the 2001 study. Nighttime attic temperatures and reverse ceiling heat flux have a significant impact on the total daily heat gain, particularly for metal roofs.

# 3<sup>rd</sup> Budget Period

In the 2001 testing, Cell #2 with the double roof/sealed attic showed the lowest attic temperatures and narrowest temperature range. (*Table 48; Figures 77 and 79*) Peak attic temperatures in Cell #2 were 5°F to 6°F lower than this same sealed cell the year before, without the double roof. This indicates that the double roof did provide a substantial benefit. Since there is no insulation on the attic floor though, there still is a




Figure 77 2001 Experimental roof cell. Cells are numbered from left to right starting with the cell second in from the left.

significant heat gain across the ceiling. In fact, the ceiling heat fluctuation actually is higher than the reference Cell #5. (Figure 78)

The true impact of the double roof construction of Cell #2 is most likely a combination of the benefits of a cooler attic space that reduces duct heat gain and minimizes the effects of air leakage from the attic into the house, and the drawback of the higher ceiling heat flux. Cell #3 with its spectrally selective dark brown metal shingles, produced lower attic temperatures at night, but higher roof deck temperatures (which were most likely due to the insulating quality of the shingles which have an air space underneath them).

	Table 48 Roofing systems tested and attic temperatures at the FSEC Flexible Roofing Facility, Summer of 2001								
Cell #	Roof Material	Venti- lation	Avg Attic Temp	Max Attic Temp					
#1	white tile (weathered)	sealed	84.6	111.2					
#2	double roof with radiant barrier (ins roof deck)	sealed	78.4	85.4					
#3	brown IR selective metal shingle	vented	85.0	110.8					
#4	terra cotta tile (weathered)	vented	89.0	124.3					
#5	dark shingles (control)	vented	91.0	143.4					
#6	white standing seam metal (weathered)	sealed	84.0	115.5					



Roofing Experiment with Habitat for Humanity in Fort Myers, Florida

In July 2000, FSEC and Florida Power and Light instrumented six side-by-side Habitat for Humanity homes in Ft. Myers with identical floor plans, orientation, and ceiling insulation, but with different roofing systems as described in *Table 49*. A seventh monitored house contained an unvented attic with insulation on the underside of the roof deck rather than on the ceiling.

Each unoccupied home was monitored from July 8 through July 31, 2001 to collect building thermal and air conditioning power data. *Table 50* presents the cooling performance of the roofing systems clearly showing the energy-saving benefits of reflective roofing systems in Florida, especially the tile and metal roofs with solar reflectance between 65% and 75%.

Table 49 Roofing systems tested at side-by-side Habitat for Humanity homes in Ft. Myers Summer of 2000								
Code								
RGS	Standard dark shingles (control)	RTB	Terra cotta "barrel" S-tile roof					
RWS	Light colored shingles	RWB	White "barrel" S-tile roof					
RWM	White metal roof	RWF	White flat tile roof					
RSL	Standard dark shingles with sealed attic							
	& R-19 roof deck insulation							

Table 50 Energy use and savings from roofing systems in Habitat for Humanity roofing study, summer of 2000							
Site	Total kWh	Savings kWh	Saved Percent	Demand kW	Savings kW	Saved Percent	
RGS	17.03			1.63			
RWS	15.29	1.74	10.2%	1.44	0.19	11.80%	
RSL	14.73	2.30	13.05%	1.63	0.01	0.30%	
RTB	16.02	1.01	5.9%	1.57	0.06	3.70%	
RWB	13.32	3.71	21.8%	1.07	0.56	34.20%	
RWF	13.20	3.83	22.5%	1.02	0.61	37.50%	

Table 50 Energy use and savings from roofing systems in Habitat for Humanity roofing study, summer of 2000						
Site	Total kWh	Savings kWh	Saved Percent	Demand kW	Savings kW	Saved Percent
RWM	12.03	5.00	29.4%	0.98	0.65	39.70%

Significant findings: Reflective roofing materials represent one of the most significant energy-saving options available to homeowners and builders. These materials also reduce cooling demand during utility coincident peak periods, and are potentially one of the most effective methods for controlling demand.

- Based on comparative data from August of 2000, the maximum decking temperatures in the sealed attic home were 23°F higher than the control home (177° versus 154°). After the installation of white shingles in midsummer, the highest deck temperature from the sealed attic home measured only 7° higher than the control in August of 2001 (161° versus 154°).
- An additional month's data was collected with the homes occupied and thermostat set points kept constant. Average cooling energy use for the homes rose by 36%, but there was no decrease in the highly reflective roofing system savings. Additional heat gained from the occupants and their appliance use increased the cooling system runtime and introduced more hot air into the air conditioning duct system.
- In 2001, the average maximum attic air temperature in the terra cotta barrel tile roof home was 15°F hotter than the maximum ambient. After installing a radiant barrier the average difference in August was +9°F. A similar evaluation with the light colored shingles showed that peak attic air temperatures dropped from + 29° to +20°F after installing a radiant barrier.
- Household interior temperature settings varied from one year to the next, making direct energy saving comparisons impossible. Still, the collected data did show that attic air temperatures were reduced by the radiant barrier. On the other hand, measured maximum plywood decking temperatures rose by 11° to 13°F.
- Based on previously evaluated roof buckling problems on the decking of the sealed attic home, researchers decided to install white shingles similar to those on the RWS roof. It was thought that buckling problems likely were caused by excessive heat buildup in this roofing system. White shingles replaced the dark shingles to see if this would drop the roof decking temperature spikes.

# **Return Air Pathway Study**

Research by BAIHP Researcher Neil Moyer with BAIHP Industry Partner Tamarack

#### Scope

In effect since March 2003, Section 601.4 of the Florida Building Code applies to *residential* and *commercial* buildings having interior doors and one, centrally located return air intake per heating and cooling system.

Objective Of The New Florida HVAC Code Requirement

Reduce pressure difference in closed rooms with respect to (wrt) the space where the central return is located to 0.01" water column (wc) or 2.5 pascal (Pa) or less. Pressure imbalances created by restricted return air flow from rooms isolated from the central return by closed interior doors create uncontrolled air flow patterns.

#### Technical Background

Ideally, forced-air heating and cooling systems circulate an equal volume of return air and supply air through the conditioning system, keeping air pressure throughout the building neutral. Each conditioned space in the building should, ideally, be at neutral air pressure at all times.

When a space is under a positive air pressure, indoor air will be pushed outward in the walls, floor and ceiling. When a space is under a negative pressure, air will be pulled inward through the walls, floor and ceiling. Negative and positive air pressures in buildings result from uncontrolled air flow patterns.



Figure 80 Return Air Flow Test Chamber

Section 601.4 of the Florida Building Code specifically deals with the uncontrolled air flow pattern when interior doors are closed thereby reducing return air flow from the closed room, while maintaining the same supply air flow to the room. This imbalance of supply and return air has been addressed conventionally by the common practice of undercutting interior doors to allow return air to flow from the room. This research quantifies the volume of air flow provided by this and other methods of return air egress from closed rooms.

Section 601.4 limits the air pressure imbalance in closed rooms to 0.01" wc or 2.5 pascals when compared to, or with respect to (wrt), the main body of the building where the return is located. With door undercuts, researchers have regularly observed room pressures with respect to the main body of the house (wrt<sub>mainbody</sub>) of +7 pascals (pa) or more. A room with this level of air pressure (+7pa, wrt<sub>mainbody</sub>) is trapping air, starving the heating/cooling system of return air. As the heating/cooling system struggles to pull in the designed amount of air, the resulting negative pressure pulls air into the main body of the building along the path(es) of least resistance. Usually this means that air is flowing through the walls, floor and ceiling from unconditioned spaces or outside environment to makeup for the trapped air in the closed room.

In the closed room, positive pressure builds up when return air is trapped. Conversely, the space with the central return gets depressurized because extra return air is being removed to make up for the air trapped in the closed room. More air is leaving the space (return air) than is entering the space (supply air). The positive pressure in the closed rooms *pushes* air into unconditioned spaces, such as the attic and wall cavities. The negative pressure in the main body of the building *pulls* air from unconditioned spaces. In Florida, the air brings heat and moisture with it that become an extra cooling load. This air is referred to as "mechanically induced infiltration" since the negative pressure drawing infiltration air in was created by the mechanical system.

#### Styles of Pressure Relief

When return air flow is restricted by closed doors, it creates pressure differences between parts of the building. This can be prevented by installing a fully ducted return system, by creating a

passive return air pathway such as a louvered transoms, door undercut, "jump duct", through-wall grilles, or a baffled through-wall grill.

A "jump duct" is simply a piece of flex duct attached to a ceiling register in the closed room and another ceiling register in the main body of the house. A jumper duct provides some noise control while providing a clear air flow path.

A through-wall grille is the simplest and least expensive approach to pressure relief for closed rooms. Holes opposite each other on either side of the wall within the same stud bay are covered with a return air grilles. The downside of this approach is a severe compromise the privacy of the closed room. An improvement on this theme would be to locate one of the grilles high on the wall and the opposing opening low on the wall. Also, such openings in interior wall cavities introduce conditioned air into what is typically an unconditioned space possibly contributing to other building problems.

However, connecting the two openings with a sleeve of rigid ducting forms an enclosed air flow path that limits introduction of conditioned air into the wall cavity but doesn't solve the visual and sound privacy issues. To address this problem, BAIHP Industry Partner Tamarack developed a sleeve with a baffle that can reduce the transfer of light and sound but still provide adequate air flow to minimize pressure differences. The product is called a Return Air Path (RAP).

To validate the effectiveness of this product and other approaches to providing return air pathways, Tamarack and BAIHP researchers devised a test apparatus and conducted experiments in FSEC's Building Science Laboratory.



Figure 81 Installing unbaffled return air flow through wall grille



Figure 82 Installing sound baffled return air flow through wall insert made by Tamarack.

#### Testing Protocol

In May of 2003, a chamber was constructed at FSEC (*Figure 80*) that simulated a frame construction room with an 8 foot high ceiling. A "Minneapolis Duct Blaster" was connected to one end of the room with a flexible duct connection leading out of the room to provide control over pressure in test chamber.

In the middle of the chamber, on a stool, a radio was tuned "off station" to effectively create a standardized level of "white noise" at 57 dBA inside the chamber with the "door" closed. The

temperature at the start of the tests was 80°F at 40%RH. A sound meter was located outside the chamber on a stand 4 feet above the floor and 20 inches from the middle of the chamber wall surface

The sound level in the test facility outside the chamber with the "white noise" turned off was 36.4 dBA and with the "white noise" turned on was 41.5 dBA, an average, sampled over a 30 second period. A series of tests on 31 different set-ups were performed, measuring the flow at 3 different pressure levels and recording a 30 second sound sample with the "Duct Blaster" deactivated.

Tests were made for 6" and 8" jump ducts, five different sized wall openings (*Figure 81*) in different configurations including straight through with and without sleeves, straight through with sleeve and privacy baffle (*Figure 82*), and high/low offset using the wall cavity as a duct, and three different slots simulating three different size undercut doors.

#### Results

*Table 51* summarizes the results of these tests arranged in ascending air flow order based on the results at 2.5 Pascals (0.01" wc), the maximum allowable pressure in a closed room under new requirement in Florida Building Code, Section 601.4.

	Table 51 Air Flow Resulting from Various Return Air Path Configurations at Controlled Room Pressure Difference (ΔP) with respect to Return Zone							
	Air	Flow (cfm	ı) at		Air Flow	Return Air		
	ΔP=1	ΔP=2.5	ΔP=5		to Area	Path	_	
Dim.	ра	ра	ра	Area	Ratio	Configuration	Extra	
6 dia	22	36	52	28	1.29	Jumper Duct		
4x12	26	41	60	48	0.85	Wall Cavity		
4x12	25	42	61	48	0.88	Wall Sleeve	RAP Insert	
4x12	28	45	65	48	0.94	No Sleeve		
4x12	29	46	68	48	0.96	Wall Sleeve		
8x8	31	49	72	64	0.77	Wall Cavity		
12x6	32	52	75	72	0.72	Wall Cavity		
12x6	33	56	82	72	0.78	Wall Sleeve	RAP Insert	
8x8	35	57	81	64	0.89	No Sleeve		
8x8	34	58	83	64	0.91	Wall Sleeve	RAP Insert	
8x8	36	59	85	64	0.92	Wall Sleeve		
12x6	36	60	88	72	0.83	No Sleeve		
12x6	37	60	88	72	0.83	Wall Sleeve		
1 x 30	39	61	88	30	2.03	Slot		
8 dia	38	62	90	50	1.24	Jumper Duct		
1 x 32	42	65	92	32	2.03	Slot		
8x8	40	67	95	64	1.05	Wall Cavity	Two Inside Holes	
8x14	44	70	100	112	0.63	Wall Cavity		
12x12	45	72	103	144	0.50	Wall Cavity		
1 x 36	49	73	103	36	2.03	Slot		
8x14	61	101	146	112	0.90	Wall Sleeve	RAP Insert	
8x14	68	107	153	112	0.96	No Sleeve		

	Table 51 Air Flow Resulting from Various Return Air Path Configurations at Controlled Room Pressure Difference (ΔP) with respect to Return Zone								
		Flow (cfm			Air Flow	Return Air			
	ΔP=1	ΔP=2.5	ΔP=5		to Area	Path			
Dim.	ра	ра	ра	Area	Ratio	Configuration	Extra		
8x14	68	110	154	112	0.98	Wall Sleeve			
12x12	75	119	170	144	0.83	No Sleeve			
12x12	74	120	169	144	0.83	Wall Sleeve			
12x12	74	120	174	144	0.83	Wall Sleeve	RAP Insert		

By comparing the air flow of the slots (door undercut) to the openings with grilles, the detrimental effect of the grille becomes clear. The ratio of air flow (cfm) to the surface area of the slot (in²) is more than 2 to 1 (for example; 30 in² to 61 cfm), whereas with grilles in place the ratio of air flow to area averages 0.83 to 1 (for example; 72 in² to 60 cfm). Similarly, the jump duct (*Figure 83*) assemblies' air flow to area ratios average 1.19 to 1. In any calculation for the size of the through wall assembly, the resistance of the grille becomes the critical factor in determining the size of the opening for achieving the desired flow.

The following formulas account for the grille resistance and maybe used to size return air path openings.

- Door undercuts: Area Sq. In. = CFM/2
- Wall opening with grilles: Area Sq. In. = CFM/.83
- Flexible jumper duct with grilles: Diameter =  $\sqrt{\text{CFM}}$



Figure 83 Return air flow path provided by jumper duct

Although there does not appear to be significant flow improvement when a sleeve is used, such an assembly will reduce the possibility of inadvertent air flow from the wall cavity itself.

The high/low grilles using the wall cavity reach maximum flow at 72 cfm because of the dimensional limitations of the wall cavity itself. Increasing the opening of each grille beyond 112 square inches does not significantly increase the flow of air through the wall cavity.

The accompanying bar chart (*Figure 84*) can be used to select the best method at various air flows while maintaining the room-to-building pressure difference at .01" wc. The strategies are ranked by air flow allowance (cfm) on equivalent to supply air delivered to the room. For example, an 8" jumper duct could be used to maintain 0.01 wc in rooms with supply air up to 60 cfm. Note that these transfer methods are additive so that, for example, combining a 6" transfer duct with a 1" undercut a 30" door, will provide a flow of 95 cfm to be delivered at .01" wc (*Figure 85*) or combining a R.A.P. 12.12 with a 1" undercut would allow up to 175 cfm to be delivered (*Figure 86*). It should be noted that door undercuts are under builder not HVAC control and that the actual dimensions are greatly affected by the thickness of the floor coverings.


#### **Summary**

Ideally buildings with forced air heating/cooling systems are pressure neutral. The same amount of air is removed from the building (and each room) as is supplied to it. However, this balance can be disturbed in homes that have one, centrally located return intake when interior doors are closed, blocking return of air supplied to private rooms. Other factors outside the scope of this study may also result in household pressure imbalances.

These research results are relevant to homes with forced air heating and cooling systems having a single, centrally located return air inlet with no engineered path for return air to exit closed rooms. Such systems pull return air from the whole house as long as interior doors are open. When an interior door is closed, more air is supplied to the closed room than can be removed, or returned, from the room.

Positive pressure builds up in the closed room while a negative pressure occurs in the connected spaces. Positive pressure presses outward on all surfaces and may eventually reduce supply air flow into the closed room and while pushing conditioned air through small breaks in the room's air barrier.

To overcome house pressure imbalances caused by door closure, a variety of passive return path strategies are studied including a product produced by BAIHP Industry Partner Tamarack that overcomes privacy issues associated with through-wall grills. Achievable air flows for jump ducts, through-wall grilles, sleeved through-wall grilles, and the Tamarack baffled through-wall grille are presented.



**Figure 84** Maximum air flow achievable using various return air paths from closed rooms for a give supply at a room pressure of 2.5 pa or 0.1" we with respect to the return zone. For example, an 8" jumper duct could be used to maintain 0.01 we in rooms with supply air up to 60 cfm.

#### **Heat Pump Water Heater Evaluation**

Research by BAIHP Researcher Carlos Colon

BAIHP researcher tested the efficiency of a heat pump water heater manufactured by EMI, a division of ECR International. The unit features a compressor (R-134A refrigerant) with a wrap-around heat exchanger mounted on top of a 50-gallon storage tank. The latest controller board model #AK 4001 was installed during the test.

The temperature regulation of the unit is achieved by an adjustable potentiometer which sets a resistance that is measured by the controller board and translated into the corresponding temperatures. The set temperature is stored in the controller's memory.

The controller logic is designed to operate the heat pump when the temperature in the bottom of the tank drops below the effective dead band temperature of 30°F (20°F deadband + assumed stratification of 10°F). The heat pump shuts off when the temperature in the bottom of the tank has reached 10°F



Figure 87 Airflow measurements using a Duct tester on heat pump cold air discharge side.

below the set point temperature. The upper element of the tank operates only when the temperature in the upper tank reaches 27°F below the set point temperature.

During laboratory testing the controller's performance was evaluated by measuring inlet and outlet water temperatures using thermocouples mounted to the copper inlet and outlet pipes as well as a Fluke hand-held thermometer inserted into the hot water outlet stream. One minute average measurements during draws were in agreement with the 10°F stratification logic utilized by EMI.

Also, following a series of hot water draws during the efficiency test (described below), the compressed refrigerant heat was able to replenish the tank to the 130 °F temperature level. However, following the heating recovery, neither compressor or resistance element were activated during standby until three days later when bottom tank temperatures dropped below 95°F. The compressor was called into operation when the tank was submitted to a hot water draw which triggered the ON compressor event in less than a minute.

Table 52 is a summary of electrical efficiency results generated from three tests performed in the laboratory. Tank pre-heating for test #1 and #2 were performed in a similar way, by forcing the compressor to turn "ON". The tank was allowed to loose heat on standby (1-2 days) and then purged with a draw of at least 30 gallons of new water. The purge forced the compressor to operate. Preheating for the test #3 was performed with the tank relatively hot and only twelve gallons of hot water were purged. This might explain the higher outlet temperatures read during test 3. For all three tests, we attempted to heat water so that initial hot water draws were near 130 °F (+/- 5 °F). However, we noticed that temperatures at the top of the tank (upper level) increased slightly with each purge (i.e., 10.7 gallon draw). During the third test shown in *Table 52* for example, outlet temperatures during the first draw averaged 129.2 °F, but during the last draw temperatures reached an average of 143.4 °F. The values shown for test #3 shows an

overall hot water delivery temperature (T<sub>outlet</sub>) of 136.6 °F. The controller never called for compressor or auxiliary energy when left on standby during the completion of the test (24-hr.).

Tal	Table 52 Electrical Efficiency Results from Laboratory Tests								
	Total Gallons	Average	Average	Total	Total				
Test	<b>Drawn</b>	T <sub>inlet</sub> (°F)	T <sub>outlet</sub> (°F)	Qout kWh	Qin kWh	СОР			
#1	63	82.3 °F	133.2 °F	7.756	3.974	1.95			
#2	53.5	82.1 °F	131.2 °F	6.533	3.516	1.86			
#3	65.9	82.0 °F	136.4 °F	8.789	4.254	2.06			

#### Conclusions

The WattSaver<sup>TM</sup> heat pump water heater is rated with an energy factor (EF) of 2.45 and clearly demonstrates that heating water can be accomplished at a relative higher efficiency when compared to conventional electric water heaters. Installed in a conditioned space, and under operation with inlet water temperatures above 80 °F (e.g., Central Florida summer water mains temperatures), an average electrical (COP) efficiency of 2.0 was attained. Other measurements and performance indicators are summarized in *Table 53*.

Two caveats to the heat pump water heater's performance was first the delayed recovery during standby which would present larger hot water temperature variation to the residential user. This also leads to diminished hot water capacity during long periods of no hot water use activity. Second, because the compressor's discharge refrigerant (i.e., hottest temperatures) enter the wrap-around heat exchanger at the top of the tank, the unit demonstrated larger hot temperature variations at the tank's upper levels when the top portion was already pre-heated. These stratified tank temperature levels differ from those obtained when heating is started with the tank filled up with mains (colder) water conditions.

Table 53 Summary of Other Measurements and Performance Overview							
Typical Cooling	Current consumption (208 VAC)						
Air Flow rate: 87 CFM (Figure 87)	Compressor2.9 amps						
Top cavity/Fan operating: -6.4 pa	Fans (2): 0.08 Amps/each						
Evaporator Air temp: 73 °F (63%RH entering)	Total 3.08 amps						
/53.1 °F (leaving)							
Condensate: 502.6 g/hr. (1.1 lb/hr)							
Sensible: 1900 Btu/hr.							
Latent: 957 Btu/hr							
Total Capacity: 2,857 Btu/hr							

# NightCool - Building Integrated Cooling System

Study led by BAIHP Researcher Danny Parker

#### Technical Background

Using a building's roof to take advantage of long-wave radiation to the night sky has been long identified as a potentially productive means to reduce space cooling in buildings. This is because a typical roof at 75 F will radiate at about 55-60 W/m2 to clear night sky and about 25 W/m2 to a cloudy sky. For a typical roof (250 square meters), this represents a cooling potential of 6,000 -

14,000 Watts or about 1.5 - 4.0 tons of cooling potential each summer night. Various physical characteristics (differential approach temperature, fan power, convection and conductance) limit what can be actually achieved, however, so that perhaps half of this rate of cooling can be practically obtained. Even so, careful examination of vapor compression space cooling in many homes in Florida shows that typical homes experience cooling loads averaging 33 kWh per day from June - September with roughly 9.2 kWh (28%) of this air conditioning coming between the hours of 9 PM and 7 AM when night sky radiation could greatly reduce space cooling.

The big problem with night sky radiation cooling concepts has been that they have typically required exotic building configurations. The research literature is extensive. These have included very expensive "roof ponds" or, at the very least, movable roof insulation with massive roofs so that heat is not gained during daytime hours. The key element of this configuration is that rather than using movable insulation with a massive roof or roof ponds, the insulation is installed conventionally on the ceiling. The operation of the system is detailed in the attached schematic.

During the day, the building is de-coupled from the roof and heat gain to the attic space is minimized by the white reflective metal roof. During this time the space is conventionally cooled with a small air conditioner. However, at night as the interior surface of the metal roof in the attic space falls two degrees below the desired interior thermostat setpoint, the return air for the air conditioner is channeled through the attic space by way of electrically controlled louvers with the variable speed fan set to low. The warm air from the interior then goes to the attic and warms the interior side of the metal roof which then radiates the heat away to the night sky. As increased cooling is required, the air handler fan speed is increased. If the interior air temperature does not cool sufficiently or the relative humidity is not kept within bounds (<55% RH) the compressor is energized to supplement the sky radiation cooling. However, by midnight on clear nights, the temperature of the metal will have dropped sufficiently to begin to dehumidify the air introduced to the attic. The collected moisture on the underside of the roof will then drain to collection points at either side of the soffits so that the home can be dehumidified during evening hours by way of only the operation of the blower fan (200-300 W). The massive construction of the home interior (tile floor and concrete interior walls) will store sensible cooling to reduce space conditioning needs during the following day.

### Experimental Design

BAIHP researcher Danny Parker developed an experiment to test the viability of NightCooling in Florida's hot-humid climate. However, construction of a suitable laboratory facility to conduct this study has been delayed. BAIHP is working with UCF and local officials to develop a design allowable under current codes for a pair of free standing, room size structures to serve as a "control" and a "test" case. A schematic of the test case and a similar drawing of the concept in a real home are shown in *Figures 88 and 89*.




Figure 88-Scehmatic design for NightCool test facility.




Figure 89 Schematic of NightCool concept in typical residential building.

# IV BAIHP WEB PAGE, TRAINING and PUBLICATIONS

#### **BAIHP WEB PAGE, TRAINING, and PUBLICATIONS**

#### **BAIHP Web Page**

The BAIHP web page at <a href="www.baihp.org">www.baihp.org</a> (Figure 90) includes an Overview of the project, a summary of the types of Activities that BAIHP researchers are engaged in, the names and links for BAIHP Partners, and the names and brief bios for BAIHP Researchers.



Figure 90 BAIHP Home Page at www.baihp.org

Periodic updates are made to the web page in Case Studies of our Partners' BA projects, Current Data from BAIHP experiments, and BAIHP Publications. In addition to those current case studies, experiments, and publications listed in *Table 54*, 44 BAIHP press items are included in *Media Recognition* and 13 Pre-2000 Publications are listed separately in "Publications". (See also BAIHP Publications 09/99-03/04in this document following the BAIHP Training section.)

Contact Us information is given for a variety of project staff, DOE officers, and sub-contractors. The web page has been visited approximately 20,000 times since August of 2000.

Table 54 – BAIHP Web Page Contents for			
Case Studies, Publicat	ions and Current Data		
<b>BAIHP Case Studies</b>	Publications		
<ul> <li>Cold Climate Case Study: High Efficiency North Dakota Twin Homes</li> <li>WCI Communities at Evergrene</li> <li>Show Me the Money: Selling Builders on Systems Engineering</li> <li>Pet House Project</li> <li>Cambridge Homes at Baldwin Park</li> <li>Zero Energy Manufactured Home</li> <li>Six Moisture Home Case Studies</li> <li>Making the DREAM Home a Reality</li> <li>Highly Efficient Central Florida Home</li> <li>Habitat for Humanity - Energy Star Examples</li> <li>Side-by-side Comparison of Manufactured Homes (Palm Harbor Homes – NCATU Campus)</li> <li>Super Good Cents/Natural Choice Program</li> <li>Portable Classrooms</li> <li>Side-by-side comparison of Manufactured Homes (Stylecrest Sales and Fleetwood Homes)</li> <li>Palm Harbor Homes – 16 Factories in 8 States</li> <li>Habitat for Humanity – Plains, GA</li> <li>The Entry Level Homes Study – Orlando, FL</li> <li>Health House® 1997 – Orlando, FL</li> <li>Health House® 1996 – New Orleans, LA</li> </ul>	<ul> <li>Standards for Clean Air Florida Homes (03/04)</li> <li>Alleviating Moisture Problems in Hot, Humid Climate Housing (01/04)</li> <li>BAIHP Annual Report – Fourth Budget Period (12 04)</li> <li>Achieving Airtight Ducts in Manufactured Housing (09/03)</li> <li>Show Me the Money: Selling Builders on Systems Engineering (04/03)</li> <li>Technical services provided to the HUD Code and modular home industry. (04/03)</li> <li>Measured and Simulated Cooling Performance Comparison; Insulated Concrete Form Versus Frame Construction (08/02)</li> <li>The Building America Industrialized Housing Partnership (05/02)</li> <li>Performance and Impact from Duct Repair and Ventilation Modifications in Two Newly Constructed Manufactured Houses Located in a Hot and Humid Climate (05/02)</li> <li>Moisture Problems in Manufactured Housing: Probable Causes and Cures (11/01)</li> <li>Preventing House Dust Mite Allergens in New</li> </ul>		
Current Data (BAIHP Research)	Housing (11/01)  Design and Construction of Interior Duct Systems		
<ul> <li>Manufactured Housing Lab</li> <li>Highly Efficient Central Florida Home</li> <li>Side by Side Comparison of Manufactured Housing (Palm Harbor – NCATU)</li> <li>Portable Classrooms</li> <li>Stein Residence, Gainesville, FL</li> <li>Zero Energy Manufactured Home</li> <li>ORNL-HFH Zero Energy Home</li> </ul>	<ul> <li>(04/01)</li> <li>Energy Efficiency and Moisture Retention Data Report (2001)</li> <li>Ventilation in US Manufactured Homes (09/00)</li> <li>Evaluation of EnergyGauge® USA, A Residential Energy Design Software, Against Monitored Data (08/00)</li> </ul>		

#### **BAIHP Training**

BAIHP research is communicated to public and industry audiences through the BAIHP web page, conference papers and presentations, and various media coverage. *Table 55* shows training events in reverse chronological order and is divided by budget period. Following the table are summaries of training events organized by audience and a summary of BAIHP web page and media coverage.

Table 55 Training and Presentations by BAIHP Staff January 2002 – December 2004

Month Venue Description Researcher Audience/Attendees

Table 55 Training and Presentations by BAIHP Staff January 2002 – December 2004				
Month	Venue	Description	Researcher	<b>Audience/Attendees</b>
Dec 2004	Performance of	Accepted Paper on Side	McGinley	Energy Efficiency
(pending)	Exterior Envelopes of	by Side Monitoring of		Industry
	Whole Buildings IX,	Energy Star and		-
	Clearwater (FL)	Standard HUD Code		
		Home.		
Dec 2004	Performance of	Accepted Paper: Cold	Chasar	Energy Efficiency
(pending)	Exterior Envelopes of	Climate Case Study of		Industry
	Whole Buildings IX,	North Dakota Twin		
	Clearwater (FL)	Homes for Performance		
		of Exterior Envelopes		
Dec 2004	Performance of	Accepted Paper:	Moyer	Energy Efficiency
(pending)	Exterior Envelopes of	Residential Ventilation		Industry
	Whole Buildings IX,	Techniques		
	Clearwater (FL)			
Aug 2004	ACEEE Summer	Accepted Paper: Six	Moyer	Energy Efficiency
(pending)	Study, Pacific Grove	Residential Ventilation		Industry
	(CA)	Techniques in Hot and		
		Humid Climates		
Aug 2004	ACEEE Summer	Accepted Paper:	Chasar	Energy Efficiency
(pending)	Study, Pacific Grove	Energy Star		Industry
	(CA)	Manufactured Homes:		
		The Plant Certification		
		Process		
July 2004	American Solar Energy	Invited Paper:	Lubliner,	Solar Energy
(pending)	Society Conference	Introducing Solar	Hadley,	Industry
		Ready Manufactured	and Gordon	
	444.0	Housing		D 00' ;
Apr 2004	14th Symposium on	Presented Referred	McGinley	Energy Efficiency
(pending)	Improving Building	Paper: Optimizing		Industry
	Systems in Hot and	Manufactured Housing		
	Humid Climates.	Energy Use	G1 1	D 00' '
Apr 2004	14th Symposium on	Presented Referred	Chandra	Energy Efficiency
(pending)	Improving Building	Paper: An Overview of		Industry
	Systems in Hot and	Experimental Research		
	Humid Climates.	on Houses by the		
		Building America		
		Industrialized Housing		
. 2004	144.0	Partnership	M 11 .	E ECC :
Apr 2004	14th Symposium on	Presented Referred	McIlvaine	Energy Efficiency
(pending)	Improving Building	Paper: Air Duct		Industry
	Systems in Hot and	Tightness in		
4 2004	Humid Climates.	Manufactured Housing	M 11 .	HEILO 4.
Apr 2004	HFH National	Presentation, 1.5 hours:	McIlvaine	HFH Construction
(pending)	Leadership Conference	Advanced Building		Managers and
		Science and Moisture		Leaders
		Control		

Table 55 Training and Presentations by BAIHP Staff January 2002 – December 2004					
Month	Venue	Description	Researcher	Audience/Attendees	
Mar 2004	IBACOS/FSEC	FSEC co-hosted 1-day	Chasar,	BA Researchers	
(pending)	Monitoring Workshop	workshop session with	Kalaghchy		
	Meeting	IBACOS. Presentations	(FSEC		
		by researchers from	Computer		
		NREL, Davis Energy	Resources		
		Group, IBACOS and	Manager),		
		FSEC as well as reps	BAIHP Staff		
		from Campbell			
		(dataloggers) and Data			
		Taker.			
Mar 2004	GreenPrints	Presentation:	Vieira	Builders, Energy	
	Conference, Atlanta	Techniques You Should		Efficiency Industry	
		Incorporate In Your		~75 attendees	
		New Home or How to			
		Star in the High			
Mar 2004	hailen ana	Hurdles,	Chandra	Davildana	
Mai 2004	www.baihp.org	Posted Standards for Clean Air	Chandra	Builders, Manufacturers,	
		Florida Homes		Building Scientists,	
		riorida fromes		Public	
Feb 2004	Central Atlantic Coast	Presentation, 2 hours:	McIlvaine	~100 HFH	
100 2004	HFH Conference	Advanced Building	Wichivallic	Construction	
		Science and Moisture		Managers/Staff	
		Control		11141149615/24411	
Feb 2004	www.baihp.org	Posted	McIlvaine	Builders,	
	1 0	Achieving Airtight		Manufacturers,	
		Ducts in Manufactured		Building Scientists,	
		Housing		Public	
Feb 2004	www.baihp.org	Posted	Moyer	Builders,	
		Alleviating Moisture		Manufacturers,	
		Problems Hot, Humid		Building Scientists,	
		Climate Housing		Public	
Feb 2004	www.baihp.org	Posted Case Study:	Martin	Builders,	
		WCI Communities at		Manufacturers,	
		Evergrene		Building Scientists,	
				Public	
Feb 2004	FSEC, Cocoa (FL)	Workshop, 3 day	Moyer	Energy Raters	
		course: Class 1 Florida			
		Home Energy Rater			
		Training. Included			
		Certification exam			

Table	e 55 Training and Prese	entations by BAIHP Staff	<b>January 2002</b> –	December 2004
Month Jan 2004	Venue USDOE Expert Meeting, Anaheim (CA)	Description Expert meeting codeveloped with ASHRAE: Residential HVAC Fans and Systems	Researcher	Audience/Attendees Building Scientists
Jan 2004	Southeastern Habitat for Humanity Conference, Jekyll Island (GA)	Short Course: Advanced Building Science and Moisture Control	McIlvaine	~60 HFH Construction Managers/Staff
Jan 2004	International Builders' Show/NAHB Conference, Las Vegas	Represented BAIHP at DOE booth	Chandra	Builders
Dec 2003	FSEC, Cocoa (FL)	Workshop, 1 day course: Green Home Certifying Agents for Florida Green Building Coalition	Martin	Green Home Certifying Agents, Candidates
Nov 2003	GreenBuild Conference and Expo, Pittsburgh (PA)	Presented Paper: Complying with Florida's Green Land Development Standard: Case Studies and Lessons Learned		Builders, Public, Building Scientists and Related Specialists
Nov 2003	www.baihp.org	Revised Partner contact i maps for each region	information and	Builders, Manufacturers, Building Scientists, Public
Oct 2003	Workshop with	Workshop, 2 day,	Chandra and	14 Builders and
Oct 2003	ALACF, Orlando AIVC Conference, Washington	Building Health Houses Presented Referred Paper: Building Envelope, Duct Leakage and HVAC System Performance in HUD-Code Manufactured Homes	Hutchinson Lubliner	Suppliers Building Scientists
Oct 2003	FSEC, Cocoa (FL)	BAIHP staff hosted a ful for 4 person team from In codes and standards, tool voluntary green building Florida regulatory and voluilding programs	ndia. Topics: ls, training, programs,	4 person team from India

Table	e 55 Training and Prese	entations by BAIHP Staff	<b>January 2002 –</b>	December 2004
Month Sept 2003	Venue Florida Housing Coalition Conference, Miami	Description Presentation: BAIHP benefits and applicability to affordable housing	Researcher	Audience/Attendees ~25 Affordable Housing Providers
Sept 2003	Sierra Club, Melbourne (FL)	Green Buildings	Martin	Environmental ~30 attendees
Sept 2003	www.baihp.org	Created Infomonitors dat Energy Manufactured Ho www.infomonitors.com/	ome	Building Scientists
		Created Infomonitors dat Energy Habitat House (w http://www.infomonitors	vith ORNL)	
Aug 2003	FSEC, Cocoa (FL)	Workshop, ½ day course: Why the Ceiling Fell In	Moyer	Public, Construction Industry
Aug 2003	FSEC, Cocoa (FL)	Workshop, 1 day course: Diagnosing Moisture Problems	Moyer	Public, Construction Industry
Aug 2003	FSEC, Cocoa (FL)	Workshop, 3 day course: Class 1 Florida Home Energy Rater Training includes certification exam	Moyer	Energy Raters
Aug 2003	FSEC, Cocoa (FL)	Workshop, 1 day: Green Home Certifying Agents for the Florida	Martin	9 Attendees seeking certification
Aug 2003	www.baihp.org	MHLab Ventilation Study	Moyer	Builders, Manufacturers, Building Scientists, Public
July 2003	Southeast Builders Show, Orlando (FL)	Short Course, 3 Hour: Health House Builder Guidelines	Chandra, Hutchinson, Tim Kensok (Honeywell)	100+ attendees, 90 builders attended all or part of course. 19 builders indicated desire to be certified Health House Builders
July 2003	www.baihp.org	Brookside Apartment testing	Chandra	Builders, Manufacturers, Building Scientists, Public

Table	e 55 Training and Prese	entations by BAIHP Staff	January 2002 –	December 2004
Month July 2003	Venue www.baihp.org	<b>Description</b> Palm Harbor Energy Star Plan certification	Researcher Chasar	Audience/Attendees Builders, Manufacturers, Building Scientists, Public
July 2003	Florida Local Environmental Resource Agencies Conference, Jupiter Beach (FL)	Green-home elements and Florida standards; How local governments can foster green building within their community.	Martin	Local Government Staff ~15 attendees
July 2003	World Resources Institute Bell Conference, Ft. Lauderdale (FL)	Panel Session: The Business of Green Construction	Martin	Business, local government, state regulatory agencies ~20 attendees
June 2003	Recycle Florida Today Conference, St. Petersburg Beach (FL)	Presentation, 30 minutes: Green-home elements and Florida standards	Martin	~35 attendees, government (local and state), solid waste management /recycling industry
June 2003	U.S Spain Construction Forum, Miami (FL)	Presentation: Florida Green Building Coalition	Martin	~20 attendees
June 2003	ASHRAE Summer Meeting, Kansas City (KS)	Presentation: Duct Leakage in New Washington State Residences: Findings and Conclusions	Lubliner	Energy Efficiency Industry
May 2003	Energy Efficiency + Solar Energy = Zero Energy Homes, Orlando (FL)	Presentation: Florida Green Home Designation; Panel included 3 BAIHP builder partners	Martin	~30 attendees eligible for 2 CEUs
May 2003	www.baihp.org	Posted Case Study: Show Me the Money: Selling Builders on Systems Engineering.	Fonorow	Builders, Manufacturers, Building Scientists, Public
May 2003	www.baihp.org	Posted Technical Services Provided to the HUD Code and Modular Industry	Chandra	Builders, Manufacturers, Building Scientists, Public

Table	e 55 Training and Prese	ntations by BA	AIHP Staff	January 2002 –	December	2004
Month	Venue	<b>Description</b>	~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~	Researcher		e/Attendees
April 2003	2003 MHI Conference,	Presentations:	Use of	Chandra,		artners and
11p111 2003	Las Vegas (NV)	innovative cro		Mullens	_	e attendees
	Las vegas (111)	duct system; I		TVTGITCHS	Compreh	e attendees
		mastic riser sy				
		Exhibit: BAIH				
April 2003	Puyallup Manufactured	Exhibit: Tech		Lubliner	Ganaral r	oublic, MH
April 2003	Home Show, Puyallup,	marketing ass		Luoinici	dealers, h	
	(WA)	worked with u			manufact	
	(WA)	representative	•		other indi	
		-				-
		promote incer	itives		represent	alives
	Continuing Educati	•		•		<b>"</b> "
Dates	Name of Course	Location	CEU-hrs	Instructor	Hours	#Students
Mar 2003	ALA Health House	Lake Mary	0	Chandra	4	15
Mar 2003	ALA Pulmonary	Lake Mary	4	Chandra	1	51
Mar 2003	FGBC Certification	FSEC	6	Martin	6	16
Feb 2003	ALA pulmonary	Leesburg	4	Chandra	1	33
Nov 2002	Rater Recertification	FSEC	0	Moyer	8	23
Sept 2002	Rater Recertification	FSEC	0	Moyer	8	8
Aug 2002	Energy Gauge - Class	FSEC	0	Moyer	11	24
8	1		-			
Aug 2002	Energy Gauge - Class	FSEC	0	Moyer/ Chasar	8	12
	2	Para	0	3.6	0	1.6
Aug 2002	Energy Gauge	FSEC	0	Moyer	8	16
	Recertification			~		
Aug 2002	Mold presentation	Orlando/	0	Chandra,	0.5	25
	BAIHP and Unvented	HBA		Chandra,		
	attics	Orlando/M		Fonorow, Hoak	2.5	50
T 1 2002	D . D	CBC	0	3.6		0
July 2002	Rater Recertification	FSEC	0	Moyer	4	9
June 2002	Energy Gauge Rater	FSEC	48	Chasar	8	7
	Training	DOD G	40			,
June 2002	Energy Gauge Rater	FSEC	48	Moyer	24	4
	Training	_			_	
June 2002	Weatherization	Tampa	0	Moyer	2	25
	Presentation		_			
June 2002	Rater Refresher	FSEC	0	Moyer	8	8
May 2002	Rater Recertification	FSEC	0	Moyer	3	8
May 2002	Rater Recertification	FSEC	0	Moyer	3	16
Apr 2002	Energy Gauge Rater	FSEC	48	Moyer	24	14
Apr 2002	Training Rater Refresher	FSEC	0	Mover	8	7
Apr 2002 Apr 2002	Rater Recertification	FSEC	0	Moyer Moyer	3	3
Apr 2002 Mar 2002		UCF	4	Chandra		5 65
wiai 2002	ALACF Pulmonary	UCF	4	Cilaliula	1	US

Care

Table 55 Training and Presentations by BAIHP Staff January 2002 – December 2004

Month	Venue	Description		Researcher	Audience/	Attendees
Mar 2002	Rater Refresher	FSEC	0	Moyer	8	6
Mar 2002	Rater Recertification	FSEC		Moyer	3	6
Mar 2002	Fl Green Home	FSEC	6	Martin	6	7
Feb 2002	Rater Recertification	FSEC	0	Moyer	3	5
Feb 2002	Energy Gauge Rater Training	FSEC	48	Moyer	24	10
Jan 2002	Rater Recertification	FSEC	0	Moyer	3	5
Jan 2002	Rater Recertification	FSEC	0	Moyer	3	8
Total Befor	re Jan 2002 – Mar 2003	8 Classes	58		51	112

#### BAIHP Training Events by Audience

BAIHP has presented research findings and Building America concepts to a variety of audiences including architects, builders, HUD Code home manufacturers, and housing decision makers; construction trades and realtors; attendees at building science conferences; portable classroom producers and decision makers; energy raters and green home certifiers, and college students in academic venues.

Audience: Architects Prior to 5th Budget Period

*North Florida AIA Chapter:* Introduced the Building America program, Florida Green Building Standards, and related issues during a presentation at a monthly meeting. 23 registered architects attended.

Evans Group: In 2002, researchers gave a presentation to the Evans Group in their Orlando office. Presentation and discussion issues included: mechanical system right-sizing, dehumidification strategies, mechanical system sensible heat ratios, importance of and methods to provide outside air and associated pressurization issues, and the impact of spectrally selective low-E windows on equipment sizing and occupant comfort. This presentation led to BA involvement in the 2003 SEBC Southern Showplace Home.

Audience: Builders, HUD Code Home Manufacturers, and Housing Decision Makers during 5th Budget Period

*American Lung Association:* Presented by BAIHP and ALACF Building Health Houses, 2-day course for 14 builders.

Florida Housing Coalition Conference: BAIHP staff presented benefits and applicability of Building America concepts to affordable housing in September of 2003 to approximately 25 affordable housing providers.

*Green Building Seminars:* BAIHP staff presented green building concepts including the Florida Green Home Standard at:

- Energy Efficiency + Solar Energy = Zero Energy Homes in Orlando, May 2003
- Recycle Florida Today Conference in St Petersburg Beach (FL), June 2003
- U.S.-Spain Construction Form in Miami, June 2003

- Florida Local Environmental Resource Agencies Conference in Jupiter Beach (FL), July 2003
- Sierra Club members in Melbourne (FL), September 2003

Habitat for Humanity Construction Managers: FSEC presented an advanced building science course for construction managers at two HFH conferences with one presentation planned for April:

- 2004 Southeastern Habitat Conference (GA): 4 hour session, ~60 attendees January
- 2004 Central Atlantic Conference (NC); 2 hour session, ~100 attendees February
- 2004 National Leadership Conference (TX): 1.5 hour session pending, April

Most participants had attended a basic building science course taught by FSEC or HFHI's Green Team at a previous conference. Discussion sprang from case studies and covered moisture detailing, air flow and pressure dynamics, return air pathways, reaching beyond Energy Star, new water heating options, and foundation detailing. An enthusiastic crowd with informed questions showed a tremendous increase in building science awareness among Habitat construction managers compared to the attendees in the early days Building America's involvement with Habitat

A two-hour version of the course was presented at the Central Atlantic Conference to approximately 100 attendees with similar response. FSEC has been asked to present the material again at the National HFH Leadership Conference in April and the Central States HFH Conference in October 2004.

Habitat for Humanity Construction Volunteers: FSEC spearheaded energy efficiency training at the 2003 Jimmy Carter Work Project sites in Anniston (AL) and LaGrange (GA) (Figure 91). FSEC worked with volunteer Energy Monitors at both sites prior to the blitz build to train project staff and supervisory volunteers regarding the elements of the energy packages and to assist with material and equipment specs and procurement. During the initial orientation sessions, volunteers got an overview of the energy features of the houses. During the week-long blitz build, FSEC and HFHI staff held training sessions each morning to discuss and demonstrate the energy details of the day.



(Figure 91) Volunteers follow energy efficiency guidelines for building Energy Star houses during Habitat for Humanity 2003 Jimmy Carter Work Project

Volunteers learned and practiced how to seal the whole house air barrier and interior air handler/furnace closets, install insulation, install exterior rigid insulation, and install flashing around windows and doors. Since the weather was rainy all week, volunteers, homeowners, and

project managers were concerned with moisture issues which led to moisture discussions regarding vapor diffusion, material drying dynamics, and moisture flow in assemblies. Approximately 500 volunteers in LaGrange (22 Energy Team Volunteers) and 800 volunteers in Anniston (~35 Energy Team Volunteers) received a hands-on education in energy efficiency, indoor air quality, moisture details, and (in Anniston) combustion safety. An Alabama environmental group installed radon mitigation systems in all 35 Anniston homes.

Volunteers participated in testing the homes they had built in LaGrange. In the end, the volunteers built 22 Energy Star Homes in LaGrange and 35 near Energy Star homes in Anniston. Due to a lapse in communication, the air conditioners procured for the Anniston site were SEER 10 instead of SEER 12, narrowly missing the Energy Star mark for all 35 homes.

*Health House Workshop (Orlando):* In July 2003 FSEC researchers conducted a Health House builder workshop with the American Lung Association of Central Florida (ALACF) at the Southeast Builders Show. Approximately 90 builders attended. The team conducted a 3 hour short course on the Health House Standard in October 2003, with 14 builders and suppliers attending.

*International Builders' Show:* BAIHP staff assisted at the BA booth, speaking with potential Partners and interested parties.

2003 MHI Conference (Las Vegas, NV): BAIHP presented Use of an Innovative Crossover Duct System and Duct Mastic Riser System and helped staff the Building America Booth.

Moisture Issues Seminars: BAIHP staff presented a 1 day course titled Diagnosing Moisture Problems and a ½ day course Why the Ceiling Fell In at FSEC in August 2003.

Puyallup Manufactured Home Show (WA): BAIHP staff provided technical and marketing assistance and worked with utility representatives to promote energy efficiency incentives.

2003 Southeast Builders Show (Orlando, FL): 3 hour short course: Health House Builder Guidelines, 100+ attendees with 90 builders attending part of or the entire course. 19 builders indicated desire to be certified Health House Builders.

Audience: Builders, HUD Code Home Manufacturers, and Housing Decision Makers during prior to 5th Budget Period

*Home Builders:* Courtland Homes, Habitat for Humanity, Ashton Woods, Engle Homes, Beazer Homes, and Golden Heritage Homes.

Habitat for Humanity Workshops: From April 2001 to March 2003, BAIHP conducted: (1) a one-hour session on Energy Code changes and energy efficiency concepts for Florida Habitat for Humanity construction managers at the Spring Construction Round Table, (2) training for City of Lubbock personnel, city builders and Habitat personnel, (3) mechanical contractor and duct installer training for Calhoun County Alabama affiliate, and (4) HFHI workshop for 60 Ohio affiliates on the home energy rating process, the house as a system concept, best improvements for Ohio affiliates and house pressure and combustion safety.

Duct Systems Workshop: In 2000, workshops in Oregon and Washington focused on improved duct installation and inspection oversight, particularly on the use of mastic as a sealing strategy for ductwork joists. Manufacturers Palm Harbor Homes, Fleetwood Homes (Washington and Oregon) and Valley Manufactured Housing participated. In 2001, these same manufacturers participated along with Fuqua Homes, Marlette, and all of the Idaho manufacturers. In 2002, BAIHP staff continued to provide these workshops, working in partnership with BAIHP partner Flexible Technologies to demonstrate the added value of their innovative duct sealing technologies

Energy Seminar: In 2002, BAIHP participated in an energy seminar held in Gainesville, FL., entitled "Responsible Buying, Building, or Retrofitting for Higher Energy Efficiency and Comfort in Homes." 80 - 100 people attended the seminar.

*Fenestration Short Course:* Researchers presented a half-day short course to about 25 attendees on windows at the Fenestration Manufacturers of Florida meeting in Ft. Lauderdale. The session was completed in approximately three hours, followed by about a half hour discussion. A broader presentation has been planned to include the entire United States.

Fleetwood Homes: Researchers made a presentation to Fleetwood corporate representatives on BAIHP research efforts - concentrating on Energy Star and the use of a crossover duct system with a flex flow elbow.

*Health House Workshops:* In 2002, FSEC researchers conducted a Health House builder workshop for the American Lung Association of Central Florida (ALACF). This workshop helped the National Health House group determine the best format for presenting National Health House guidelines to builders.

MHRA Energy Star Committee: Assisted MHRA on a request for on Quality Assurance procedures for Energy Star manufactured homes in a joint effort with the US EPA.

Mid Florida Builders Association: BAIHP held a seminar in August 2002 in Maitland (FL) on building healthy, energy efficient homes in central Florida. More than 60 builders attended the program and many were still asking questions more than two hours after the seminar formally ended. Researchers also provided a building science seminar for Shea Active Adult sales and construction personnel and for the general public.

Audience: Trades and Realtors

In 2002, BAIHP provided training for Trane Air Conditioning Company and developed a certified New Home Professional Realtor Course attended by 22 real estate professionals

Audience: Papers and Presentations at Building Science Conferences in 5th Budget Period Conference Name (number of papers accepted/presented, date)

- Performance of Exterior Envelopes of Whole Buildings IX (3, pending December 2004)
- American Council on an Energy Efficient Economy (ACE3) Summer Study (2, pending August 2004)
- American Solar Energy Society (ASES) Conference (1, pending July 2004)
- 14th Symposium on Improving Building Systems in Hot and Humid Climates (3, pending April 2004)

- GreenPrints Conference (1, March 2004)
- US DOE Expert Meeting, Residential HVAC Fans and Systems, Co produced with ASHRAE at Winter Meeting in Anaheim.
- GreenBuild Conference and Expo (1, November 2003)
- Air Infiltration and Ventilation Centre (AIVC) Conference (1, October 2003)
- American Society of Heating, Refrigeration, and Air Conditioning Engineers (ASHRAE)
   Summer Meeting (1, June 2003)

Audience: Papers and Presentations at Building Science Conferences prior to 5th Budget Period

- 2002 American Council on an Energy Efficient Economy (ACE3) Summer Study: four papers presented:
- Pushing the Envelope: A Case Study of Building the First Manufactured Home Using Structural Insulated Panels
- Washington State Residential Ventilation and Indoor Air Quality Code (VIAQ) Whole House Ventilation Systems Field Research Report
- Measured and Simulated Cooling Performance Comparison: Insulated Concrete Form Versus Frame Construction.
- Do Energy Star Homes Live Up to Their Promoted Energy Savings? A Comparison of Utility Bill Data for Recently Built Energy Star and Control Homes in Alachua County, Florida, and co-presented a paper on Structural Insulated Panels with PNNL.
- 1st Annual USGBC International Green Building Conference and Exposition, Austin
- Energy and Environmental Integration Through a Green Municipality Designation" Florida Annual Pollution Prevention Conference in Miami Beach, presenting details of the sustainable design approach planned for the Miami-Dade HOPE VI Project
- Manufactured Housing Institute Convention on healthy homes and cool roofs
- National Institute of Standards and Technologies (NIST) Annual Meeting in Gaithersburg, Maryland, presenting a program on manufactured home testing to HUD, DOE, and EPA staff
- ASHRAE Summer Meeting on uncontrolled air flow in small commercial buildings
- Quality Modular Building Task Force in Charlottesville, Virginia summarizing 2002
  research results for members including modular industry energy benchmark study results, a
  proposed plan for adding quality metrics to employee incentive programs, and
  advancements in lean manufacturing in the modular industry
- Central Florida Simulation Users Group Conference in Orlando, FL. on the role of simulation in a homebuilding productivity suite
- Southwest Chapter of the Washington Association of Maintenance Operations Administrators Conference on the results, findings, and recommendations of the portable classroom study
- Washington State Manufactured Housing Coordination Conference with the Washington Departments of Labor and Industries, Licensing, Community Development and Office of Manufactured Housing, The Attorney General's Office, and the Washington Manufactured Housing Association, presenting results of the BAIHP/Energy Star for manufactured housing efforts.
- EEBA Conference in Phoenix (3 presentations)
- 2002 ACEEE Summer Study on Energy Efficiency in Buildings Conference on Comparative Evaluation of the Impact of Roofing Systems on Residential Cooling Energy Demand in Florida
- 13th Symposium on Improving Building Systems in Hot and Humid Climates in Houston

(TX)

- Measured Cooling Performance of Two-story Homes in Dallas, Texas: Insulated Concrete Form Versus Frame Construction
- Performance and Impact from Duct Repair and Ventilation Modifications of Two Newly Constructed Manufactured Houses Located in a Hot and Humid Climate
- The Building America Industrialized Housing Partnership (BAIHP)
- Mid West Energy Alliance meeting in Chicago
- 2nd Annual Interagency Conference on Tribal Affairs in Orlando, Florida on Building America, building science, and energy efficiency concepts for Native America housing providers HUD, PATH, and Pennsylvania State University
- DOE's 25th Annual Weatherization Conference on Interior Duct Study
- Affordable Comfort Conference Buildings that Last in a Hot-Humid climate
- Weatherization Conference, Tampa.
- Daylighting Class: In 2001, staff taught a two-hour class in Orlando on daylighting calculations, as part of a continuing education series sponsored by the Central Florida Chapter of the Illuminating Engineering Society of North America.

### Conference and Training Attendance prior to 5<sup>th</sup> Budget Period Year 4 (April 2002 to March 2003)

- NAHB International Builders Show in Las Vegas, NV.
- Southeastern Regional Habitat for Humanity Conference, exhibiting and providing information on Florida's new Energy Code, building science, energy efficiency details for hot-humid climates, and the Building America program during educational sessions
- Idaho Energy Conference (IEEC 2002 commercial code training)
- RESNET Conference in San Diego, CA.
- Basement, Crawlspace, Slab Insulation & Moisture Control Seminar in Westford, MS. (a Building Science Corporation expert meeting)
- Salem Home Show in Salem, WA.
- Westford Building Science Seminar
- ACCA Manual J Training Class
- Zero Energy Manufactured House dedication ceremony in Nez Perce tribal fish facility near Lewiston.
- The Health Home Media Tour in Orlando, FL. (covered by local television stations, Channels 2 and 35, and an AM radio station).

#### *Year 3 (April 2001 to March 2002)*

- Design charette organized by Steven Winter Associates and McStain Enterprises in Boulder, CO.
- National Association of Home Builders Conference in Atlanta, GA.
- 16th Annual National Low-Income Energy Conference in Ft. Lauderdale, FL., introducing Building America and building science principals
- Building VIII Conference in Clearwater Beach, FL.
- NCA&TSU manufactured housing advisory committee meeting in Raleigh (NC)
- Zero Energy Buildings workshop in Orlando, FL.
- Mold seminar put together by the Mid-Florida Home Builder Association
- Seminar on WUFI, a moisture analysis software developed by ORNL
- Council of State Administrative Agencies' Spring Workshop in San Antonio, TX, representing BAIHP and sharing Building America research.

#### Tours

In 2002, BAIHP conducted a tour of the National Institute of Standards and Technologies (NIST) facilities in Gaithersburg, Maryland to HUD, DOE, and EPA staff. BAIHP also led a Beaverton Classroom tour for DOE, WSU, and PNNL staff.

Audience: Energy Raters and Green Home Certifiers in 5th Budget Period: Class I Florida Home Energy Rater Training and Certification: BAIHP staff worked with the Florida Energy Gauge Office to provide training to energy raters seeking Class I certification in August 2003 and February 2004. The 3 day course ended with the certification exam.

Green Home Certifying Agents for Florida Green Building Coalition: BAIHP staff worked with the FGBC to provide training to those seeking to become Green Home Certification Agents in August and December (2003). The 1 day course ended with the certification exam.

Audience: Energy Raters and Green Home Certifiers prior to 5th Budget Period: Pulmonary Symposium: In 2003, researchers conducted two one-hour pulmonary symposiums in Lake Mary, Florida for 86 health professionals. Symposium topics covered building science and lung health components.

Audience: Portable Classroom Producers and Decision Makers Prior to 5th budget period Energy Optimization for Universities and School Districts Workshop (Seattle, WA.): In 2002, BAIHP presented findings and recommendations of the three-year Pacific Northwest Portable Classroom Study. Facility managers from across the state attended the workshop.

Portable Classroom Presentations/Training: In 2001, BAIHP staff conducted four installer certification training sessions in WA, involving more than 200 onsite setup crew personnel. During 2002, 100 set-up crew personnel received the training and certification.

Smart Portable Classroom Collaborative Workshop (Portland, OR): In 2000, BAIHP staff hosted this workshop which was the first opportunity for national experts in portable classroom design, construction, siting, and end-use to come together and discuss energy-related issues. Outreach to other school districts included numerous meetings like the Oregon School Facilities Managers' annual meeting, and the Oregon Association of School Business Officials annual meeting.

Academic Venues prior to 5<sup>th</sup> Budget Period Arizona State University: Del E. Webb School of Construction and Scottsdale Community College.

*University of Florida:* Director of School of Building Construction and Environment, 22 post-graduate students at the Cobblefield subdivision on techniques and methodologies incorporated at this "Green" subdivision.

#### BAIHP Publications List – All Budget Periods (09/99-03/04)

Papers

- Arif, M., Mullens, M., Espinal, D., & Broadway, R. (2002). "Estimating, Planning and Controlling Labor in the Industrialized Housing Factory." Industrial Engineering Research '02 Conference Proceedings, Orlando, FL.
- Armacost, R., J. Pet-Armacost,, M. Mullens, and A. Salem (2001). "Information Support for Efficient Assembly of Roof Trusses," in Khattab, M. (ed.), Proceedings of the International Conference on Information Systems in Engineering and Construction (ISEC 2001), Cocoa Beach, FL, 2001, CD-ROM.
- Armacost, R., J. Pet-Armacost, M. Mullens, and A. Salem (2001). "Scheduling for Roof Truss Manufacturing," in Harris, R. (ed.), Proceedings of the ICC&IE and IEMS 2001 Joint Meeting, Cocoa Beach, FL 2001, pp. 644-649.
- Baechler, M.; Lubliner, M; Gordon, A (2002). "Pushing the Envelope: A Case Study of Building the First Manufactured Home Using Structural Insulated Panels" 2002 ACEEE Summer Study on Energy Efficiency in Buildings Conference, Pacific Grove, CA.
- Chasar, D., Moyer, N., Rudd, A. F., Parker, D., & Chandra, S. (2002). "Measured Cooling Performance of Two-story Homes in Dallas, Texas: Insulated Concrete Form Versus Frame Construction." Thirteenth Symposium of Improving Building Systems in Hot and Humid Climates, Houston, TX.
- Chasar, D., Moyer, D., Rudd, A. F., Parker, D. K., & Chandra, S. (2002). "Measured and Simulated Cooling Performance Comparison; Insulated Concrete Form Versus Frame Construction." 2002 ACEEE Summer Study on Energy Efficiency in Buildings, Pacific Grove, CA.
- Chandra, Subrato, Danny Parker, David Beal, David Chasar, Eric Martin, Janet McIlvaine, Neil Moyer (2004). Alleviating Moisture Problems in Hot, Humid Climate Housing. Position Paper for NSF Housing Research Agenda Workshop, UCF Feb. 12-14, 2004.
- Chandra, Subrato, Fonorow, Ken, McCloud, Matthew, Moyer, Neil, Beal, David, Chasar, David, McIlvaine, Janet, Parker, Danny, Sherwin, John, Martin, Eric, Mullens, Michael, Lubliner, Michael, McSorley, Michael (2002). "The Building America Industrialized Housing Partnership" Symposium on Improving Building Systems in Hot, Humid Climates Houston, Texas, May 20-22, 2002.
- Chandra, S., & Beal, D. (2001). "Preventing House Dust Mite Allergens in New Housing.' In ASHRAE IAQ Conference Proceedings, San Francisco, CA.
- Chandra, S., Moyer, N., Beal, D., Chasar, D., McIlvaine, J., & Withers, C. (2001). "The Building America Industrialized Housing Partnership (BAIHP): Enhancing Energy Efficiency, Durability and Indoor Air Quality of Industrialized Housing." In XXIX IAHS World Congress on Housing Conference Proceedings, Ljubljana.
- Cummings, J., C.Withers, J. McIlvaine, J. Sonne, M. Lombardi (2003). Air Handler Leakage: Field Testing Results in Residences. ASHRAE Transactions V.109 pt.1 February 2003. To be published in ASHRAE Journal.
- Elshennawy, A., Mullens, M., & Nahmens, I. (2002). "Quality Improvement in the Modular Housing Industry." In Industrial Engineering Research '02 Conference Proceedings, Orlando, FL.
- Fuehrlein, B., Chandra, S., Beal, D., Parker, D.K., & Vieira, R. (2000). "Evaluation of EnergyGauge® USA, a Residential Energy Design Software Against Monitored Data." In ACEEE Summer Study Proceedings, Pacific Grove, CA.
- Hales, D; M. Lubliner, A. Gordon (2003). "Duct Leakage in New Washington State Residences: Findings and Conclusions" Proceedings of the 2003 ASHRAE Summer Meeting.

- Hodgson, A.T., Apte, M.G., Shendell, D.G., Beal, D. and McIlvaine, J.E.R. (2002). Implementation of VOC source reduction practices in a manufactured house and in school classrooms. In Levin, H. (Ed.), Proceedings of the 9th International Conference on Indoor Air Quality and Climate. Indoor Air 2002, Santa Cruz, CA, Vol. 3. pp. 576-581.
- Hodgson, A.T., D. Beal and J.E.R. McIlvaine. 2002. Sources of formaldehyde, other aldehydes and terpenes in a new manufactured house. *Indoor Air* **12**: 235-242.
- Hodgson, A.T., A.F. Rudd, D. Beal and S. Chandra. 2000. Volatile organic compound concentrations and emission rates in new manufactured and site-built houses. *Indoor Air* **10**: 178-192.
- Lubliner, M, Nelson, M, & Parker, D. (2003). "Gossamer Wind Solar Power Ceiling Fan." In 2003 ASES Conference Proceedings, Austin, TX.
- Lubliner, M, Kunkle, R, Devine, J, & Gordon, A. (2002). "Washington State Residential Ventilation and Indoor Air Quality Code (VIAQ) Whole House Ventilation Systems Field Research Report." 2002 ACEEE Summer Study on Energy Efficiency in Buildings Conference, Pacific Grove, CA.
- Lubliner, M.; Gordon, A.; Persily, A.; Moyer, N.; Richins, W.; Blakeley, J (2003). "Building Envelope, Duct Leakage and HVAC System Performance in HUD-Code Manufactured Homes" 23<sup>rd</sup> Annual AIVC Conference Proceedings.
- Lubliner, M., & Gordon, A. (2000). "Ventilation in US Manufactured Homes: Requirements, Issues and Recommendations." 21st Annual AIVC Conference Proceedings, The Hague.
- McCluney, R. (2003). "Methodologies for Determining the SHGC of Complex Fenestration Systems." Paper presented at the 2003 National Fenestration Rating Council Meeting, Houston, TX.
- Mullens, Michael A. and Mark E. Kelley III. 2004. "Lean Homebuilding Using Modular Technology." Housing and Society. January 31, 2004 pp.41-54.
- Mullens, M. and M. Hastak (2004). "Defining a National Housing Research Agenda: Construction Management and Production" Proceedings of the NSF Housing Research Agenda Workshop, Feb. 12-14, 2004, Orlando, FL. Eds. Syal, M., Mullens, M. and Hastak, M. Vol 2.
- Mullens, M. (2004). "Production flow and shop floor control: Structuring the modular factory for custom homebuilding" Proceedings of the NSF Housing Research Agenda Workshop, Feb. 12-14, 2004, Orlando, FL. Eds. Syal, M., Mullens, M. and Hastak, M. Vol 2.
- Mullens, M., & Kelley, M. (2003, January). "Lean Homebuilding Using Modular Technology." NAHB International Builders Show Conference Proceedings, Las Vegas, NV.
- Mullens, M., & Kelley, M. (2002). "Introducing Revolutionary Change in the Modular Housing Construction Process Using a Kaizen Blitz." In Industrial Engineering Research '02 Conference Proceedings, Orlando, FL.
- Moyer, N., Beal, D., Chasar, D., McIlvaine, J., Withers, C, & Chandra, S. (2001). "Moisture Problems in Manufactured Housing: Probable Causes and Cures." ASHRAE IAQ 2001 Conference Proceedings, San Francisco, CA.
- Nasereddin, M., Mullens, M., & Cope, D. (2002). "The Development of a Reusable Simulation Model for the Modular Housing Industry Using Promodel and Visual Basic." In Industrial Engineering Research '02 Conference Proceedings, Orlando, FL.
- Withers, C., Moyer, N., Chasar, D., & Chandra, S. (2001). "Performance and Impact from Duct Repair and Ventilation Modifications of Two Newly Constructed Manufactured Houses Located in a Hot and Humid Climate." Paper presented at the 13th Symposium on Improving Building Systems in Hot and Humid Climates, Houston, TX.

- Contract Reports
- Cummings, J., Withers, C., Gu, L., McIlvane, J., Sonne, J. K., & Lombardi, M. (2002). "Field Testing and Computer Modeling to Characterize the Energy Impacts of Air Handler Leakage." Florida Solar Energy Center Contract Report # FSEC-CR-1357-02, Cocoa, FL.
- Florida Solar Energy Center, & York Unitary Products Group. (2000). "The Coleman® Pressure Control System: A Comprehensive and Proactive Process to Eliminating Pressure Driven Moisture Damage in Manufactured Housing." Florida Solar Energy Center Contract Report, Cocoa, FL.
- Hodgson, A.T., N. Moyer and D. Beal (2005). "Effect of residential ventilation techniques for hot and humid climates on indoor concentrations and emission rates of volatile organic compounds." February 2005, LBNL-57030, Lawrence Berkeley National Laboratory, Berkeley, CA.
- McCluney, R., L. Mills (2003). The Benefits of Using Window Shades "Florida Solar Energy Center Nov. 01, 2003.
- McCluney, R., N. Dhere (2002). "Industry Guide to Selecting the Best Residential Window Options for the Florida Climate" Florida Solar Energy Center, Pf-358-00, Dec. 01, 2002.
- McGinley, M. (2002). "Study of Innovative Manufactured Housing Envelope Materials." BAIHP Subcontract Report, Greensboro, NC.
- McIlvaine, Janet, David Beal, Philip Fairey (2001). Design and Construction of Interior Duct Systems. FSEC PF-365-01. Florida Solar Energy Center. Cocoa, Florida, May 2001.
- Mullens, M., & Burdick, J. (2003). "Energy Test Results and Recommendations for Avis America Homes." University of Central Florida Housing Constructability Lab BAIHP Report, Cocoa, FL.
- Mullens, M., Gallas, K., & Moyer, N. (2002). "Energy Test Results and Recommendations for General Homes Corporation." University of Central Florida Housing Constructability Lab BAIHP Report, Cocoa, FL.
- Mullens, M., Gallas, K., Chasar, D. (2002). "Energy Test Results and Recommendations for Nationwide Homes." University of Central Florida Housing Constructability Lab BAIHP Report, Cocoa, FL.
- Mullens, M., & Chasar, D. (2002). "Energy Test Results and Recommendations for Cardinal Homes." University of Central Florida Housing Constructability Lab BAIHP Report, Cocoa, FL.
- Parker, D., Sonne, J., Sherwin, J. (2003). Flexible Roofing Facility: 2002 Summer Test Results, Prepared for: U.S. Department of Energy Building Technologies Program, July 2003.
- Parker, D. K., Sonne, J. K., Sherwin, J. R., & Moyer, N. (2000). "Comparative Evaluation of the Impact of Roofing Systems on Residential Cooling Energy Demand." Florida Solar Energy Center Contract Report #FSEC-CR-1220-00, Cocoa, FL.
- Sonne, J K, D S Parker and J R Sherwin (2002). Flexible Roofing Facility: 2001 Summer Test Results. FSEC-CR-1336-02. Florida Solar Energy Center, Cocoa, FL.
- Articles in Trade Press, Popular Press, and DOE Program Newsletters
- Automated Builder Magazine. "WSU Energy House." October 2000.
- Automated Builder Magazine "Northwest Portable Classroom Study." August 2003.
- Automated Builder Magazine. "Zero Energy Manufactured Home." October 2003.
- Buildings for the 21st Century. "Genesis Homes Showcases Innovative, High-performance Home." Spring 2002, p. 2.
- Energy Design Update. "Transforming Manufactured Housing: The Building America Way." January 2002, pp. 11-13.

Energy Design Update. "Palm Harbor's Prototype Home Scores Impressive Energy Savings." December 2001, pp. 7-8.

Energy Design Update. "Field Tests Commence on the World's Most Energy-efficient Manufactured Home," December 2000, p.3.

Energy Design Update. "New Building America Consortium to Focus on Industrialized Housing." March 2000, pp. 3-4.

Energy Design Update. "Energy Savings (and Unsolved Mysteries) Draw Attention to Georgia Habitat Project." Vol. 20 Number 4. April 2000.

Energy Design Update. "Ventilation System Decision Flow Chart." February 1999, p.16.

FlaSEIA Industry News. "SunBuilt and Building America Partnership." Spring 2002, Vol. 23, N.1 pp.5-8.

Florida Home Builder. "Today's Home Buyers Seeking Resource-efficient New Homes." May/June 2002, p.25.

Florida Home Builder (Ad). "Their Lifestyle Demands Quality and Comfort: Their Values Dictate a Healthy House." May/June 2002, p.25.

Gainesville Sun - Issues & Trends Section. "The Good News on Solar Homes." April 14, 2002, pp. G1 & G3.

Home Energy. "ICFs in North Texas." Nov/Dec 2002, pp. 39-40.

Home Energy. "Energy-efficient Manufactured Homes." May/June 2002, pp. 16-17.

Home Energy. "Chasing Interior Ducts." May/June 2002, Vol. 19.3.

Home Energy. "Building America: Seven Years of Progress." May/June 2002, p.2.

Home Energy. "Allergy Relief in Humid Climates." March/April 2002, pp. 30-33.

Home Energy. "Moisture Problems in Manufactured Housing." March/April 2002, pp. 24-29.

Indoor Environment Business. "Center Finds IAQ Problem from Leaky Air Handlers, Ducts in Florida." April 2002, p.4.

Orlando Sentinel - Home Section. "A Clean Sweep: Simple Steps Can Improve a Home's Indoor Air." September 22, 2001 (OrlandoSentinel.com)

Orlando Sentinel - Home Section. "In the Name of Energy." September 2, 2001. (OrlandoSentinel.com)

Rebuild America - Building America Partner Update. "Portable Classrooms: An Efficiency Challenge." March/April) 2002, p. 7.

Rebuild America - Building America Partner Update. "Building America: Solving Problems with Energy Efficiency." January/February 2002, p. 10.

Solar Today. "Home Energy Use Halved." November/December 2001, pp. 54-55.

#### One Page Fact Sheets

Building America Industrialized Housing Partnership,

Transforming the Market: Super-Efficient Manufactured Housing.

Manufactured Housing Laboratory: A Research and Training Facility.

Durable, Resource-Efficient Achievable Model (DREAM) Home.

Habitat for Humanity Collaborations: Affordable Energy Efficiency.

#### BAIHP Web Page Contents:

#### Manufactured Housing:

 Technical services provided to the HUD Code and modular industry. Chandra, Subrato, Michael Mullens, Mike Lubliner. <a href="http://www.fsec.ucf.edu/bldg/baihp/pubs/techserv/index.htm">http://www.fsec.ucf.edu/bldg/baihp/pubs/techserv/index.htm</a>

- Palm Harbor Homes Partnership, Case Study, http://www.fsec.ucf.edu/bldg/baihp/casestud/PALM/INDEX.HTM
- Plains Habitat Structural Insulated Panel Field Project, Case Studies page.
   <a href="http://www.fsec.ucf.edu/bldg/baihp/casestud/PLAINSHABITAT/index.htm">http://www.fsec.ucf.edu/bldg/baihp/casestud/PLAINSHABITAT/index.htm</a>
- Portable Classrooms, Case Studies page.
   http://www.fsec.ucf.edu/bldg/baihp/data/Portables/index.htm
- Side by side Comparison of Manufactured Homes, Case Study, http://www.fsec.ucf.edu/bldg/baihp/casestud/Bossier/index.htm
- Super Good Cents/Natural Choice Program, http://www.fsec.ucf.edu/bldg/baihp/casestud/WSU/index.htm
- WCI Communities, Inc. Evergrene Community, Case Studies page. http://www.fsec.ucf.edu/bldg/baihp/casestud/wci/index.htm
- WSU Energy House, Case Studies page.
   (www.fsec.ucf.edu/bldg/baihp/casestud/wsu/wsuhouse.htm).
- Zero Energy Manufactured Home, Case Studies page. http://www.bpa.gov/Energy/N/tech/zemh/

#### Site Built Housing:

- Cambridge Homes at Baldwin Park, Case Studies page.
   <a href="http://www.fsec.ucf.edu/bldg/baihp/casestud/cambridge/index.htm">http://www.fsec.ucf.edu/bldg/baihp/casestud/cambridge/index.htm</a>
- Central Florida DREAM Home, Case Studies page. http://www.fsec.ucf.edu/bldg/baihp/casestud/DREAM/index.htm
- Entry Level Homes, Case Studies page.
   <a href="http://www.fsec.ucf.edu/bldg/baihp/casestud/ELH/index.htm">http://www.fsec.ucf.edu/bldg/baihp/casestud/ELH/index.htm</a>
- Habitat for Humanity Energy Star Home Examples.
   <a href="http://www.fsec.ucf.edu/bldg/baihp/casestud/HfH\_EStar/index.htm">http://www.fsec.ucf.edu/bldg/baihp/casestud/HfH\_EStar/index.htm</a>
- High Efficiency Florida Home, Case Studies page.
   <a href="http://www.fsec.ucf.edu/bldg/baihp/data/CFRes/index.htm">http://www.fsec.ucf.edu/bldg/baihp/data/CFRes/index.htm</a>
- Orlando House, Florida's Future, Case Studies page.
   <a href="http://www.fsec.ucf.edu/bldg/baihp/casestud/orlando/index.htm">http://www.fsec.ucf.edu/bldg/baihp/casestud/orlando/index.htm</a>

#### Building Science and Design:

- About Window Films. McCluney, Ross.
   <a href="http://www.fsec.ucf.edu/bldg/active/fenestration/ResOptions/films.htm">http://www.fsec.ucf.edu/bldg/active/fenestration/ResOptions/films.htm</a>
- Advice to Florida Homeowners on Windows, Shades, and Film Selection. Ross McCluney. www.fsec.ucf.edu/bldg/active/fen/w select.htm.
- Industry Guide to Choosing the Best Residential Window Options for the Florida Climate. Ross McCluney. <a href="https://www.fsec.ucf.edu/bldg/active/fen/industry16.pdf">www.fsec.ucf.edu/bldg/active/fen/industry16.pdf</a>.
- Filter Back Grill Experiment, Current Data page.
   <a href="http://www.fsec.ucf.edu/bldg/baihp/data/filter/index.htm">http://www.fsec.ucf.edu/bldg/baihp/data/filter/index.htm</a>
- Fenestration Research. <a href="http://www.fsec.ucf.edu/bldg/active/fen/index.htm">http://www.fsec.ucf.edu/bldg/active/fen/index.htm</a>
- Pet House Project, Case Studies page.
   <a href="http://www.fsec.ucf.edu/bldg/baihp/casestud/pethouse/index.htm">http://www.fsec.ucf.edu/bldg/baihp/casestud/pethouse/index.htm</a>
- Six Moisture Damaged Homes, Case Studies.
   <a href="http://www.fsec.ucf.edu/bldg/baihp/casestud/moisture/index.htm">http://www.fsec.ucf.edu/bldg/baihp/casestud/moisture/index.htm</a>

# V BAIHP COLLABORATIONS

#### **BAIHP COLLABORATIONS**

BAIHP researchers collaborate with a variety of entities in the homebuilding industry and the energy efficiency and research realm. *Table 56* lists collaborators in the following categories:

- DOE National Labs (e.g. NREL, LBNL, ORNL)
- Code and Standards Bodies (e.g. RESNET, NFPA)
- Industry and Professional Organizations, Universities, and Suppliers

	Table 56 BAIHP Collaborations				
Collaborators	Description/Subject of Collaboration	Month			
<b>DOE National Labs</b>	· · · · · · · · · · · · · · · · · · · ·				
DOE-ATLANTA & Pacific Northwest National Lab (PNNL)	Hosted Traci Leath (DOE Atlanta Regional Office) and Michael Baechler (PNNL) for a tour of BAIHP facilities (FSEC in Cocoa) and BAIHP partners and projects in Florida (Orlando, Plant City, and Gainesville.)	JULY 03			
NIST and BA Partner The Energy Conservatory	NIST test home in Gaithersburg, Maryland	JULY 03			
PNNL	Technical Assistance for PNNL's efforts to evaluate HUD Uo value.	JUNE, JULY 03			
PNNL	Finalized efforts with PNNL and DOE on BAIHP cost data and duct research efforts.	AUG 03			
LBLN	Hosted Al Hodgson at FSEC and participated with Al on VOC sampling at the MHLab	JUNE 03			
ORNL	Participated in ORNL partnership with Loudon County (TN) Habitat for Humanity. Instrumentation, data collection, and web hosting of data.	APR 03 - MAR 04			
NREL	Philip Fairey and Danny Parker assisted with the BA benchmark development and review process.	APR 03 - MAR 04			
Code and Standards					
NFPA	Integrated BAIHP research and cost information into 5 proposals for the NFPA501 standards committee	JULY 03			
NFPA	Presented BAIHP cost and duct research efforts which resulted in adoption of a new standard on duct air tightness and testing protocol.	SEPT 03			
HUD - NFPA	Supported HUD's John Steven proposals to NPFA-501 committee. Proposals regard ducts and ventilation systems.	JAN, FEB 04			
RESNET	BA Benchmark Support, Philip Fairey.	APR 03 - MAR 04			
Industry and Professional Organizations, Universities, and Suppliers					
ASHRAE	Submitted draft of revised Chapter 9 of ASHRAE Handbook for HVAC Systems and Equipment Systems to Building America partners.	APR 03			
ASHRAE	Chapter 9 approved by ASHRAE TC6.3 with revisions suggested by TC 6.3 members.	MAY 03			

Table 56 BAIHP Collaborations				
Collaborators	Description/Subject of Collaboration	Month		
ASHRAE	Submitted Chapter 9 to ASHRAE for publication.	MAY 03		
ASHRAE	As part of ASHRAE Technical Committee 6.3 (TC6.3):	JUNE,		
	worked with committee members to develop a program	JULY 03		
	plan and research plan.			
ASHRAE	Worked with TC6.3 members and BAIHP partners to	JUNE,		
	coordinate committee activities for 2004 ASHRAE	JULY 03		
	Symposium in Anaheim, CA.			
ASHRAE	For 2004 Symposium, review of papers on HVAC	MAY,		
	performance.	JUNE,		
		JULY 03		
MHRA	Met in DC and Las Vegas, NV to discuss potential	APR 03		
N. GYD. I	collaborations.	1.00.00		
MHRA	M. Mullens and S. Chandra participated in MHRA	APR 03		
) (III) i	planning conference for 2005	3.6.437.02		
MHRA	At MHRA request, Neil Moyer assisted MHRA staff in	MAY 03		
	testing single a wide home in Alabama for the MHRA			
	moisture study.			
MHRA	Provided feedback to MHRA on their moisture research	JAN 04		
WITIKA	plan. MHRA attended <i>BAIHP Project Review Meeting</i>	JAN 04		
	plan. Wither attended Diffil Troject Review Meeting			
MHRA	Continued collaborations with MHRA on testing houses	MAR 04		
1,111111	for their moisture study. Written and oral feedback			
	provided.			
ACEEE	As Residential Buildings Panel Chair, Danny Parker	NOV 03		
	conducted a preliminary review of 99 abstracts for ACEEE			
	2004 Summer.			
ACEEE	Followed up on issues from ACEEE Summer Study.	JAN,		
		FEB 03		
ACEEE	Began peer review on papers submitted to ACEEE	MAR 04		
	Residential Building's panel; followed up on issues for			
	ACEEE Summer Study.			
HONEYWELL	Organized a meeting with Honeywell to exchange	MAY 03		
	information on Indoor Air Quality research and products			
HONEYWELL	Honeywell joined BAIHP team.	JULY 03		
HONEYWELL	Monthly/periodic conference calls to exchange	SEPT 03-		
NAUD	information.	MAR 04		
NAHB	Participated in the NAHB Building Systems Councils plant	MAY 03		
	tour. Networked with D. Kaufman, exec director and			
	began a dialogue to significantly participate in BSC			
MAUD	activities.  Mike Lybling participated in Energy Value Hausing	OCT 03		
NAHB	Mike Lubliner participated in Energy Value Housing	001 03		
	Award judging at NAHB Research Center.	ļ		

	Table 56 BAIHP Collaborations	
Collaborators	Description/Subject of Collaboration	Month
NOMACO	Continued collaborations with Mike Schroeder, Nomaco	APR 03 -
	representative on potential new product. Non disclosure	MAR 04
	agreement was finalized.	
SSHC, Inc.	Met with SSCI, manufacturer of ENERJOY radiant heating	JUNE 03
	panels, on continued BAIHP research efforts.	
USGBC	Met at Affordable Comfort in Kansas City, MO.	APR 03
USGBC	Met at GreenBuild conference in Pittsburgh, PA.	NOV03
USGBC	Hosted 2 day meeting for approximately 25 people	FEB 04
	at FSEC in February 2003. Group worked	
	through a business plan for national residential green	
	building standard operation.	
USGBC	Bi-monthly conference calls.	APR 03
	Anticipate continued collaboration with meeting in August	through
	2004 to discuss technical details of the standard with pilot	MAR 04
	standard development by end of 2004/beginning of 2005.	
AUBURN	Department of Architecture, Design, and Construction on	JUNE 03
UNIVERSITY	DESIGNhabitat, a sustainability and energy efficiency	
	project - Worked with undergraduate fellowship winner to	
	draft a monitoring plan and select HOBO sensors.	
AUBURN	HOBOs installed in, and data collected from 2	JULY,
UNIVERSITY	DESIGNhabitat homes and 1 conventional Habitat home	AUG 03
	(~3 yrs old).	
AUBURN	Data from HOBO monitoring sensors posted online and	SEPT 03-
UNIVERSITY	utility bill analysis completed. Review of data and	NOV 04
	refinement of utility bill analysis.	
AUBURN	Fellow completed study and presented paper to senior	DEC 03
UNIVERSITY	thesis committee.	
	Student took and passed USGBC's LEED certification test	
	as result of fellowship experience.	
CITY OF SANTA	City began planning a community of Green manufactured	JUNE 03
MONICA, CA	homes.	
IBACOS	Support IBACOS technical assistance to the New	SEPT 03-
	American Home to be displayed during the International	MAR 04
	Builders Show in Orlando, FL. in 2005.	
	Photo/video of the stages of construction provided on a	MAR 04
	weekly basis.	
NSF/PATH	Participated in NSF/PATH Housing Research Workshop	FEB 03
	(Feb 12-14) and presented paper.	
UCF	1 hour lecture to about 250 students as part of UCF Life	MAR 04
	activities on improving residential energy efficiency and	
	indoor air quality	

# VI BAIHP PROJECT MANAGEMENT

#### PROJECT MANAGEMENT

BAIHP project management includes participating in Building America program reviews/meetings and preparing monthly and yearly reports for project activities as well as managing all project tasks (see Sections 1-6) and subcontracts. In the 5<sup>th</sup> Budget Period, BAIHP also held a Project Review Meeting at FSEC in January 2004 to give interested parties an opportunity to give feedback to the project management team. A list of project management activities is included in *Table 57*.

Note that only project management activities for the current budget period are available here; if activities from previous budget periods are desired, please contact BAIHP project manager Subrato Chandra at <a href="mailto:subrato@fsec.ucf.edu">subrato@fsec.ucf.edu</a> or through the BAIHP web page at www.baihp.org.

Table 57 BA	Table 57 BAIHP Project Management Activities for the 5 <sup>th</sup> Budget Period			
BAIHP Task/Staff	Description/Subject	Month		
Task: Participation	in BA Quarterly Review Meetings			
Chandra	Washington DC. attendee	APRIL 03		
Fairey, Chandra	Washington DC, presenters	JULY 03		
Chandra	Washington DC, presenters	DEC 03		
Chandra,	Washington DC, attendees	FEB 04		
McIlvaine				
Task: Participation	in other BA Meetings	_		
Vieira,	DOE Meeting in Washington DC.	MAY 03		
McIlvaine	McIlvaine presented "Challenges to Implementing			
	Resource Efficiency," a summary strategies gleaned			
	BAIHP and EEIH projects and experience.			
Colon	SWA and BIRA expert review meetings in CA.	JUNE 03		
McCluney	BAIHP Project Fenestration Tasks Summary Report for	JUNE 03		
	work performed in June 2003			
Chandra	Responded to information requests from DOE	Through-		
	headquarters.	out the		
		budget		
		period		
<u> </u>	Budget Period Progress Report	_		
Chandra, All	Compiled and summarized results from 4 <sup>th</sup> Budget Period	APR 03		
Researchers	Report completed.	DEC 03		
Prepare Monthly Re		_		
Chandra,	Compiled and summarized monthly results from research,	APR 03-		
Alidina, All	implementation research, presentations, and publications.	MAR 04		
Manage Project and Subcontracts and Perform Related Activities				
Chandra	FY03 BAIHP subcontracts issued.	JULY 03		
Chandra	Met with WSU staff to coordinate 5 <sup>th</sup> budget period	OCT 03		
	activities and plan for 6 <sup>th</sup> budget period.			
Chandra	Continued meetings and discussions with Sam Taylor	FEB 04		
	regarding Building America deployment through Energy			
	Extension services			

Chandra	Continued proposal preparation for BAIHP FY04 funding.	FEB 04
Chandra	Preparation of FY05 AOP proposal submission to DOE.	MAR 04
D : 4D : M	4. A EGE C	
Project Review Meeting at FSEC		
Chandra	Planned BAIHP Project Review meeting at FSEC.	OCT 03-
		JAN 04
Chandra, All	Hosted BAIHP Project Review Meeting (2 days) at FSEC	JAN 04
Researchers	with participation from industry partners and DOE.	

### Appendix A BAIHP Media Coverage

#### **BAIHP Media Coverage**

#### **5th Budget Period:**

During the fifth budget period, BAIHP research received media attention in a variety of publications and television shows.

- Orlando Sentinel, Sunday, February 8, 2004. "The Green Revolution: A Florida First. Part 1 of a 4-part series." "Blueprints for the home planet." (*Figures A1-A3*)
- Orlando Sentinel, Sunday, February 15, 2004. "The Green Revolution: Interior Motives. Part 2 of a 4-part series." "Health worries hit home." (*Figures A4-A6*)
- Orlando Sentinel, Sunday, February 22, 2004. "The Green Revolution: Applying Principles. Part 4 of a 4-part series." "Pioneer spirit." (*Figure A7-A9*)

#### **Prior to 5th Budget Period:**

- "Tricks of the Trade" radio show and "Build It Green" pilot television program. BAIHP provided training and presentation.
- *FlaSEIA Industry News*, "SunBuilt and Building America Partnership," Spring 2002, Vol.23, Number 1, pp.5-8.
- Florida Home Builder, "Today's Home Buyers Seeking Resource-Efficient New Homes," May/June 2002, p.25.
- *Home Energy Magazine*, "Chasing Interior Ducts," May/June 2002, pp.24-28.
- Home Energy Magazine, "Energy-Efficient Manufactured Homes," May/June 2002, pp.16-17.
- Energy Design Update, "Building America: Seven Years of Progress," May 2002, p.2.
- Indoor Environment Business, "Center Finds IAQ Problem from Leaky Air Handlers, Ducts in Florida," April 2002, p.4.
- The Gainesville Sun Issues & Trends Section, "The Good News on Solar Homes," April 14, 2002
- Buildings for the 21st Century, "Genesis Homes Showcases Innovative, High-Performance Home," Spring 2002, p.2.
- Home Energy Magazine, "Allergy Relief in Humid Climates," March/April 2002, pp. 30-33.
- *Home Energy Magazine*, "Moisture Problems in Manufactured Housing," March/April 2002, pp. 24-29.
- Partner Update (Rebuild America Building America), "Portable Classrooms: An Efficiency Challenge," March/April 2002, p.7.
- Partner Update (Rebuild America Building America), "Building America: Solving Problems with Energy Efficiency," January/February 2002, p.10.
- Energy Design Update, "Transforming Manufactured Housing (the Building America Way)," January 2002, pp.11-13.
- *Energy Design Update*, "Palm Harbor's Prototype Home Scores Impressive Energy Savings," December 2001, pp. 7-8.
- Solar Today, "Home Energy Use Halved," November/December 2001, pp. 54-55.

Listing continued on page A11.



Figure A1 Page J1 of Orlando Sentinel, Sunday, February 8, 2004. "The Green Revolution: A Florida First. Part 1 of a 4-part series." "Blueprints for the home planet."



Figure A2 Page J4 of Orlando Sentinel, Sunday, February 8, 2004. "The Green Revolution: A Florida First. Part 1 of a 4-part series." "Blueprints for the home planet."



Figure A3 Page J5 of Orlando Sentinel, Sunday, February 8, 2004. "The Green Revolution: A Florida First. Part 1 of a 4-part series." "Blueprints for the home planet."



Figure A4 Page J1 of Orlando Sentinel, Sunday, February 15, 2004. "The Green Revolution: Interior Motives. Part 2 of a 4-part series." "Health worries hit home."



Figure A5 Page J4 of Orlando Sentinel, Sunday, February 15, 2004. "The Green Revolution: Interior Motives. Part 2 of a 4-part series." "Health worries hit home."



Figure A6 Page J5 of Orlando Sentinel, Sunday, February 15, 2004. "The Green Revolution: Interior Motives. Part 2 of a 4-part series." "Health worries hit home."

\_



Figure A7 Page J1 of Orlando Sentinel, Sunday, February 22, 2004. "The Green Revolution: Applying Principles. Part 4 of a 4-part series." "Pioneer spirit."



Figure A8 Page J3 of Orlando Sentinel, Sunday, February 15, 2004. "The Green Revolution: Interior Motives. Part 2 of a 4-part series." "Health worries hit home."

- *Orlando Sentinel* Home Section, "<u>A Clean Sweep</u>; Simple Steps Can Improve a Home's Indoor Air," September 22, 2001
- Orlando Sentinel Home Section, "<u>In the Name of Energy</u>," September 2, 2001
   OrlandoSentinel.com
- WSU Cougar Football Program, "WSU Energy House Serves as a Technology Test Bed," September 2001, WSU Press Release
- *Energy Design Update*, "Field Tests Commence on the World's Most Energy-Efficient Manufactured Home," December 2000, p.3.
- *Energy Design Update*, "New Building America Consortium to Focus on Industrialized Housing," March 2000, pp. 3-4.
- Automated Builder Magazine, "WSU Energy House", October 2000.
- Energy Design Update, "Ventilation System Decision Flow Chart," February 1999, pp. 16.
- Builder, "Resources: HVAC Electronic Control," October 1998, pp. 296.
- *Air Conditioning, Heating & Refrigeration News*," Fan recycling control offers improved indoor air and comfort for tight houses," September 28, 1998, pp. 30-33.
- Air Conditioning, Heating & Refrigeration News," What's New: Blower Control," September 14, 1998, pp. 24.
- *Energy Design Update*, "Computer Simulations Look Good for "Cathedralized" Attics," September 1998, pp. 6-10.
- Home Energy Magazine, "Energy Stars Shine on Manufactured Homes," July/August. 98, pp. 9-10.
- *The Home Front News*, "My Favorite New Product," July 1998.
- *Architecture*, "Technology: SIPS, Not Studs," June 1998, pp.148-152.
- Concrete Home News, "New \$50 Device Controls Ventilation," June 1998.
- Environmental Design and Construction, "New HVAC Products," May/June 1998, pp. 41.
- Builder, "Space Shot Building Products: In Orbit FanRecycler," January 1998, pp. 330.
- Builder, "Space Shot Building Products: Steel studs with thermal breaks," Jan 98, pp. 324.
- Solar Collector, "Smart box a boon to indoor air quality," December 1997, pp. 3.
- Energy and Housing Report, "FSEC Develops FanRecycler," December 1997, pp. 206.
- *Energy Design Update*, "Controller Improves the Efficiency of Furnace-Based Ventilation Systems," September 1997, pp. 15.
- New Building Products, "Low-Cost Ventilation System," August-September 1997, Vol. 3
   No. 5, pp. 2.
- Nisson, J.D. Ned, Don Best, 1997. "Steel Framing for Houses," pp. 47-48, Cutter Information Corp., Arlington, MA.
- The *Building Systems Magazine*, of the National Association of Homebuilders, features a one-half-page add on a regular basis for the Structural Insulated Panel Association which prominently sites a direct quote from Armin Rudd's research report on the 1993 side-by-side testing in Louisville, KY.
- *Popular Science*, "Home Technology, Building Technology: The Panels Prevail," by Judith Anne Gunther, Apr-94.
- *The DSM Letter*, "New Technology: Insulated Panels Could Challenge Fiberglass Batts In Residential Market," Feb-94, pp.5.
- Progressive Architecture, "Technics Focus: Building With Panels," by Steven Winter, Nov-93, pp. 88-90
- Energy and Housing Report, "Side-By-Side Tests," Mar-93.
- *Energy Design Update*, "Most Practical Research of the Month Award: Foam Core vs. "Stick Built"--Side-by-Side Tests," Jan-93.

# Appendix B UCF Housing Constructability Lab Annual Report

Progress Report: April 2003 – March 2004

#### **Prepared for**

# The Industrialized Housing Partnership & The Building America Program

**Sponsored by** U.S. Department of Energy

Prepared by UCF Housing Constructability Lab Dr. Michael A. Mullens, PE

June 15, 2004

#### **Executive Summary**

UCF researchers continue to identify and develop prototype applications of computer technology for the modular factory floor. Research efforts this year focused on real time production labor data collection. While labor represents a relatively modest fraction of production cost, typically 10-15%, it has a profound impact on operations, including product quality, cycle time, material waste, and labor productivity. The Status Tracking and Control System (STACS) is a real time shop floor labor data collection and reporting system. Production workers use wireless laser scanners to report their current work assignment. STACS reporting is web based and provides both real time manufacturing status and summaries of historical production performance.

An alpha prototype of STACS was tested in drywall finishing operations at Avis American Homes (Avis, PA) in Summer 2003. Test results demonstrated that production workers could operate the system effectively and that the system accurately captured scanned activity. Large scale plant-wide testing began at Penn Lyon Homes (Selinsgrove, PA) in March 2004 and will continue into Summer 2004. Test results will be used to develop labor models using linear regression and neural nets.

Trinity Construction Corporation is a large shell contractor serving Florida homebuilders. Faced with increasing demands for higher quality, lower cost and more timely delivery, Trinity is actively exploring innovative alternatives to conventional concrete block construction, the predominant homebuilding technology in the central and south Florida market. Trinity operates a pre-cast concrete panel production facility, in South Bay, Florida where concrete panels are pre-cast, transported to the construction site, and quickly assembled using a construction crane. The UCF Housing Constructability Lab (HCL) was asked to assist Trinity in improving the current panelizing process by incorporating lean production principles.

Preliminary research determined that material handling and rework were primary contributors to the 47% of labor consumed by non-value added activities. Once started, the flow of value-added activity was routinely interrupted. Poor access to materials and tools, rework, ill-defined process flows, and workforce/1<sup>st</sup> line supervision issues were contributing factors. To address these issues, HCL researchers utilized lean production principles - challenging non-value added activities and removing the obstacles to continuous production flow. Recommendations addressed issues of organization/communication, structured procedures and work flow, material handling, and off-line sub-assembly.

To test the recommendations, Trinity allowed HCL researchers to perform a 3-day pilot test. The test involved a single house consisting of 25 wall panels with a gross wall area of 3,119 ft<sup>2</sup>. Productivity increased for all observed activities, with an average increase of 68%. Not all recommendations could be realized during the test. Some equipment and personnel issues could not be resolved on a short-term test basis. This suggests that the true potential is significantly greater than that observed during the test – possibly approaching 200% increase in labor productivity. Corresponding cycle time reductions are estimated to be 20-25%. This successful pilot test has given Trinity the opportunity to develop a competitive advantage in the housing construction market and a good foundation to dominate it.

#### **Innovative Applications of Computer Technology on the Factory Floor**

UCF researchers continue to identify and develop prototype applications of computer technology for the modular factory floor. Research efforts this year focused on the collection of real time production labor data. While labor represents a relatively modest fraction of production cost, typically 10-15%, it has a profound impact on operations. Except for the slower winter months, experienced labor is a scarce resource. Even if labor is sufficient in the aggregate, it is rarely positioned where it is most needed at a particular moment in time. Competitive market pressures are resulting in an increasing mix of custom home features, increasing the likelihood of "floating bottlenecks" in production. Quality and safety can suffer as undermanned crews rush to complete custom features (i.e., fire-rated walls or a hip roof). If a crew cannot keep pace, the line slows, production rate drops, overtime is required and delivery dates are missed.

In the past, the sheer number of production activities, lengthy cycle times and extensive product customization have discouraged manufacturers from accurately estimating labor needs and using this information to plan and control production. Instead, they have responded by controlling labor at the overall plant level, attempting to maintain labor at a historical target value, which is stated as a percentage of overall production cost or sales revenue. A limitation of this approach is that it seldom reflects the actual labor content in the product, particularly in periods of increasing customization. To address the problem of shifting bottlenecks, many manufacturers use flexible resources termed "utility workers", "flex workers", or expeditors. However, the decision to deploy these workers is often made with minimal planning, after a problem has started to impact the line.

To better understand the true usage of production labor, the UCF research team has developed the Status Tracking and Control System (STACS). STACS is a real time labor data collection and reporting system designed specifically to meet the needs of the industrialized housing industry. A schematic of the STACS system is shown in Figure 1. Production workers use wireless laser scanners to report their current work assignment. Scanned information is transmitted immediately to a base station and then relayed to a local shop floor processor, where it is verified and temporarily staged. Information is periodically transmitted via wireless LAN to a central database server where it is stored and used for reporting. STACS reporting is web based and provides both real time manufacturing status and summaries of historical production performance. Real time production performance can be monitored from the web-based STACS Dashboard (Figure 2). "Clicking" on any item on the Dashboard will display corresponding real-time details. Historical results can be used for a variety of analytical and management purposes:

- The development of analytical labor estimating models. These models can be used to estimate labor requirements for product costing, production scheduling and labor planning.
- o As a baseline for continuous improvement efforts.

An alpha prototype of STACS was tested in drywall finishing operations at Avis American Homes (Avis, PA) in Summer 2003. Test results demonstrated that production workers could operate the system effectively and that the system accurately captured scanned activity (Figure 3). Large scale plant-wide testing began at Penn Lyon Homes (Selinsgrove, PA) in March 2004 and will continue into Summer 2004. Test results will be used to develop labor models using linear regression and neural nets.




Figure 1. Structure of STACS system




Figure 2 STACS real-time dashboard



Figure 4. Scanning drywall activities at Avis America

#### Lean Production of Precast Concrete Panels

Trinity Construction Corporation is a large shell contractor serving Florida homebuilders. Faced with increasing demands for higher quality, lower cost and more timely delivery, Trinity is actively exploring innovative alternatives to conventional concrete block construction, the predominant homebuilding technology in the central and south Florida market. Trinity operates a pre-cast concrete panel production facility, in South Bay, Florida where concrete panels are pre-cast (Figure 1), transported to the construction site, and quickly assembled using a construction crane (Figure 2). The UCF Housing Constructability Lab (HCL) was asked to assist Trinity in improving the current panelizing process by incorporating lean production principles.





Figure 1 Panel forms on forming bed

Figure 2 Setting pre-cast concrete wall panel

Preliminary research involved extensive observation and analysis. Value stream mapping identified activities that contributed value to the customer as well as activities that added little or no value. Material handling and rework were primary contributors to the 47% of labor consumed by non-value added activities. Once started, the flow of value-added activity was routinely interrupted. Poor access to materials and tools, rework, ill-defined process flows, and workforce/1<sup>st</sup> line supervision issues were contributing factors. To address these issues, HCL researchers utilized lean production principles - challenging non-value added activities and removing the obstacles to continuous production flow. Recommendations addressed issues of organization/communication, structured procedures and work flow, material handling, and off-line sub-assembly. A typical recommended daily production flow is shown in Figure 3.

To test the recommendations, Trinity allowed HCL researchers to perform a 3-day pilot test. The test involved a single house consisting of 25 panels. The panels had a total of 21 window and door openings and a gross wall area of 3,119 ft². The first day was spent organizing and training the test production team and the second and third days were dedicated to production. All 25 panels were produced. Productivity increased (Table 1) for all observed activities. Lifting productivity was not observed. Conservatively assuming that lifting will remain at historical levels, overall labor productivity increased by 47%. If lifting productivity is assumed to increase

at the average rate observed for the other activities, overall productivity would increase 68%. Not all recommendations could be realized during the test. Some equipment and personnel issues could not be resolved on a short-term test basis. This suggests that the true potential (Table 1) is significantly greater than that observed during the test – possibly approaching 200% increase in




Figure 3. Summary of typical daily production schedule using continuous flow

labor productivity. Corresponding cycle time reductions are estimated to be 20-25%.

The HCL research team recommended that Trinity proceed with implementation of the lean production recommendations. In addition to the technical recommendations, the research team also made recommendations involving worker empowerment, dealing with the heat and sun, and

Table 1. Productivity - ft <sup>2</sup> of wall/ labor hour							
		Potential	Pilot	Productivity			
<b>Process</b>	Existing	Process	Test	Increase			
Phase	Process	Results	Results	during Test			
Layout	53	152	91	72%			
Prep	52	149	79	52%			
Pouring	146	211	296	103%			
Lifting	75	440	75*	0%			
Total	17	49	25	47%			

material/equipment availability. Potential future research areas include covers for the production area, on-site factories in new home developments, and factory installed wall insulation. This successful pilot test has given Trinity the opportunity to develop a competitive advantage in the housing construction market and a good foundation to dominate it.

#### **Publications and Presentations**

Mullens, M. and M. Kelley, "Lean Homebuilding Using Modular Technology," *Housing and Society: Journal of the Housing Education and Research Association*. In Press

Mullens, M. and M. Hastak, "Defining a National Housing Research Agenda: Construction Management and Production" *Proceedings of the NSF Housing Research Agenda Workshop*, Feb. 12-14, 2004, Orlando, FL. Eds. Syal, M., Mullens, M. and Hastak, M. Vol 2.

Mullens, M. "Production flow and shop floor control: Structuring the modular factory for custom homebuilding" *Proceedings of the NSF Housing Research Agenda Workshop*, Feb. 12-14, 2004, Orlando, FL. Eds. Sval. M., Mullens, M. and Hastak, M. Vol 2.

Mullens, M. and I. Nahmens, "Lean Principles Applied to Pre-cast Concrete Homebuilding," *Industrial Engineering Research '04 Conference Proceedings*, Houston, May, 2004.

- Elshennawy, A., M. Mullens, I. Nahmens, "Quality-Based Compensation Schemes for Modular Homebuilding," *Industrial Engineering Research '04 Conference Proceedings*, Houston, May, 2004.
- Nahmens, I., M. Mullens and A. Elshennawy, "The Impact of Demographics on New Homebuyer Satisfaction," *Industrial Engineering Research '04 Conference Proceedings*, Houston, May, 2004.
- Broadway, R. and M. Mullens, "Shop Floor Information Systems for Industrialized Housing Production," *Industrial Engineering Research '04 Conference Proceedings*, Houston, May, 2004.

### **Appendix C**

Annual Report of
Washington State University Energy Program (WSU)
with Oregon Office of Energy, and
Idaho Department of Water Resources, Energy Division

#### Annual Report

#### BUILDING AMERICA INDUSTRIALIZED HOUSING PARTNERSHIP WSU Extension Energy Program, IDWR, ODOE April 1, 2003 – March 30, 2004

The Washington State University Energy Program (WSU), together with partners Oregon Office of Energy and Idaho Department of Water Resources, Energy Division, continue to provide technical and research support to the Northwest Energy Efficient Manufactured Housing Program (NEEM)/Energy Star program in the Pacific Northwest. The NEEM/Energy Star program involves 20 plants in three states, hundreds of retailers and thousands of homebuyers.

The NEEM program includes the brands Super Good Cents and Natural Choice, denoting homes heated respectively by electricity and Natural Gas/propane (note – NEEM staff are in the process of phasing out the Natural Choice brand, as it is no longer supported by natural gas utilities and regional propane associations. After Year 5, the Super Good Cents brand will denote both electric and gas heated homes.)

#### Aligning with New Building America Goal

During Year 5, BAIHP staff performed a benchmarking evaluation, to assess the improvement of NEEM homes over the entire BAIHP project period. The benchmarking was based on a home defined by NREL (built to IECC requirements). The savings over the benchmark home were estimated using version 2.2 of Energy Gauge USA. Evaluations were performed for a typical 1600 ft<sup>2</sup> double wide home with 12% glazing to floor area (the NEEM fleet average) in three Pacific Northwest climate zones: Portland, OR; Spokane, WA; and Missoula MT.

The homes were benchmarked assuming a continuously operating whole house ventilation system, resulting in a significant thermal energy penalty. Additional benchmarking was also conducted using the 164 kWh/year ventilation assumption in the NREL benchmark, in an effort not to penalize the homes for improved IAQ associated with HUD whole house ventilation system requirements and ASHRAE 62.2.

In Year 5, improvements were made to NEEM HVAC systems and duct specifications as a result of BAIHP research (see Refinement of NEEM Specifications, below.) Additional benchmarking is presented that reflects 2004 improvements made to the NEEM duct specification.

The results of the benchmarking varies considerably by HVAC type, water heat and climate, as noted in Table 1 below. Some key observations:

- In all climate zones, electric homes result in negative savings if the ventilation penalty is assumed. This is largely the result of the assumption that the benchmark home has a heat pump that performs without installation problems; an assumption that will be evaluated by BAIHP research.
- Gas heated NEEM homes came closest to meeting the overall BAIHP goal of 40% over the NREL benchmark, but only met the goal if gas heat is paired with electric water heat.
- Eliminating the ventilation system penalty has a higher impact on benchmarking results (9 to 23 percentage points) than improved duct leakage tightness (3 to 11 percentage points).
- It should be noted that Benchmarking these NEEM homes against the HUD-FMCSS

requirements (Uo=.079) for manufactured homes rather than the IECC (Uo=0.06) would yield considerably higher savings than current benchmark assumptions.

Table 1
Benchmarking Savings Results

Duct Leakage	Pre-2004*	2004**	Pre-2004*	2004**
Ventilation System Penalty	Yes	Yes	No	No
Portland				
Electric Furnace	-31	-20	-8	0
Heat Pump	11	14	20	22
Gas Heat/Elec DHW	16	22	32	37
Gas Heat/Gas DHW	15	20	30	34
Spokane				
Electric Furnace	-18	-9	2	10
Heat Pump	17	21	27	30
Gas Heat/Elec DHW	22	27	36	41
Gas Heat/Gas DHW	21	26	35	39
Missoula				
Electric Furnace	-12	-3	8	15
Heat Pump	17	22	28	32
Gas Heat/Elec DHW	21	26	35	40
Gas Heat/Gas DHW	20	25	34	38


<sup>\*</sup> Pre-2004 – Duct leakage of -132 cfm@25PA

**Technical Assistance**/Figure 1 shows, by program year, the number of homes produced with technical assistance from BAIHP, as well as the number of homes submitted for Energy Star designation by BAIHP staff, and the breakdown of homes by benchmarking score. Please note the following:

- The benchmarking includes the assumption, based on the random study (see Random Study, below) that 24% of all homes included after-market heat pumps.
- No benchmarking was performed for Years 1 and 2, due to a lack of accurate regional data.
- In Year 5, the appearance of homes that achieved a 30+% benchmark is the result of the improvements made to the NEEM HVAC specifications.

<sup>\*\* 2004 –</sup> Duct leakage of -60 cfm@25PA

## Homes produced with BAIHP Technical Assistance



<sup>\*</sup> Homes not benchmarked due to a lack of regional data

The continued success of the program is due to several factors. BAIHP and NEEM staff have worked to increase awareness within the manufactured housing industry of the marketing value of energy efficiency, increase participation by utilities in incentive programs, and promote the cobranding of NEEM with Energy Star.

The increase in Energy Star designations is due to refinement of the SGC duct sealing specifications, resolving a discrepancy between the SGC specifications with Energy Star's duct sealing protocols; while this question was being resolved, BAIHP staff did not submit homes to DOE for Energy Star designation. In year 5, remaining discrepancies with manufacturers in Idaho were further resolved, allowing BAIHP staff to accurately report all qualifying homes.

#### SGC/E-STAR program activities include:

Refinement of SGC specifications: BAIHP staff continually work to refine the existing SGC specifications, a result in large part to innovative building technologies researched in BAIHP.

In Year 5, BAIHP staff worked with the NEEM team and individual manufacturers to develop revisions to NEEM specifications, including allowing only mastic for duct sealing, requiring metal flex duct for whole house ventilation fans, and changing the air infiltration specification from  $7.0 \text{ ACH}_{50}$  to  $5.0 \text{ ACH}_{50}$ .

The revised specifications were voted on and accepted by the manufacturers; they took effect on January 1, 2004.

BAIHP staff continue to work with EPA and other regional partners on clarifying the equivalency of SGC with Energy Star. In Year 4, BAIHP staff developed a new Energy Star compliance path for climate zone 2 that does not require a heat pump. The non-heat pump path uses a heat recovery ventilation system, a .93 EF hot water heater and tighter ducts and envelope.

Revised In-plant Manual: In Year 5, in light of the revisions to the NEEM specifications, BAIHP staff from the Oregon Department of Energy developed an updated in-plant inspection manual, with new graphics, including details on correct installation of heat recovery ventilation. Many of the manual updates are the result of BAIHP research and demonstration efforts, including use of hybrid floor systems and proper duct sealing with mastic. The manual also now include a regionally consistent problem home inspection protocol.

SGC Random Home Testing: In 1994-1995 (prior to implementation of BAIHP), SGC staff conducted field testing of 178 SGC homes built in 1992-1993. In BAIHP Year 1, staff in Idaho and Washington field-tested 49 SGC homes built in 1997-98. In Year 2, analysis of field test data confirmed some improvements to home set-up procedures and air leakage control, while highlighting a need to improve duct tightness and ventilation system operation (through homeowner education.) In Year 3, BAIHP staff produced an updated homeowner ventilation brochure.

In Years 4 and 5, BAIHP staff worked with Ecotope to develop a valid sample for the next round of field testing, and began to develop the field testing protocol. In year 5, Ecotope selected 105 homes from the total production for the years 2001-2002. The field testing took place in the summer of Year 5. Findings from the testing include:

- Average house size is 1769 ft<sup>2</sup>; double section homes are also getting bigger, on average. The house size is very comparable to the homes built in 1997-1998 but 20% larger than the homes in 1994-1995 study
- Houses are getting tighter, according to the blower door results. The average air leakage rate at 50 Pa is 4.2, which represents a tightening of almost 25% over the original MAP home average. The median equivalent leakage area (ELA) for double-section homes has decreased by about 12% despite a substantial increase in house size.
- Only about 20% of NEEM homes in this study contain intentional outside air inlets. This is the result of BAIHP research indicating that intentional outside air inlets are unnecessary to provide adequate fresh air.
- 2/3 of homes in the study have dedicated whole house fans and a substantial fraction of homeowners are using their whole house fans. However, a significant minority (30%) does not turn them on.
- About half of homes in the study use central cooling, with more than half of these homes using a heat pump.
- Duct systems are about 20% leakier than in the Year 1 study and about 10% leakier than in the 1994-1995 study (when the comparison is normalized by house size).
- The median supply leakage fraction is 11-13% for the homes in this sample. The duct loss translates into a heating system efficiency loss of between 10-20% overall, depending on the location of the home (west side or east side of the mountains) and type of heating equipment (heat pumps perform worse).

Problem Homes: In offering technical support to owners of over 100,000 homes built since 1990, the staff answers questions from homeowners, manufacturers, retailers and others. In Year 5, staff from Washington, Oregon and Idaho responded to over 90 phone calls and conducted 18 field visits. The number of problem home field visits has significantly decreased over the history of the program, in large part because of manufacturer's and installer's increased awareness of the SGC/E-Star specifications, and the requirement that manufactured home installers be certified in Washington and Oregon.

BAIHP staff participated in quarterly meetings of the Washington State Manufactured Housing Technical Working Group, which coordinates the certification of manufactured housing set-up crews.

While butyl duct tape is no longer allowed under current NEEM specifications, a consistent issue in the field continues to be excessive duct leakage, due in large part to failures of duct tape. These findings were brought to the attention of the NFPA-501 Mfg Housing Standards committee, resulting in a successful proposal to revise the duct sealing specifications in the NFPA-501 standard

*In-Plant Inspections:* On a quarterly basis, BAIHP staff visits each of the manufactured housing plants to verify compliance with SGC/E-Star specifications. Inspections include a plant audit, ventilation system testing, and troubleshooting construction-related problems with plant staff and independent inspectors. Consistent issues in the plant include wall insulation compression or voids due to improper cutting of batts, attention to duct installation and air sealing.

Transition to mastic: As mentioned above, the NEEM program eliminated the use of butyl tape for duct sealing, and implemented mastic. As of the end of Year 5, ten manufacturers have successfully transitioned to the mastic. Testing in-plant has indicated significant improvement in the duct leakage rates of these homes in these factories—an average 36.8 cfm @ 25 PA (versus 50.1 cfm @ 25 PA pre-mastic), a 27% improvement.

Duct Workshops: In Year 5, BAIHP staff continued to provide workshops focused on improved duct installation and inspection oversight, working in partnership with BAIHP partner Flexible Technologies to demonstrate the added value of their innovative duct sealing technologies.

Blown Cellulose Floor Insulation: Industry partner Engineered for Life (EFL, formerly Greenstone) has been working with SGC/E-STAR manufacturers to validate a hybrid insulation system. These systems, composed of one R-11 belly blanket and R-22 blown cellulose insulation eliminates overcompression and reduces the chance of leakage during transport and set-up, while minimizing material and labor costs. Fleetwood Homes of Washington adopted this system for all of their homes in Year 3. One potential consequence of using the hybrid system is increased moisture in the belly; in Year 5, BAIHP staff installed data loggers in two homes to determine whether this is a problem; the data loggers will be retrieved in Year 6.

High Efficiency Gas Furnaces: Initial evaluations of 90% efficient gas furnaces indicates that there is no incremental installation cost to the use of these furnaces, as no field modifications are required. In Year 5, Nordyne and Evcon came out with furnaces with an appropriate footprint for manufactured housing; Intertherm also continues to offer a 90% efficient model.

Demonstration Homes: In Year 5, technical support was provided for the following demonstration homes:

Zero Energy Manufactured Home (ZEMH): BPA, working with BAIHP staff in Idaho and Washington, provided funding for the most energy efficient manufactured home in the country. The RFP was sent to 18 Northwest manufacturers; Kit Homes of Idaho was selected as the manufacturer of the home. BAIHP staff solicited 24 industry partners to provide energy efficient building components, including Icynene wall, floor and roof insulation, a low-cost HUD-approved solar system, sun-tempered solar design, and Energy Star© windows, appliances and lighting. Partners include Building America Team members such as Flexible Technologies, Icynene and LaSalle.



Figure 3: Zero Energy Manufactured Home, on site at the Nez Perce Fish Hatchery

The ZEMH was built in Year 4 along with a control home. The ZEMH was displayed at the 2002 Spokane County Interstate Fair before siting at the Nez Perce tribal fish facility near Lewiston Idaho. Blower door and duct leakage tests at the plant and on-site indicate that this is the tightest home ever tested by BAIHP staff.

Working with FSEC and BPA, BAIHP staff installed monitoring equipment for the ZEMH. Monitoring of the home began in Year 5. Preliminary findings include:

- Measured net energy use of the ZEMH 6% is lower than the base home, not normalized for occupant behavior. This also does not take into account the fact that the ZEMH's PV system was only fully operational for one month.
- The ZEMH required 45% less space heating energy, possibly due to improved building envelope measures, and the lack of consistent HRV operation.
- The measured envelope leakage in the ZEMH was 2.0 ACH<sub>50</sub>, much lower than the base home (indeed, lower than any other NEEM home tested in the field) and substantially tighter than typical HUD code homes.
- The ZEMH total duct leakage was 46% lower than the base home; leakage to the outside was 405% lower than the base home. BAIHP staff speculate that the unprecedented low leakage to the outside value is the result of the ducts in the ZEMH being located within the conditioned space, and effectively within the pressure envelope of the home,

- surrounded as they are by foam insulation.
- The solar water heating system in the ZEMH provides most, if not all of the energy needed during the summer months, and roughly 45% of the overall water heating energy use.
- The PV system with net metering provides 38% of the total ZEMH energy use.

The project highlights the importance of occupant choices and behavior on the performance of energy efficient housing. Based on the preliminary monitoring data and occupant surveys, the behavior patterns of the ZEMH occupants are not themselves "energy efficient". These patterns create the appearance of a less efficient home. On the other hand, the behavior of the ZEMH occupants may shorten the payback for the innovative technologies of the ZEMH.

BAIHP staff also performed a benchmarking analysis on the ZEMH, as part of the overall benchmarking effort. The ZEMH reached a level of 60% above the NREL prototype, which indicates the difficulty of obtaining a high benchmarking score As part of the effort to

- NOGI Gardens:, Nogi Gardens is a 75-home community located in southeast Seattle The project contains the first two-story, HUD code attached "townhouse homes." All the homes have been built by Marlette Homes in Hermiston, Oregon to SGC/E-Star specifications. A blower door test of the building envelope showed 5.0 ACH at 50PA, average for a manufactured home in the Pacific Northwest. Duct leakage is very low, due to Marlette's use of mastic and duct risers. During Year 5, Noji Gardens was the recipient of the HUD Secretary's Gold Award for Excellence. Marlette was also the winner of the Energy Value Housing Award in Year 5.
- WSU Energy House: This 2600 ft.<sup>2</sup> home has been built to beyond SGC standards, and incorporates Energy Star lighting and appliances. The home has received significant national exposure through tours, local and trade media, and the BAIHP website, which includes house monitoring data. BAIHP staff use the house to test additional innovative technologies and testing methods. In Year 5, BAIHP staff developed a moisture case study based on research at the WSU Energy House, published under a separate Building America project.

In addition to the projects listed above, previous highlights from BAIHP research include:

- Vincent Village: Vincent Village is a 49 home rental community, located in Richland, WA. All of the homes are small, single section, heated and cooled by Insider heat pumps. Half the homes were built to SGC standards, the other half were not. Metered utility data indicate average yearly savings of \$241 for the SGC homes.
- Fish Facility: Three SGC homes were built at the Nez Perce tribal fish facility in Cle Elum, Washington. One of these homes is equipped with Energy Star appliances and lighting; all three homes are heated with Insider heat pumps. Testing revealed significant envelope and duct leakage, likely due from failure of butyl duct tape at risers.
- *SIP House:* This home, located in Western Washington and constructed by Champion Homes, is the first stress skin insulated panel manufactured home. House tightness was measured at 3.55 ACH at 50 Pa, well below the average numbers for all previous random home studies. Energy savings are estimated at 50% greater than HUD code minimum.

Field Monitoring: In Year 5, monitoring equipment was installed in the ZEMH and base home. The monitoring equipment collects the following energy use data from each home:

- Total electric use from grid
- Resistance elements in heat pump
- Heat pump compressor and fan motors
- Water heating equipment, including gallons used
- PV energy production (ZEMH)

Sensor data are collected every 15 minutes by data loggers and transmitted daily to the host computer. Summary data reports are available at: http://infomonitors.com/zmh/. Plug-type energy loggers were installed in mid March 2003 to sub-meter the energy use of the refrigerator, freezer and clothes washer in each home, as well as the radiant heat panel and HRV in the ZEMH. Data from these loggers was collected (by occupant readings) in mid-December 2003.

The WSU Energy House data has been monitored since year 1. Monitoring data being collected includes weather, temperature, humidity, CO<sub>2</sub>, CO, and 8 differential pressures. Energy use data from water heat, laundry, fireplace, and HVAC are also being collected. Monitoring results from the WSU Energy House have been presented to the building science, IAQ and HVAC research communities at ASHRAE, AIVC, HUD/NIST, NFPA and BETEC. Data is available at <a href="http://logger.fsec.ucf.edu/cgi-bin/wg40.exe?user=lubresidence">http://logger.fsec.ucf.edu/cgi-bin/wg40.exe?user=lubresidence</a>

#### New Product and Technology Evaluation

- Through the rim crossover duct system: Three Oregon manufacturers, Marlette, Skyline and Homebuilders Northwest, adopted a crossover duct system that runs through a cut out section of the rim joist, effectively placing the entire crossover system in the heated space. A gasket on the marriage line provides a seal between sections. Correct measurements, gasket material designed not to rip off the rim.
- La Salle Duct Riser: BAIHP staff worked with BAIHP partner La Salle Air to design and produce a duct riser for manufactured homes that uses mastic instead of tape. BAIHP staff demonstrated prototype designs of the riser to Northwest manufacturers in Year 3. Three manufacturers (Redman, Fleetwood and Marlette) have adopted the new riser; several others are considering it. BAIHP staff have also worked with Fleetwood's national office to promote the use of the riser in all Fleetwood plants. During Year 5, BAIHP staff promoted the use of this technology at the annual MHI conference.
- Flexible Technologies: BAIHP partner Flexible Technologies has developed an innovative system that improves the heat and tear resistance of the duct inner liner, reduces the crimping of ductwork without the use of sheet metal elbows, and an improved system to air seal where the crossover duct penetrates the bottom board. BAIHP staff are evaluating the use of this system in the WSU Energy House, and are working with Flexible Technologies staff to promote the use of the new system to the region's manufacturers.

In addition to the above technologies, past BAIHP technology evaluation efforts include:

- Energy Conservancy: BAIHP staff worked with the Energy Conservancy to evaluate their new products for measuring air handler and exhaust fan flows.
- *Insider Heat Pump:* Monitoring of the Insider heat pump at the WSU Energy House was begun in Year 1. Measured flow rate of the indoor unit was good (850 CFM total, 425 CFM per ton), but BAIHP staff identified two performance issues: a too-frequent operation of the defrost cycle and a lower than expected airflow at the outdoor coil. Continued testing of the Insider in Year 3

indicated a 10% increase in COP due to increased airflow at the outdoor coil. At Vincent Village, the property manager indicated a high degree of satisfaction with the Insider heat pumps, with no comfort complaints.

#### Research Support

ASHRAE: During Year 5, in the capacity of chairing ASHRAE's 6.2 Technical committee, BAIHP staff directed a major effort to revise Chapter 9 of the ASHRAE Systems Handbook, "Design of Small Forced-air Heating and Cooling Systems." The revisions to the chapter, which incorporated BAIHP research, were accepted by the committee, and forwarded to ASHRAE for publication.

BAIHP staff have also participated in ASHRAE research projects, conferences, symposiums, seminars and forums, including:

- \* Authoring a paper on duct leakage, which was submitted and approved for presentation at ASHRAE summer meeting in Year 5.
- \* Making a presentation at the ASHRAE summer meeting in Year 4, "Uncontrolled Air Flow in Small Commercial Buildings."
- \* Moderating a forum on HVAC experiences in HUD code housing at ASHRAE's summer meeting in Year 3. 20 industry and building science professionals participated in the forum.
- \* Co-chairing ASHRAE's Technical Committee 6.3 Residential Forced Air Heating and Cooling Equipment, which is responsible for ASHRAE standard 152 Thermal Distribution Systems.
- \* Building America research on ductwork and HVAC systems will be included in the next version of the ASHRAE standards. Building America research will also be a part of future efforts in TC 6.3.
- NFPA-501: BAIHP continues to support the NFPA standards process. The NFPA standard is typically incorporated into the HUD code, which governs the construction of over 250,000 HUD code homes each year.
  - \* In Year 5, BAIHP staff integrated BAIHP duct leakage and cost data into proposals to the NFPA-501 committee. Based on this data, NFPA approved a new standard on duct tightness, as well as a refined duct testing protocol.
  - \* In Year 4, BAIHP staff cited Building America research and demonstration efforts in support of additional successful proposals for standards revision, including duct testing, and use of mastic in duct sealing.
- ACEEE: BAIHP staff have co-authored two papers presented at ACEEE Conferences, "Pushing the Envelope: A Case Study of Building the First Manufactured Home Using Structural Insulated Panels," and "Washington State Residential Ventilation and Indoor Air Quality Code (VIAQ) Whole House Ventilation Systems Field Research Report."
- National Institute of Standards and Technologies (NIST): BAIHP staff continues to work with NIST staff and industry representatives to evaluate ventilation and IAQ issues in HUD code homes.
  - \* BAIHP staff also worked with NIST and the Energy Conservancy to perform tests on a typical HUD code model house on the NIST campus in Gaithersburg, Maryland. Testing indicates low flow rates of the whole house ventilation system and significant duct leakage.
- National Manufactured Housing Research Alliance (MHRA): BAIHP staff continues to participate on MHRA's Energy Star committee, which is developing Quality Assurance procedures with USEPA on Energy Star manufactured homes. An article on the ZEMH appeared in the MHRA newsletter.

#### PORTABLE CLASSROOMS

During Years 1 through 4, BAIHP staff conducted a major effort to promote the adoption of energy efficient portable classrooms in the Pacific Northwest. BAIHP staff from Washington, Oregon and Idaho studied both new, energy efficient portable classrooms and a retrofitted classroom (originally built in the 1970s).

As a result of these studies and additional computer modeling, project staff developed a series of energy-efficient guidelines for portable classrooms in the Pacific Northwest. These guidelines cover the procurement, set-up and commissioning of new portable classrooms, as well as the retrofitting of existing portable classrooms.

The project final report and guidelines are available on the project website:

http://www.energy.wsu.edu/projects/building/portable\_prj.cfm

As part of a separate Building America project, former BAIHP staff are continuing to provide outreach on efficient portable classrooms, based on the BAIHP efforts.

LIST OF PEER REVIEWED PAPERS PRODUCED UNDER BAIHP

#### ACEEE

Baechler, M.; Lubliner, M; Gordon, A. "Pushing the Envelope: A Case Study of Building the First Manufactured Home Using Structural Insulated Panels" – Invited paper, presented at ACEEE Summer Study, Year 3.

Lubliner, M; Kunkle, R; Devine, J; Gordon, A. "Washington State Residential Ventilation and Indoor Air Quality Code (VIAQ) - Whole House Ventilation Systems Field Research Report" – Invited paper, presented at ACEEE Summer Study, Year 3.

#### AIVC

Lubliner, M; Gordon, A. "Ventilation in US Manufactured Housing" – Invited paper, presented at the 21<sup>st</sup> annual AIVC conference, Year 1.

Lubliner, M.; Gordon, A.; Persily, A.; Moyer, N.; Richins, W.; Blakeley, J. "Building Envelope, Duct Leakage and HVAC System Performance in HUD-Code Manufactured Homes" – Invited paper, presented at the 23<sup>rd</sup> annual AIVC conference, Year 4.

#### **American Solar Energy Society (ASES)**

Lubliner, M; Nelson, M; Parker, D. "Gossamer Wind Solar Power Ceiling Fan" – invited paper, presented at ASES conference, Year 5.

Lubliner, M.; Hadley, A.; Gordon, A. "Introducing Solar ready Manufactured Housing" – invited paper, to be presented at ASES conference, Year 6.

#### **ASHRAE**

Lubliner, M.; et. al. ASHRAE 2004 Systems and Equipment Handbook chapter 9 – Residential and Small Commercial HVAC Systems. Year 5.

Hales, D; Lubliner, M; Gordon, A. "Duct Leakage in New Washington State Residences: Findings and Conclusions" – Invited paper, presented at ASHRAE Summer Meeting, Year 5.

Lubliner, M.; Gordon, A.; Hadley, A. "Manufactured Home Performance; Comparing Zero Energy and Energy Star". Invited paper, submitted to Whole Buildings IX International Conference, to take place in Year 6.

#### **Automated Builder Magazine**

Baechler, M; Gordon, A. "Northwest Portable Classroom Study", Year 5.

Gordon, A.; Lubliner M. "Zero Energy Manufactured Home", Year 5.

#### **Manufactured Housing Research Alliance**

Lubliner. "Zero Energy Manufactured Home", Year 5.

# Appendix D

Florida H.E.R.O. Standard Technical Specifications

#### Florida H.E.R.O. Standard Technical Specifications

While it is crucial to work within the context of individual industry partner's designs, budget constraints, and the skill sets of available tradesmen, there are several areas that Florida H.E.R.O. consistently deals with on all projects. The keystone of an energy efficient home begins with a right sized mechanical system, a properly designed air distribution system, and performance testing to insure intended results. To accomplish these goals, a room-by-room ACCA Manual J calculation is performed for each home. In addition, an ACCA Manual D calculation is developed. The use of 13 SEER air conditioning equipment or better, in conjunction with a variable speed air handler is recommended. Ongoing site visits and communication of issues to the various sub-contractors help to insure that problems are minimized.

As windows account for the single greatest source of heat gain/loss, Florida H.E.R.O. encourages the use of double pane, vinyl frame low-e windows with an SHGC of 0.35 or less. As Florida has a rigorous air infiltration control requirement as part of the state Energy Code, most new homes are being built fairly "air-tight," with typical natural infiltration rates of 0.35 or less. Frame homes that use fiberglass batts for wall insulation typically have significantly higher infiltration rates than those insulated with cellulose or expandable foam.

The introduction of outside air for ventilation helps ensure better indoor air quality and when it is introduced to the return side of the plenum, results in a home operating under positive pressure with respect to the outside, ideal for Florida's hot-humid climate. This has become a standard feature in most of the sub-divisions that Florida H.E.R.O. works in. Other Florida H.E.R.O. recommended features include:

- 92+ AFUE gas furnaces
- Electronic thermostat
- Ducts in conditioned space
- Maximizing passive solar heat rejection measures
- Moisture management
- Instant or sealed combustion gas water heating
- Solar water heating
- Hot water pipe insulation
- Energy Star appliances
- Energy Star lighting
- "Air-Loc" style recessed (can) lights
- Ceiling fans
- Radiant barrier or unvented attic

The single most challenging are is the mechanical system. Builders are not adequately educated regarding system design and installation. Mechanical contractors attempt to overcome deficiencies by over-sizing equipment. Consumers pay a higher initial price for systems that often do not perform efficiently. In an attempt to improve this situation, each home that Florida H.E.R.O. works with is fully commissioned. Florida H.E.R.O. measures both total duct leakage and duct leakage "to out" as well as system operating static pressure, temperature drop across the coil, and air flow through each supply register. A pressure map of the house is generated

showing pressure differential with respect to outside of each room with interior doors closed. The ventilation air flow through the outside air intake is measured and adjusted if needed. Problems discovered during commissioning are resolved with the builder and responsible subcontractors. A completed Home Energy Rating Report is provided to the builder (Sample next page).



#### Part of the Solution... One Home at a Time

#### **Home Energy Rating Report**

Street Address		Orientatio	n
	Energy Ratir	ng	_HERS
C: N:	_R:CFM50	Indoor Temp	Outdoor Temp
CFM25-T: S: CFM-Out: S:	_ R: AVG: _ R: AVG:	Indoor RH	Outdoor Temp Outdoor RH
Mechanical Chara	cteristics: Make	SEER/AF	UE/HSPF
System 1:CU	To	ons AH	
System 2:CU	To	onsAH	
Controls: Manual	Programmable_	Zoned/#	
Outside Air: Type_		Measured Flow	
Delta T:	Static F	Measured Flow Pressure:	
<b>Pressure Characte</b>	ristics in Pa:		
House to out N	MBR BR 1	BR 2 BR 3	BR 4 Other
Water Heating Ch Window Characte	aracteristics: Type_ ristics:	Size/Input	EF
Stove: Dr	ver: Wash	er: Frig:	Freezer:
Radiant Barrier:		<u> </u>	
Special Features/Co	omments:		
Job #:	Tec	chnician:	

Florida Home Energy & Resources Organization, Inc. 15220 N.W. 5<sup>th</sup> Avenue · Newberry, FL 32669 · Phone 352.472.5661 · Fax 352.472.2291